REMEDIAL INVESTIGATION REPORT SYRACUSE CHINA LANDFILL SYRACUSE, NEW YORK

December 1995

Prepared for

Syracuse China Company
Post Office Box 4820
Syracuse, New York 13221-4820

Prepared by

Geraghty & Miller, Inc. 24 Madison Avenue Extension Albany, New York 12203 (518) 452-7826

REMEDIAL INVESTIGATION REPORT SYRACUSE CHINA LANDFILL SYRACUSE, NEW YORK

December 1, 1995

Prepared by GERAGHTY & MILLER, INC.

This Report is being requested for the purpose of determining compliance with local, state, or federal laws relating to hazardous materials that may affect or be on or about the site, and may be submitted to appropriate governmental regulatory agencies for those purposes. Geraghty & Miller, Inc. certifies that we have examined and are familiar with the information stated in this Report. To the best of our knowledge and upon our inquiry of those individuals responsible for obtaining or furnishing the information presented, the foregoing is true, accurate, and complete in accordance with accepted professional standards.

Andrew J. Barber

Senior Associate/Project Officer

CONTENTS

	<u>ī</u>	<u>Page</u>
1.0	INTRODUCTION	-1
2.0	SITE BACKGROUND	
	2.1 SITE DESCRIPTION	-1
	2.2.1 Solid Waste Characteristics	
3.0	PHYSICAL SETTING	
	3.1 GEOGRAPHY 3.2 REGIONAL GEOLOGY 3.3 SITE HYDROGEOLOGY 3.3	-1 -1
4.0	METHODOLOGY 4	-]
	4.1 MAGNETOMETER SURVEY	-1
	4.2.1 Landfill Borings	-2 -3
	4.3 SEDIMENT/SOIL SAMPLING 4.4 SURFACE WATER SAMPLING 4.5 MONITORING WELL DRILLING AND INSTALLATION 4.6 SURVEYING 4.7 GROUNDWATER SAMPLING 4.8 HORIZONTAL DIRECTION OF GROUNDWATER FLOW 4.9 HYDRAULIC CONDUCTION TRANSPORT	-3 -4 -4 -6 -6 -7
	4.10.1 Field Blanks and Trip Blanks	-8 -8
	4.11 CHEMICAL DATA VALIDATION	
5.0	RESULTS 5	
	5.1 MAGNETOMETER SURVEY 5.2 LANDFILL THICKNESS 5.3 SLUDGE BORINGS	-1 -1 -2
6.0	GROUNDWATER, SOIL, SURFACE WATER, AND SEDIMENT QUALITY DATA	- 1

CONTENTS (continued)

	6.1 GROUNDWATER QUALITY DATA
	6.1.1 Volatile Organic Compounds 6-6.1.2 Inorganic Parameters
	6.2 SOIL QUALITY DATA 6-
	6.2.1 Volatile Organic Compounds
	6.3 SURFACE WATER QUALITY DATA 6-
	6.3.1 Volatile Organic Compounds 6-6.3.2 Inorganic Parameters
	6.4 SEDIMENT/SOIL QUALITY DATA 6-
	6.4.1 Volatile Organic Compounds
7.0	RISK ASSESSMENT 7-
	7.1 BACKGROUND INFORMATION
	7.2.1 Groundwater
	7.3 EXPOSURE ASSESSMENT
	7.3.1 Sources and Receiving Media
	7.4 TOXICITY REVIEW
8.0	SUMMARY AND CONCLUSIONS
9.0	REFERENCES

TABLES

- Groundwater Elevation Data Collected January 5, 1995, Syracuse China Site, Syracuse, New York.
- 2. Summary of Volatile Organic Compounds Detected in Groundwater Samples Collected January 5, 1995, Syracuse China, Syracuse, New York.
- 3. Summary of Inorganic Parameters Detected in Groundwater Samples Collected January 5, 1995, Syracuse China, Syracuse, New York.
- 4. Summary of the Dissolved Metals Concentrations in Groundwater Samples Collected on January 5, 1995, Exceeding the New York State Department of Environmental Conservation Division of Water Technical and Operational Guidance Series (TOGS 1.1.1) Ambient Water Quality Standards and Guidance Values, Syracuse China Site, Syracuse, New York.
- 5. Summary of Volatile Organic Compounds Detected in Soil Samples, Syracuse China, Syracuse, New York.
- 6. Summary of Inorganic Parameters Detected in Soil Samples, Syracuse China, Syracuse, New York.
- 7. Summary of Semivolatile Organic Compounds Detected in Soil Samples Collected December 6, 1994, Syracuse China, Syracuse, New York.
- 8. Summary of Volatile Organic Compounds Detected in Surface-Water Samples Collected December 7, 1994, Syracuse China, Syracuse, New York.
- 9. Summary of Volatile Organic Compounds Detected in Sediment Samples, Syracuse China, Syracuse, New York.
- 10. Summary of Volatile Organic Compounds Detected in Sediment Samples, Syracuse China, Syracuse, New York.
- 11. Summary of Inorganic Parameters Detected in Sediment Samples, Syracuse China, Syracuse, New York.
- 12. Summary of Polychlorinated Biphenyl Compounds Detected in Sediment Samples Collected December 1, 1994, Syracuse China, Syracuse, New York.

TABLES - continued

- 13. Metal Concentrations in Sediment and New York State Sediment Criteria, Syracuse China Site, Syracuse, New York.
- 14. Calculated Hydraulic Conductivity Values for Monitoring Wells at the Syracuse China Site, Syracuse, New York.
- Summary of Total and Dissolved Metals Detected in Groundwater Samples Collected on August 17, 1995 at Syracuse China Landfill, Syracuse China Company, Syracuse, New York.
- 16. Summary of Total Metals and Cyanide Detected in Surface Water Samples Collected at Syracuse China Landfill, Syracuse China Company, Syracuse, New York.
- 17. Summary of Total Metals and Cyanide Detected in Sediment Samples Collected at Syracuse China Landfill, Syracuse China Company, Syracuse, New York.
- 18. Summary of the Dissolved Metals Concentrations in Groundwater Samples Collected on August 17, 1995, Exceeding the New York State Department of Environmental Conservation Division of Water Technical and Operational Guidance Series (TOGS 1.1.1) Ambient Water Quality Standards and Guidance Values, Syracuse China Site, Syracuse, New York.
- 19. Summary of the Total (Unfiltered) Metals Concentrations in Groundwater Samples Collected on January 5, 1995, Exceeding the New York State Department of Environmental Conservation Division of Water Technical and Operational Guidance Series (TOGS 1.1.1) Ambient Water Quality Standards and Guidance Values, Syracuse China Site, Syracuse, New York.
- 20. Summary of Total (Unfiltered) Metals Concentrations in Groundwater Samples Collected on August 17, 1995, Exceeding the New York State Department of Environmental Conservation Division of Water Technical and Operational Guidance Series (TOGS 1.1.1) Ambient Water Quality Standards and Guidance Values, Syracuse China Site, Syracuse, New York.

FIGURES

1. Site Location, Syracuse China Site Landfill, Syracuse China Manufacturing Company, Syracuse, New York.

FIGURES - continued

- 2. Location of Site Landfill, Syracuse China Landfill, Syracuse China Manufacturing Company, Syracuse, New York.
- 3. Plan View of Cross Section A-A' and B-B', Syracuse China Site, Syracuse China Manufacturing Company, Syracuse, New York.
- 4. Geologic Cross Sections A-A' and B-B', Syracuse China Site, Syracuse China Manufacturing Company, Syracuse, New York.
- 5. Water-Level Elevations, January 5, 1995, Syracuse China Site, Syracuse China Manufacturing Company, Syracuse, New York.
- 6. Lead Concentrations in Surface Water, Sediment/Soil, and Soil Boring Samples, Syracuse China Site, Syracuse Manufacturing Company, Syracuse, New York.
- 7. August 1995 Surface Water and Soil/Sediment Sampling Locations, Syracuse China Landfill, Syracuse China Company, Syracuse, New York.

<u>APPENDICES</u>

- A. Soil Boring and Well Construction Logs
- B. Surface-Water Sampling Logs
- C. Permeability Testing Results
- D. Groundwater Sampling Logs
- E. Hydraulic Conductivity Testing Data
- F. Data Validation
- G. Laboratory Reports
- H. Lead Model

REMEDIAL INVESTIGATION REPORT SYRACUSE CHINA LANDFILL SYRACUSE, NEW YORK

1.0 INTRODUCTION

Geraghty & Miller, Inc. was retained to conduct a focused Remedial Investigation/Feasibility Study (RI/FS) at the Syracuse China Landfill (Site) which is located on the property of Syracuse China Company (Syracuse China), in Syracuse, New York. The RI was conducted in accordance with the approved work plan (Geraghty & Miller, Inc. 1994a) generated for the site as required in the Administrative Order on Consent dated November 1, 1994.

Previous data from a preliminary hydrogeologic site assessment (O'Brien & Gere Engineers, Inc. 1990), quarterly groundwater and surface water sampling (April 1991 to December 1992), and SPDES Permit monitoring (February 1986 to September 1989) were evaluated in the RI work plan (Geraghty & Miller, Inc. 1994a). Based on that data, a focused scope of work was developed for the site to characterize the nature and extent of contamination in support of an analysis of remedial alternatives to be subsequently addressed in a feasibility study (FS).

This document provides the results of the RI, completed during November 1994 through January 1995, and August 1995, and is presented to characterize the nature and extent of impacts at the site to determine potential contaminant migration pathways, and to provide a basis for the completion of a focused FS.

2.0 SITE BACKGROUND

2.1 SITE DESCRIPTION

The Syracuse China landfill is located to the north of the Syracuse China manufacturing facility in Syracuse, Onondaga County, New York (Figure 1). The landfill occupies an area of approximately 13 acres and is bound by Conrail railroad tracks on the south side, wetlands on the north side, and undeveloped Syracuse China property on the east and west sides (Figure 2).

Current site topography is dominated by two mounds; the western half of the landfill and the eastern half of the landfill (Figure 3). The western portion of the landfill is the oldest part of the landfill and reportedly contains broken china. gypsum molds, facility wastewater treatment sludge, cement, and construction debris. The eastern portion of the landfill reportedly contains broken china, gypsum molds, wastewater treatment sludge, and refractory material.

Two primary settling ponds and two secondary settling ponds are located between the landfill mounds (Figure 3). Effluent from the facility wastewater treatment was discharged to primary Settling Ponds 1 and 2. Prior to discharge to Settling Pond 1, a flocculent was added which aided in settling out suspended solids in the wastewater stream. Periodically, the settling ponds were dredged and the bottom materials were placed in the sludge pond. The material in the sludge pond was allowed to dry prior to being placed in the landfill. There have been no dredging activities since May 1989.

In July 1990, modifications were made to the wastewater treatment pond system. Non-sanitary effluent from the facility combines in a single discharge line prior to a facility sampling point (Site 011). At Site 011 a coagulant/flocculent is added continuously to the wastewater effluent stream to accelerate the settling process. The discharge line passes under

the railroad tracks to an open ditch which flows to Settling Pond 3, then through a culvert to Settling Pond 4, and to Settling Pond 2, discharging to the permitted outfall at sampling point (Site 001) located at the north end of Settling Pond 2 (Figure 3).

Syracuse China maintains a State Pollutant Discharge Elimination System (SPDES) Permit (NY 010-0137) to discharge effluent from its manufacturing facility to Ley Creek through the outfall (Site 001) at the north end of Settling Pond 2. At the same time wastewater modifications were made in July 1990, Syracuse China incorporated process changes to capture suspended solids prior to discharge to the settling pond. Leaded materials (e.g., glaze and pigments) are recycled in a closed-loop system or are put through a pretreatment system and then discharged to the local publicly operated water treatment facility.

In 1992, Syracuse China began a program to reevaluate and improve its wastewater collection and treatment process. Syracuse China retained the services of C & H Engineers, P.C. to perform an evaluation of their current wastewater collection and treatment systems, and to assist in elimination of specific waste streams from its SPDES discharge.

Information regarding the specifics of the facility wastewater collection and treatment systems were submitted to the New York State Department of Environmental Conservation (NYSDEC) Region 7 Division of Water (Syracuse China, 1992, C & H Engineers 1992).

2.2 SITE HISTORY

Syracuse China has used the area north of the manufacturing facility as an industrial landfill since approximately 1940. The general public had access to the landfill until it was fenced, sometime in the late 1960s or early 1970s. Although undocumented, the public reportedly left some refuse materials in the landfill. In addition, contractors for the City of Syracuse, and the Towns of Salina and Dewitt disposed of road fill and materials cleared from storm sewer catch basins in the landfill (O'Brien & Gere 1990).

During late 1988, Syracuse China contacted the NYSDEC Region 7 regarding upgrading or closure of the landfill in response to revised regulations governing solid waste management (i.e.: 6 NYCRR Part 360). Subsequently, Syracuse China conducted a study of the groundwater quality around the landfill and submitted to NYSDEC a "Preliminary Hydrogeologic Site Assessment Report" (O'Brien & Gere 1990). This report detailed the results of an investigation conducted to characterize the quality of groundwater and surface water in the vicinity of the landfill and the wastewater treatment sludge disposed in the landfill. The analytical data collected as part of the assessment indicated that four wastewater treatment sludge samples, collected in the vicinity of the settling ponds, exceeded the EP Toxicity threshold for lead (5.0 milligrams per liter [mg/L]). Based on this data, the NYSDEC listed the Site on the Registry of Inactive Hazardous Waste Disposal Sites with a classification of 2.

2.2.1 Solid Waste Characteristics

The Syracuse China "Solid Waste Management Plan" (O'Brien & Gere 1991) has identified that the following materials were disposed at the on-site landfill:

Biscuit China Scrap

Biscuit China Scrap (unfinished product) is produced from the manufacturing process. It is composed of fired ceramic pieces which have not yet been decorated and/or glazed. It should be noted that since 1990, approximately 90 percent of all biscuit china scrap has been recycled off-site to be utilized as feedstock for a refractories manufacturing process.

Glost China Scrap

Glost China Scrap (finished product) is the final product of the manufacturing process. It is composed of glazed and/or decorated china which has been fired two or more times.

Gypsum Mold Scrap

Gypsum molds are comprised of plaster of paris and are used to form all the ceramic pieces. Gypsum molds are manufactured at the plant. The gypsum molds have a limited service life due to surface wear.

Refractory Scrap

The majority of the refractory scrap is composed of shelves and posts. Shelves and posts are assembled so that the china can be placed on them before it is fired through a tunnel kiln. The material used to make the shelves and posts is cordierite (magnesium aluminum silicate). Other refractory wastes include brick shapes and other castable materials which are used as girders or blocks to form the cars upon which the shelves and posts are placed for firing through the tunnel kiln. These items are made of materials similar to magnesium aluminum silicate. Refractory items have a limited service life due to thermal stress which causes them to eventually crack and/or warp.

• Wastewater Filter Cake

In August, 1990, the facility undertook the process change to redirect process water to the clay preparation department for filtration. Suspended solids from various wastewater streams at the plant are removed by a standard plate and frame filter press system and a wastewater filter cake is formed. From November 1991 to October 1992, all wastewater filter cake was sent off-site for disposal at the City of Auburn Landfill. Since October 1992, the wastewater filter cake has been sent off-site to Seneca Meadows in Waterloo, New York.

Construction and Demolition Materials

Construction and demolition materials include concrete demolition debris, paving materials from parking lot repair, and excavated materials from road repair and underground pipe maintenance at the facility.

Material Handling ^

Material Handling materials include bag and bulk non-hazardous materials such as clay, silica, feldspar, etc. (raw materials) which were unusable in the manufacturing process.

In December 1990, samples of the biscuit china scrap, glost china scrap, gypsum mold scrap, refractory scrap, and wastewater filter cake were analyzed for volatile organic compounds (VOCs), semivolatile organic compounds (SVOCs), metals, pesticides, and herbicides using the Toxicity Characteristic Leaching Procedure (TCLP) for hazardous waste characterization. The analytical results indicated that only the glost china scrap had detectable concentrations of any TCLP parameter. The glost china scrap had a lead concentration of 1.0 mg/L, which is below the maximum allowable concentration of 5.0 mg/L established for lead in 40 CFR Part 261.

Syracuse China ceased disposal of solid wastes in the landfill in September, 1994.

3.0 PHYSICAL SETTING

This section describes the physical setting (local and regional) of the Syracuse China site. Discussed below are geography, geology, and hydrogeology.

3.1 GEOGRAPHY

The site is located in the glaciated portion of the Ontario Lowlands Physiographic Province of New York State. This area is characterized by flat to gently rolling lake plain topography and is bound by Lake Ontario to the northwest, Oneida Lake to the northeast, Onondaga Lake to the southwest, and the east-west trending escarpment of the Allegheny Plateau (Todd 1983).

The site is situated in the Ley Creek drainage basin. Ley Creek is located north of the site and flows southwesterly to Onondaga Lake, which acts a regional discharge point. Ley Creek drains approximately 30 square miles of an area which is urbanized and industrialized and has large areas of man-made impermeable surfaces.

3.2 REGIONAL GEOLOGY

The bedrock underlying the region is the Silurian age Vernon shale. The Vernon shale is a horizontally interbedded red and green silty shale which was deposited in a coastal plain and shallow shelf environment (Fischer 1970). Residential wells installed in the Vernon shale reportedly yield approximately 20 gallons per minute (gpm) with some commercial well yields approaching 250 gpm (Kantrowitz 1970).

The surface geology of the region is characterized by Pleistocene age till, overlain by glacio-fluvial and glacio-lacustrine deposits. The glacial till unit consists of a dense reddish brown clay/silt matrix with a small amount of sand and gravel. Due to its dense

compact nature, the till generally exhibits low permeability. Overlying the till is a silt, clay and fine sand unit deposited in glacial Lake Iroquois during the recessional stage of Wisconsinan glaciation. The glacio-lacustrine sediments are vertically stratified with occasional lenses of fine to medium sand (Fischer 1970).

3.3 SITE HYDROGEOLOGY

Subsurface samples collected during this and previous investigations indicate that the geology at the site consists of glacio-lacustrine and till deposits. The glacio-lacustrine deposits vary in thickness from 10 to 30 feet across the Site and consist of clay, silt, fine sand, and variable amounts of gravel. The stratigraphy of these deposits is not well defined and most likely represent glacio-lacustrine sediments which have been reworked and deposited by more recent fluvial activity. The underlying till consists of a very dense reddish brown clay/silt matrix with small amounts of sand and gravel. Based on soil borings conducted during the RI, the thickness of the till in the vicinity of the landfill ranges from 5 to 15 feet (see Figure 4).

Groundwater occurs within the sandy silt unit above the till. Groundwater was also encountered in the till unit, although this unit did not yield a large volume of water during development, sampling, and hydraulic conductivity testing of monitoring well MW-4I. Bedrock groundwater was encountered in boring PMW-3I while attempting to install a monitoring well. Artesian conditions in the bedrock yielded 20 to 30 gallons per minute prior to sealing the borehole.

4.0 METHODOLOGY

In this section, the methodologies employed for completion of the RI tasks are reviewed. These methods are described in detail in the Field Sampling Plan (FSP) (Geraghty & Miller, Inc. 1994b). Deviations or changes from the FSP protocols are discussed in the appropriate sections. Laboratory analyses were performed in accordance with the NYSDEC Analytical Services Protocol (ASP) dated December 1991.

4.1 MAGNETOMETER SURVEY

A magnetometer survey was conducted across the western portion of the landfill in accordance with the protocols described in Section 4.11 of the RI work plan (Geraghty & Miller, Inc. 1994a). The survey was conducted in response to anecdotal information that drums may have been disposed of in the western portion of the landfill.

4.2 SOIL BORINGS

Eleven soil borings (SB-1 through SB-11) were completed during the soil boring program. Locations of these soil borings are identified on Figure 3. The soil borings were drilled by Parratt-Wolff, Inc., East Syracuse, New York, under the supervision of a Geraghty & Miller hydrogeologist.

The drilling was performed in accordance with Appendix A of the FSP (Geraghty & Miller, Inc. 1994b). A truck-mounted, hollow-stem auger drilling rig was used to drill the soil borings. At each boring location, a 6-inch diameter borehole was drilled. Soil samples were collected in continuous 2-foot intervals using a 2-inch (outside diameter) split-spoon sampler. Standard penetration tests (ASTM D1586) were performed throughout the entire length of each borehole. After retrieval of the split-spoon sampler, the soil sample was described and logged by the supervising hydrogeologist. Soil boring logs are provided in Appendix A.

Upon completion of the soil borings, the boreholes were backfilled with the drill cuttings and completed at grade with a cement plug. Soil boring locations were staked and labeled to allow subsequent identification.

4.2.1 Landfill Borings

Five borings (SB-1 through SB-5) were drilled into the landfill at the locations shown on Figure 3. The purpose of these borings was to characterize the fill material and determine the thickness of the landfill.

Soil samples were collected from each boring as described in Section 4.2. During drilling, the boreholes were screened for the presence of flammable concentrations of gases using a Gastech model 1214 combustible gas meter. Potentially flammable concentrations of gases were not detected (see soil boring logs in Appendix A). A split of each soil sample was retained for performance of a headspace analysis to aid in selection of samples for laboratory analysis. Headspace analyses were performed in accordance with the procedures described in Appendix A of the FSP (Geraghty & Miller, Inc. 1994b).

Based on the results of the headspace analyses and visual inspection, one soil sample was selected from each 20-foot depth interval of the borehole and submitted for laboratory analysis. The soil samples were analyzed for the Target Compound List Volatile Organic Compounds (TCL VOCs) and the Target Analyte List (TAL) inorganics. In addition, one soil sample from soil boring SB-3 was submitted for laboratory analysis of TCL semivolatile organic compounds (SVOCs) (excluding pesticides and polychlorinated biphenyls [PCBs]). Two soil samples for SVOCs analysis were originally proposed to be collected from this boring, however, the limited amount of soil separates (sand, silt, etc.) present in the samples precluded collection of a second sample.

4.2.2 Sludge Borings

Six borings (SB-6 through SB-11) were drilled at the locations shown on Figure 3. The purpose of these borings was to determine whether identifiable deposits of sludge material were present within the landfill and if so, what the thicknesses of these deposits were. The soil borings were terminated when fill material was encountered. Samples for laboratory analysis were not collected.

4.3 SEDIMENT/SOIL SAMPLING

Samples were collected on two occasions during the Remedial Investigation. Eight samples (SS-5, SS-6, SS-7, SS-8, SS-9, SS-10, SS-11, and SS-12) were collected on December 7, 1994 in accordance with Appendix C of the FSP (Geraghty & Miller, Inc. 1994b). Sampling locations are shown on Figure 6. To determine the potential impact to the wetland resulting from surface runoff from the site, an additional nine sediment samples (SED-1, SED-2, SED-3, SED-4, SED-5, SED-6, SED-2A, SED-4A and SED-6A) were collected on August 17, 1995 in response to a request from the NYSDEC dated June 5, 1995. The additional samples were collected in an effort to delineate the extent of lead impact to the wetlands between the outfall of Pond 2, and the culvert under Factory Avenue. Sampling locations for the August 1995 event are shown on Figure 7.

At each location, samples were collected from depths of 0 to 1 foot using a stainless-steel trowel. The December 1994 samples were submitted for laboratory analysis of target compound list (TCL) VOCs and target analyte list (TAL) inorganics as specified in the QAPP (Geraghty & Miller, Inc. 1994c). The August 1995 samples were submitted for analysis of TAL inorganics only.

Samples were also collected at two locations (BM-1 and BM-2) on the landfill berms in December 1994. These samples were submitted for laboratory analysis of TCL VOCs and PCBs. Sampling locations are shown on Figure 6.

4.4 SURFACE WATER SAMPLING

Surface water samples were also collected on two occasions during the RI. Seven surface water samples (SW-5, SW-6, SW-7, SW-8, SW-9, SW-10, and SW-12) were collected on December 7, 1994 in accordance with the protocols described in Appendix C of the FSP (Geraghty & Miller, Inc. 1994b). The locations of the surface water samples are identified on Figure 6. The purpose of the surface water sampling was to determine potential impacts to the wetlands adjacent to the landfill area. A surface water sample could not be collected from the sludge pond as this feature did not contain standing water at the time of sampling. Eight additional surface water samples (SW-1, SW-2, SW-3, SW-4, SW-5, SW-6, SW-2A, and SW-4A) were collected on August 17, 1995, as part of the delineation effort described previously. Sampling locations for the August 1995 event are shown on Figure 7.

Surface water samples were collected by slowly lowering a disposable glass flask into the surface water. Laboratory sample containers were filled by slowly pouring the sample from the flask into the container. The remainder of the sample was transferred into a clean glass beaker for field analysis. The temperature, turbidity, pH, and specific conductance of the sample were measured and recorded in field sampling logs (see Appendix B). The December 1994 surface water samples were submitted for laboratory analysis of TCL VOCs, TAL metals, and cyanide, and the August 1995 samples were submitted for TAL inorganics only.

4.5 MONITORING WELL DRILLING AND INSTALLATION

A total of three monitoring wells were installed during the monitoring well installation program.

Two monitoring wells (MW-6 and MW-7) were installed, bridging the water-table in the shallow glacio-lacustrine deposits, at the locations shown on Figure 3. These monitoring wells were installed to complete a groundwater monitoring network in the first water-bearing unit at the site.

One monitoring well (MW-4I) was installed in the till unit beneath the site to provide water-level information and geologic characterization of this unit. Proposed till unit monitoring wells adjacent to MW-1 and MW-3 could not be installed due to the small thickness of till encountered (less than 5 feet) at these locations. Although these wells could not be installed, soil samples were collected for geologic description and laboratory analysis. Soil samples from borings PMW-3I and MW-4I were collected for permeability testing (ASTM D5084) and laboratory analyses as specified in the QAPP (Geraghty & Miller, Inc. 1994c). Results of the permeability testing are provided in Appendix C.

The monitoring wells were drilled and installed in accordance with the protocols described in Appendix A of the FSP (Geraghty & Miller, Inc. 1994b).

Monitoring wells were drilled using the hollow-stem auger method. An 8-inch diameter borehole was advanced into the water table. Soil samples were collected in continuous 2-foot intervals using a 2-inch (outside diameter) split-spoon sampler. Standard penetration tests (ASTM D1585-74) were performed throughout the entire length of the borehole. A split of each soil sample was retained for performance of a headspace analysis to aid in selection of samples for laboratory analysis. Headspace analyses were performed in accordance with the procedures described in Appendix A of the FSP (Geraghty & Miller, Inc. 1994b). Soil samples were described and logged by the supervising hydrogeologist. Soil boring logs are presented in Appendix A. Soil samples from each borehole were analyzed for TCL VOCs and TAL inorganics.

When the desired depth was reached, a 2-inch diameter monitoring well was installed through the hollow-stem augers. Each well was constructed of a 5-foot length of 2-inch diameter, PVC well screen with 0.010-inch slot openings and 6-inch diameter, flush-joint, PVC riser pipe. As the augers were gradually removed, the annular space around the well screen was backfilled with No. I graded sand to approximately one foot above the top of the well screen. A bentonite pellet seal, approximately two feet thick, was installed above the sand pack. The remainder of the annular space was sealed with a cement/bentonite grout that was emplaced through a tremie pipe to just below ground surface. The well head was completed with a steel protective casing and locking cap. A cement surface pad was constructed around the protective casing to direct surface runoff away from the well. Well construction logs are presented at the end of Appendix A.

4.6 SURVEYING

After completion, the ground surface and monitoring well casings were surveyed to U.S. Geological Survey (USGS) vertical datum by a New York State-licensed land surveyor. The surveys were performed to an accuracy of 0.01 foot. Ground-surface and measuring-point elevation data are presented in Table 1.

4.7 GROUNDWATER SAMPLING

Three newly installed monitoring wells (MW-41, MW-6, and MW-7) and five previously existing monitoring wells (MW-1, MW-2, MW-3, MW-4, and MW-5) were sampled in January 1995 and August 1995 in accordance with the protocols described in Appendix B of the FSP (Geraghty & Miller, Inc. 1994). Laboratory analyses were performed by IEA, Inc. of Monroe, Connecticut. The August round of groundwater sampling was performed pursuant to a request from the NYSDEC in a comment letter dated June 5, 1995.

Groundwater sampling was performed by a Geraghty & Miller hydrogeologist. Prior to sampling, three to five times the volume of standing water in the well casing was evacuated using a centrifugal pump. Sampling was then conducted using a Teflon bailer. Water sampling logs are provided in Appendix D. Groundwater samples for the January 1995 round were submitted for TCL VOCs analysis and TAL inorganics analysis using NYSDEC ASP Methods. Groundwater samples for the August 1995 sampling round were submitted for TAL inorganics only.

4.8 HORIZONTAL DIRECTION OF GROUNDWATER FLOW

A summary of the water-level elevation data collected during the groundwater sampling is presented in Table 1. This elevation data was used to prepare a water-level elevation contour map for January 5, 1995 (see Figure 5).

The contour maps indicates that the direction of the horizontal component of groundwater flow in the first water-bearing unit is north towards Ley Creek. The hydraulic gradient was determined to be approximately 0.03 ft/ft.

4.9 HYDRAULIC CONDUCTIVITY TESTING

In-situ hydraulic conductivity tests were performed on Monitoring Wells MW-1, MW-2, MW-3, MW-4, MW-4I, MW-5, MW-6, and MW-7 to determine general conductivity values for the formations immediately surrounding the screened intervals of these wells. The tests were conducted in accordance with ASTM D4044.

Prior to testing each well, static water levels were measured using an electronic water level indicator. A volume of water was then "instantaneously" removed from each of the wells using a clean Teflon bailer and dedicated polypropylene rope. As the water recovered to static level within the wells, the recovery rate was recorded using an electronic water level

AQTESOLV, a Geraghty & Miller software program (based on the Bouwer and Rice method) for aquifer testing solutions. AQTESOLV plots drawdown versus time on a semi-logarithmic graph. A best fit line is then drawn through the data curve and the slope of the line is calculated. The slope of the line is equivalent to the hydraulic conductivity of the formation materials. A steep line indicated relatively high hydraulic conductivities, a flatter line indicates much lower hydraulic conductivities. Time-Drawdown graphs and calculated hydraulic conductivities are provided in Appendix E.

4.10 QUALITY ASSURANCE AND QUALITY CONTROL

Field sampling activities were conducted in accordance with the QA/QC requirements described in Section 5.3.6 of the QAPP (Geraghty & Miller, Inc. 1994c). A summary of the QA/QC requirements is presented below.

4.10.1 Field Blanks and Trip Blanks

Field blanks were analyzed to evaluate potential cross-contamination of samples by field sampling equipment. The frequency of field blank preparation was one per equipment type per day. Field blanks were prepared by pouring analyte-free water over sampling apparatus and into an appropriate sample container. Field blanks were collected for VOC analysis. Laboratory-prepared trip blanks of analyte-free water were submitted for VOC analysis with each shipment of groundwater samples.

4.10.2 <u>Duplicate Samples</u>

Duplicate samples were analyzed to evaluate the reproducibility of the groundwater sampling technique. Duplicates were collected at a frequency of one per 10 groundwater samples.

4.10.3 Matrix Spike/Matrix Spike Duplicates

Matrix spikes (MS) were analyzed to determine the effectiveness of the method for the matrix being analyzed. The matrix spike sample is fortified (spiked) with known quantities of specific compounds and subjected to the entire analytical procedure. The matrix spike duplicate (MSD) is a second aliquot of the same matrix that is spiked to determine the precision of the method. MS/MSD samples of soil and groundwater were analyzed at a frequency of one per 20 samples for each matrix sampled.

4.11 CHEMICAL DATA VALIDATION

The chemical data from the soil, sediment, surface water, and groundwater samples collected at the site were validated by a Geraghty & Miller chemist. Validation of the VOC and SVOC data was performed following the "USEPA Contract Laboratory Program, National Functional Guidelines for Organic Data Review", dated June 1991 (Draft). PCB data was validated following the "United States Environmental Protection Agency (USEPA) Region II Standard Operating Procedure (SOP)", dated January 1992. Inorganic data was validated following the "USEPA Laboratory Data Validation Functional Guidelines for Evaluating Inorganic Analyses", dated July 1988 and the NYSDEC ASP. The data validation consisted of a systematic review of the analytical results and quality control documentation to ensure the data are technically valid and defensible.

The results of the validation performed on the laboratory analytical data from the soil, sediment, groundwater, and surface water samples collected are provided in Appendix F. The quality of the data was acceptable with the appropriate qualifications described in Appendix F and summarized in Tables 2 through 20. Therefore, the TCL VOC, TCL SVOC, TAL inorganic, and PCB data can be classified as quantitative and are considered valid and acceptable, except those parameters which have been qualified as estimated. The data for the compounds that were estimated should be considered qualitative.

5.0 FIELD RESULTS

Based on the data generated during completion of the RI and observations made in the field, the results for each part of the RI are presented in the appropriate sections below.

5.1 MAGNETOMETER SURVEY

A magnetometer survey was conducted across the western portion of the landfill in November 1994. The survey was conducted in response to anecdotal information that drums may have been disposed of in this portion of the landfill. A report describing the findings of this survey was submitted to the NYSDEC in January 1995 (Geraghty & Miller, Inc. 1995a). The results indicated that ten magnetic anomalies were identified during the investigation. Two of these ten anomalies were determined to exhibit amplitude and scattering characteristics that might suggest buried drums. A work plan to conduct exploratory test pits at several of the anomalies has been submitted for NYSDEC approval (Geraghty & Miller, Inc. 1995b).

5.2 LANDFILL THICKNESS

As discussed in Section 4.2.1, five borings (SB-1 through SB-5) were drilled into the landfill at the locations shown on Figure 3 to characterize the fill material and determine the thickness of the landfill. Soil boring logs are provided in Appendix A.

Soil borings SB-1, SB-2, and SB-3 were drilled in the western portion of the landfill. Landfill thickness at these locations were 16 feet, 28 feet, and 22 feet, respectively. Fill material in these borings consisted of china scrap, gypsum molds, refractory materials, cinders, wood, and some fiberglass insulation. Soil borings SB-4 and SB-5 located in the vicinity of the settling ponds indicated fill material thicknesses of 4 feet. Fill material in these borings consisted of china scrap and small amounts of sludge.

5.3 SLUDGE BORINGS

As discussed in Section 4.2.2, six borings (SB-6 through SB-11) were drilled at the locations shown on Figure 3 to determine whether identifiable deposits of sludge were present within the landfill.

Sludge material was encountered just below the surface in borings SB-6, SB-8, SB-9, SB-10, and SB-11. The thickness of sludge material in these borings was 4-inches, 4.5 feet, 1.5 feet, 11 feet, and 5 feet, respectively. Soil boring logs are provided in Appendix A.

5.4 HYDRAULIC CONDUCTIVITY TESTING

In-situ hydraulic conductivity tests were performed on monitoring wells MW-1, MW-2, MW-3, MW-4, MW-41, MW-5, MW-6, and MW-7. The tests were performed in accordance with ASTM D4044 as discussed in Section 4.9. The resulting data was analyzed using the Bower and Rice method for partially penetrating wells to determine the hydraulic conductivity of the geologic formation adjacent to the tested well (Bouwer and Rice 1976). A graphical presentation of the data is provided in Appendix E. Calculated hydraulic conductivity values for each monitoring well are presented in Table 14. Hydraulic conductivity values for the upper sand and silt unit range from 6.27 x 10-5 feet per minute (ft/min) (MW-1) to 2.03 x 10-3 ft/min (MW-4). The average hydraulic conductivity for the upper unit is 4.60 x 10-4 ft/min (2.34 x 10-4 centimeters per second [cm/sec]). This value is within the typical range of a sandy silt (1 x 10-3 cm/sec to 1 x 10-5 cm/sec) (Freeze and Cherry 1979).

6.0 <u>GROUNDWATER</u>, SOIL, SURFACE WATER, AND SEDIMENT QUALITY DATA

The following sections summarize the validated analytical data collected during December 1994, January 1995, and August 1995 at the Syracuse China site. Copies of the original IEA, Inc. laboratory reports are provided in Appendix G.

6.1 GROUNDWATER QUALITY DATA

The January 1995 validated VOC and inorganic parameter (cyanide and dissolved and total metals) water quality data collected from each new (MW-41, MW-6, and MW-7) and existing (MW-1, MW-2, MW-3, MW-4, and MW-5) monitoring wells sampled are summarized in Tables 2 and 3, respectively. The inorganic groundwater data collected during the August 1995 sampling event is presented in Table 15.

6.1.1 Volatile Organic Compounds

The analytical results (Table 2) indicate that VOCs were not detected above the method quantitation limit (10 ug/L) in the groundwater samples collected. The method quantitation limit is the minimum concentration of a compound that can be confidently measured and reported by the laboratory when using the analytical method specified. The actual quantitation limits reported by the laboratory for the groundwater samples (10 ug/L) were higher than the ideal target quantitation limits listed in the QAPP (1 to 3 ug/L). The ideal limits are not always achievable because quantitation limits are dependent upon the sample matrix, the USEPA method used for analysis, and the laboratory confidence in the measurement.

6.1.2 Inorganic Parameters, January and August 1995

The work plan specified the collection of both dissolved (filtered) and total (unfiltered) samples for metals analysis if the turbidity measured at the time of groundwater sampling exceeded 50 nephelometric turbidity units (NTUs). Each groundwater sample collected had a turbidity greater than 50 NTUs; therefore, both dissolved and total samples were collected from each location sampled.

Historically, filtration of groundwater samples has served several important functions in groundwater quality monitoring. Filtration helps to minimize the problems of data variability that commonly results from variable levels of suspended sediment in individual samples. In addition, filtration of samples makes it possible to determine actual dissolved concentrations of metals in groundwater that have not been artificially elevated as a result of sample preservation (acidification), which can potentially leach metals from the surfaces of suspended sediments and/or colloids. Since the groundwater samples collected had turbidities greater than 50 NTUs, the total (unfiltered) analyses are probably not representative of the dissolved concentrations of metals in groundwater at the site. However, the following discussions include the results of both the dissolved (filtered) and total (unfiltered) analyses.

Table 3 presents both total (non-filtered) and dissolved (filtered) inorganic analytical results from January 1995. The (filtered) analytical metals results indicate that five metals (iron, magnesium, manganese, sodium, and zinc) were detected in excess of their respective NYSDEC Division of Water Technical and Operational Guidance Series (TOGS) 1.1.1-Ambient Water Quality Standards and Guidance Values. A summary of the dissolved (filtered) metals concentrations detected exceeding the standards and guidance values are presented in Table 4.

The following ranges of dissolved concentrations were detected above the NYSDEC TOGS 1.1.1 Standards and Guidance Values for the January 1995 sampling event: iron,

0.72 mg/L in MW-5 to 106 mg/L in MW-4I; magnesium, 44.3 mg/L in MW-3 to 165 mg/L in MW-4I; manganese, 0.46 mg/L in MW-6 to 4.38 mg/L in MW-4I; sodium, 21.2 mg/L in MW-1 to 69.5 mg/L in MW-5. Zinc was detected at a concentration of 3.78 mg/L in MW-4I. The water quality standards and guidance values for iron, magnesium, manganese, sodium, and zinc are secondary drinking water standards and are based on aesthetic criteria (taste, color, etc.) rather than toxicity.

As can be expected (i.e. from suspended sediment), the total (unfiltered) metals samples contained higher concentrations for the five metals listed above, plus detection of four additional metals; arsenic, copper, lead, and vanadium (Table 19). Arsenic ranged between 0.027 mg/L in wells MW-4 and MW-41, to 0.062 mg/L in MW-3 (duplicate); copper was detected at a concentration of 0.356 mg/L in MW-6; lead ranged between 0.051 mg/L in MW-4, to 0.254 mg/L in MW-3 (duplicate); and vanadium ranged between 0.074 mg/L in MW-3 and MW-41, to 0.24 mg/L in MW-2.

The lead data reported for the January 1995 sampling of MW-41 were deemed unusable upon data validation. Subsequently, a second round of groundwater sampling was conducted on August 17, 1995, exclusively for inorganic parameters. Both filtered and non-filtered samples were collected in August 1995, and analytical results from both analyses are presented in Table 15.

The August 1995 dissolved (filtered) analytical metals results (Table 15) indicate that four metals (iron, magnesium, manganese, and sodium) were detected in excess of their respective NYSDEC TOGS 1.1.1-Ambient Water Quality Standards and Guidance Values. A summary of the dissolved (filtered) metals concentrations detected exceeding the standards and guidance values is presented in Table 18.

The following ranges of dissolved concentrations were detected above the NYSDEC TOGS 1.1.1 Standards and Guidance Values: iron, 0.59 mg/L in MW-4 to 5.2 mg/L in MW-4I; magnesium, 35.6 mg/L in MW-1 to 54.0 mg/L in MW-2; manganese, 0.472 mg/L

in MW-3 to 2.02 mg/L in MW-4; and sodium, 26.8 mg/L in MW-41 to 62.5 mg/L in MW-5. Zinc was not detected above the standard in the August 1995 dissolved samples.

Table 20 presents a summary of total metals concentrations exceeding the TOGS 1.1.1 standards for the August 1995 sampling event. Nine metals were reported above the standards as follows: arsenic, ranging from 0.0276 mg/L in MW-6 to 0.107 in MW-3; copper, ranging from 0.038 mg/L in MW-7I to 0.276 mg/L in MW-6; iron, ranging from 1.89 mg/L in MW-5 to 126 mg/l in MW-3; lead, ranging from 0.0565 mg/L in REP-1 to 0.292 mg/L in MW-7; magnesium, ranging from 41.5 mg/L in MW-1 to 207 mg/L in MW-3; manganese, ranging from 1.45 mg/L in MW-7 to 5.72 mg/L in MW-4; sodium, ranging from 21.7 mg/L in REP-1 to 68 mg/L in MW-5; vanadium, ranging from 0.016 mg/L in MW-2 to 0.0967 mg/L in MW-4I; and zinc, ranging from 0.053 mg/L in MW-4 to 0.419 mg/L in MW-4I.

Cyanide was not detected above the method quantitation limit (10 ug/L) in the groundwater samples collected in January 1995, and therefore was not analyzed in August 1995.

Groundwater in Onondaga County is typically hard water which exhibits naturally occurring high concentrations of iron, manganese, sodium, and magnesium due to the geologic composition of the shale bedrock and glacial overburden material. The concentrations of metallic salts reported above are within the expected ranges for Onondaga County (Kantrowitz 1970).

6.2 SOIL QUALITY DATA

The validated VOC, inorganics, and semivolatile organic compound (SVOC) data from the nine soil samples collected at the site are summarized in Tables 5, 6, and 7, respectively.

6.2.1 Volatile Organic Compounds

The analytical results (Table 5) indicate that VOCs were not detected above the method quantitation limit with the exception of acetone, which was detected in soil samples MW-41 (38 ug/kg), MW-6 (39 ug/kg), MW-7 (150 ug/kg), SB-4 (20 ug/kg), and SB-5 (22 ug/kg) at the concentration indicated. Acetone is a common laboratory solvent and its detection is most likely due to laboratory contamination.

6.2.2 <u>Inorganic Parameters</u>

The metals results (Table 6) indicate that aluminum, calcium, chromium, iron, lead, magnesium, manganese, and zinc were detected in each of the nine samples analyzed; arsenic (five samples), copper (four samples), nickel (four samples), vanadium (two samples), and barium (one sample) were also detected in selected soil samples. The highest concentrations of arsenic (5.9 mg/kg), barium (57.2 mg/kg), iron (16,800 mg/kg), nickel (16.2 mg/kg), and vanadium (15.2 mg/kg) were detected in soil sample SB-1; the highest concentrations of aluminum (6,690 mg/kg), calcium (55,600 mg/kg), lead (426 mg/kg), and zinc (36.7 mg/kg) were detected in soil sample SB-3; the highest concentrations of chromium (11.1 mg/kg) and manganese (458 mg/kg) were detected in soil sample MW-6; and the highest concentration of magnesium (17,200 mg/kg) was detected in soil sample PMW-31.

The metals concentrations were compared to recommended soil cleanup objectives and eastern United States background concentrations for metals, obtained from the January 1994 NYSDEC Technical Assistance Guidance Memorandum (HWR-94-4046) for comparative purposes. The results indicated that the concentrations of metals detected are within the range of eastern United States background concentrations, with the exception of lead, which was detected at a concentration of 426 mg/kg in sample SB-3. It should be noted that background concentrations for lead vary widely. Average concentrations in undeveloped, rural areas may range from 4 to 61 mg/kg. However, average concentrations in metropolitan and suburban areas or near highways are higher and typically range from 200

to 500 mg/kg (NYSDEC 1994). The lead concentrations detected in each soil sample collected are illustrated on Figure 6.

Cyanide was not detected above the method quantitation limit in the soil samples collected.

6.2.3 Semivolatile Organic Compounds

The analytical results from sample PSB-3 (Table 7) indicate that SVOCs were not detected above the method quantitation limit.

6.3 SURFACE WATER QUALITY DATA

The December 7, 1994 validated VOC and inorganic parameter (cyanide and total metals) water quality data collected from each surface water sampling location (SW-5, SW-6, SW-7, SW-8, SW-9, SW-10, and SW-12) are summarized in Tables 8 and 9, respectively.

6.3.1 Volatile Organic Compounds

The analytical results (Table 8) indicate that VOCs were not detected above the method quantitation limit with the exception of chloroform, which was detected at a concentration of 10 ug/L in surface water sample SW-10. Chloroform is commonly found in treated water supplies and does not likely reflect site contamination.

6.3.2 Inorganic Parameters, December 1994 and August 1995

The total metals results (Table 9) indicate that two metals, lead and zinc, were detected in excess of NYSDEC surface-water standards during the December 1994 sampling event. The surface-water standard for lead was calculated to be 6.4 ug/L based on a water hardness of 200 mg/L (as calculated from the average calcium and magnesium concentrations detected in SW-5, SW-6, and SW-12). Lead was detected above the 6.4 ug/L standard at

6.4.2 <u>Inorganic Parameters</u>

The December 1994 metals results (Table 11) indicate that eight metals (arsenic, chromium, copper, lead, mercury, nickel, silver, and zinc) were detected above NYSDEC (1993b) sediment criteria (see Table 13) contained in the NYSDEC Division of Fish and Wildlife Technical Guidance for Screening Contaminated Sediments.

A second round of samples were collected on August 17, 1995, pursuant to the Department request comment letter dated June 5, 1995. The results of this sampling event are presented in Table 17. Analytical results from the second sampling event indicate that the same eight metals listed above were detected above NYSDEC sediment criteria.

Note, however, that sampling results in excess of the sediment criteria must be viewed against the intent of the guidance document. The technical guidance document for screening contaminated sediment provides the NYSDEC with a constructive and objective test to identify sediments that may or may not be of particular concern. Although sampling results may show guidance criteria exceedence, the development of cleanup levels is based upon a balancing of environmental, technical, economic, and legal considerations (NYSDEC 1993b). These considerations will be discussed in the upcoming Feasibility Study. A more complete discussion of the sediment/soil metal results is contained in Section 7.2.4 of the risk assessment data review.

6.4.3 Polychlorinated Biphenyls

The analytical results (Table 12) indicate that PCBs were not detected above the method quantitation limit in the two sediment samples collected (BM-1 and BM-2).

7.0 RISK ASSESSMENT

A risk assessment addresses potential human health and ecological risks associated with chemical constituents present in environmental media at a site under current and expected future site conditions and provides a consistent approach for determining if remedial action is warranted at a site. Thus, the risk assessment is a key component of the RI. Its primary objective is to identify constituents of potential concern (COCs), describe potential current and future exposure pathways and receptors, and evaluate potential risks. This section focuses on human health risks. Ecological resources were addressed in the Fish and Wildlife Habitat Impact Analysis report (Terrestrial Environmental Specialists, 1995).

A risk assessment may be qualitative, quantitative, or a combination of both. This risk assessment primarily will provide a qualitative assessment consistent with the United States Environmental Protection Agency's (USEPA) Superfund Accelerated Cleanup Model (SACM) and guidance on streamlining the RI/FS process at landfill sites (USEPA, 1990). This approach encourages the use of presumptive remedies such as capping and containment for landfill sites. Therefore, in most cases, a detailed quantitative risk assessment is not required.

7.1 BACKGROUND INFORMATION

The site background and physical setting information was presented in Sections 2.0 and 3.0 of this report and is used to identify potential exposure pathways and receptors in Section 7.3.3. The 13-acre landfill was used to dispose various debris associated with product manufacturing. Settling ponds within the landfill were used to contain effluent from the wastewater treatment facility (Figure 3). Sludges from these ponds were subsequently disposed in the landfill. Wastewater ultimately is discharged to the wetland area on the northeast side of the landfill under a SPDES permit.

Surface water from the wetland area discharges through a culvert which passes under Factory Avenue to the north and discharges to Ley Creek. Ley Creek is a Class B fresh surface water. The best usages for Class B waters are primary and secondary contact recreation and fishing and should be maintained to support fish propagation and survival (NYSDEC 1991). Primary contact recreation includes swimming, water skiing, and diving; secondary contact recreation includes fishing and boating.

7.2 DATA REVIEW

The primary purpose of this section is to identify COCs. COCs will be selected for each medium based on the frequency of detection, range of concentrations, comparison to background concentrations, general toxicity, comparison to regulatory standards or criteria, and the expected source(s). For example, constituents which occur infrequently at low concentrations are unlikely to pose a health concern. Background concentrations are particularly important for naturally occurring constituents such as metals. When site-specific background data are unavailable, regional data are useful for determining if concentrations are within the expected range. It is also important to determine if the presence of a particular constituent is likely related to a release from the site.

The RI/FS Work Plan (Geraghty & Miller, 1994) for the Syracuse China site reviewed the soil, surface-water, and groundwater data collected between 1986 and 1992. Based on these data, the primary environmental issues addressed by the RI included lead in subsurface soils and sludges, VOCs in surface water, surface water transport of impacted sediments/soils, and characterization of hydrogeologic conditions. This risk assessment focuses on the data collected during the RI as reported in Section 6.0. These data are reviewed briefly below.

7.2.1 Groundwater

On January 5, 1995, eight monitoring wells were sampled and analyzed for VOCs, cyanide, and total and dissolved metals (Tables 2 and 3). Results were comparable to previous data reviewed (Geraghty & Miller 1994a). Low concentrations (below 10 ug/L) of xylenes and ethylbenzene were detected in the groundwater from MW-3, MW-6, and MW-7; these concentrations were below the method quantitation limit. In addition, these concentrations are below the New York State (NYS) Class GA groundwater standard for these constituents and do not pose a threat to public health. Pursuant to a request from the NYSDEC dated June 5, 1995, the wells were resampled on August 17, 1995 and analyzed exclusively for inorganic parameters.

Metals (total and dissolved) were detected in the groundwater samples collected in January 1995 (Table 3) and August 1995 (Table 15). Dissolved metals were reported in fewer samples and indicate that most of the metals in groundwater are bound to aquifer material. MW-4I contained the highest concentrations of dissolved metals with the exception January 1995 data from MW-4I are somewhat suspect because dissolved concentrations were consistently higher than total concentrations (Table 3). However, the August 1995 inorganic data shows the reverse trend in which the dissolved concentrations are significantly lower than the total metal results, which would be expected since most of the suspended solids are removed during filtering. MW-6, which is hydraulically upgradient from the site, contained the highest total concentrations for eight metals. MW-1, which is also upgradient from the site, contained the highest dissolved lead concentration (0.023) mg/L) which is below NYSDEC groundwater standards. The NYSDEC Class GA groundwater standard for lead is .025 mg/L. MW-7 contained the highest total lead concentration (0.292 mg/L) reported for both sampling rounds. Although several metals (total concentrations) exceeded groundwater standards, dissolved concentrations were generally below standards and indicate minimal impacts to groundwater at the site. Therefore, COCs were not selected.

7.2.2 Soil

In November 1994, nine subsurface soil samples (4 to 30 ft below land surface) were collected from the site and analyzed for VOCs and metals (Tables 5 and 6). One subsurface soil sample (PSB-3) was analyzed for SVOCs (Table 7). Four VOCs (acetone, 2-butanone, trichloroethene, and toluene) were detected at estimated concentrations ranging from 2 to 150 ug/kg. Toluene also was detected in one field blank. These low concentrations do not pose a health risk based on a comparison to NYSDEC (1994) recommended soil cleanup objectives. Metal concentrations were within the reported background concentrations for US soils (USGS, 1984) with the exception of lead detected at 426 mg/kg in SB-3. Average lead concentrations in urban/suburban areas or near highways typically range from 200 to 500 mg/kg (NYSDEC 1994). Based on these data, lead was identified as the only COC in soil.

7.2.3 Surface Water

In December 1994, seven surface-water samples were collected and analyzed for VOCs, cyanide, and total metals (Tables 8 and 9). Four of these samples were from the settling ponds and three were from the wetland area north of the site (Figure 3). Chloroform (8 to 10 ug/L) and bromodichloromethane (BDCM) (2 ug/L) were the only VOCs detected. The detected concentrations were below the method quantitation limit. Chloroform and BDCM are commonly found in treated water supplies and do not likely reflect site contamination.

Metal concentrations in surface water were not highly variable and were generally below NYSDEC surface-water standards with the exception of lead and zinc. Zinc was consistently detected above the surface-water standard of .03 mg/L, based on protection of aquatic life. The surface-water standard for lead was calculated to be .0064 mg/L based on a water hardness of approximately 200 mg/L (as calculated from on the average concentrations of calcium and magnesium in SW-5, SW-6, and SW-12). Surface-water standards also are based on the acid soluble form of the metal and are not necessarily

directly comparable to total concentrations. Sample SW-8 from Pond 2 contained the highest concentrations of zinc. SW-12, near the SPDES outfall contained the highest concentration of lead. Therefore, lead and zinc were identified as COCs in surface water.

7.2.4 Sediment/Soil

In December 1994, eight samples were collected from the settling ponds and wetland area and analyzed for VOCs and metals (Tables 10 and 11). Two samples from the landfill berms were analyzed for VOCs and PCBs (Tables 10 and 12). Five VOCs were detected in two or three samples at estimated concentrations ranging from 2 to 36 μ g/kg. These concentrations were below the method quantitation limit. Metals, with the exception of lead, were within the background ranges for soil (USGS 1984); however, eight metals exceeded NYSDEC (1993b) guidance for determining sediment criteria (Table 13). In August 1995, nine samples were collected from the wetland area and analyzed for metals only; lead concentrations in the nine samples exceeded the NYSDEC (1993b) sediment criteria guidance. It should be noted that background concentrations for lead vary widely. Average concentrations in undeveloped, rural areas may range from 4 to 61 mg/kg. However, average concentrations in metropolitan and suburban areas or near highways are higher and typically range from 200 to 500 mg/kg (NYSDEC 1994). Sediment criteria include a lowest effect level (LEL) and severe effect level (SEL). Concentrations above the LEL are considered evidence of moderate impacts. If both criteria are exceeded, the sediment is considered severely impacted; however, site-specific conditions may affect the bioavailability and toxicity of metals in sediment. Based on these criteria, lead and zinc have the greatest potential for impacts and were selected as COCs. Copper and silver were not selected as COCs based on the limited number of samples above both the LEL and the SEL. These metals were not detected at concentrations above groundwater and surface-water standards and were not associated with site use.

The lowest lead and zinc concentrations reported for both sampling events were 51.9 mg/kg and 57.1 mg/kg, respectively at SS-6 on the far end of the wetland area. Maximum

concentrations for lead and zinc were 6,010 mg/kg at SED-6A (August 1995) near the SPDES outfall and 796 mg/kg at SED-2 (August 1995) near Factory Avenue, respectively. Concentrations in sediments/soils did not correlate well with the surface-water concentrations. For example, although SS-6 had the lowest lead concentration in sediment/soil SW-6 had one of the higher lead concentrations in surface water. Conversely, SED-6A (August 1995) had the highest lead concentration in sediment/soil but nearby SW-5 (December 1994) had one of the lowest lead concentrations in surface water.

It is noted that measurements for sediment criteria must be viewed against the intent of the guidance document. The technical guidance document for screening contaminated sediment provides the NYSDEC with a constructive and objective test to identify sediments they may or may not be of particular concern. Although COCs have been identified for risk analysis purposes, the development of cleanup levels is based upon a balancing of environmental, technical, economic, and legal considerations (NYSDEC 1993b). These considerations will be discussed in the upcoming Feasibility Study.

7.3 EXPOSURE ASSESSMENT

This section presents an overview of the potential exposure pathways associated with the site. Consistent with the presumptive remedy for the site, and the screening risk assessment approach, a complete quantitative exposure assessment was unnecessary. Rather, this section presents a brief discussion of the sources and receiving media, fate and transport of the COCs, identifies the potential exposure points and receptors, and provides a qualitative discussion of exposure.

7.3.1 Sources and Receiving Media

Section 2.2.1 identified seven solid waste types which were disposed at the Syracuse China site. These included biscuit china scrap, glost china scrap, gypsum mold scrap, refractory scrap, wastewater filter cake, construction and demolition materials, and material

concentrations for lead and zinc were 6,010 mg/kg at SED-6A (August 1995) near the SPDES outfall and 796 mg/kg at SED-2 (August 1995) near Factory Avenue, respectively. Concentrations in sediments/soils did not correlate well with the surface-water concentrations. For example, although SS-6 had the lowest lead concentration in sediment/soil SW-6 had one of the higher lead concentrations in surface water. Conversely, SED-6A (August 1995) had the highest lead concentration in sediment/soil but nearby SW-5 (December 1994) had one of the lowest lead concentrations in surface water.

It is noted that measurements for sediment criteria must be viewed against the intent of the guidance document. The technical guidance document for screening contaminated sediment provides the NYSDEC with a constructive and objective test to identify sediments they may or may not be of particular concern. Although COCs have been identified for risk analysis purposes, the development of cleanup levels is based upon a balancing of environmental, technical, economic, and legal considerations (NYSDEC 1993b). These considerations will be discussed in the upcoming Feasibility Study.

7.3 EXPOSURE ASSESSMENT

This section presents an overview of the potential exposure pathways associated with the site. Consistent with the presumptive remedy for the site, and the screening risk assessment approach, a complete quantitative exposure assessment was unnecessary. Rather, this section presents a brief discussion of the sources and receiving media, fate and transport of the COCs, identifies the potential exposure points and receptors, and provides a qualitative discussion of exposure.

7.3.1 Sources and Receiving Media

Section 2.2.1 identified seven solid waste types which were disposed at the Syracuse China site. These included biscuit china scrap, glost china scrap, gypsum mold scrap, refractory scrap, wastewater filter cake, construction and demolition materials, and material

handling materials (Geraghty & Miller, 1994). The available analytical data for the site indicate that lead is the primary COC with respect to human health. Zinc was identified as a COC based on potential impacts to aquatic life. VOCs and several other metals were detected in site samples but the frequency and range of concentrations did not indicate that the site was likely an appreciable source of these constituents or that they posed a health concern.

Historically, potential sources of lead and zinc may have included pigment and glazing operations and wastewater treatment sludge. This risk assessment focuses on human health issues because ecological issues have been discussed in a separate report (Terrestrial Environmental Specialists, 1995). Therefore, the following sections emphasize potential impacts of lead on human health. The Risk Characterization section of this chapter will provide a brief review of ecological issues based on a comparison of site data to the water quality and sediment standards and criteria.

Lead was detected in each of the media sampled; however, soil samples from the site generally did not contain elevated concentrations of lead compared to reported background concentrations. Groundwater and surface-water samples generally contained total lead concentrations above NYS groundwater and surface-water standards. Dissolved concentrations of lead in groundwater did not exceed NYS Class GA groundwater standards. Sediments/soils in the wastewater settling ponds and in the wetlands near the SPDES outfall contained the highest concentrations of lead. Lead was identified as a COC in soil, surface-water, and sediments/soils.

7.3.2 Environmental Fate and Transport of Lead

Lead is a naturally occurring element and is ubiquitous in the environment. Significant anthropogenic sources of lead release to the environment include past gasoline and oil combustion; lead, copper, and zinc smelters; and lead products manufacture. Gasoline combustion once accounted for about 90 percent of lead emissions to the atmosphere; however, due to the elimination of leaded gasoline, municipal waste incineration and primary lead smelting are the current major sources of lead emissions. As a result of past and current lead emissions, most food, water, and air contain detectable concentrations of lead and serve as sources of background exposure to the general population.

Atmospheric fallout is the primary source of lead found in most surface waters. Lead tends to form insoluble compounds with the naturally occurring anions (hydroxide, sulfide, carbonate, sulfate, etc.) in surface water (USEPA, 1979). Lead and its compounds also form complexes with organic matter and are adsorbed by sediments. Precipitation out of solution is an important process which removes lead from surface water. Solubility is dependent on the form of lead, pH, temperature, and salt content; however, natural compounds of lead have low solubility and generally are not highly mobile in the environment.

Inorganic lead generally is adsorbed and retained in the soil. Some lead compounds may leach from soils with low organic matter, clay content, and pH. Erosion and overland flow would be the primary transport mechanism for inorganic lead in soil. Uptake by plants is limited. Studies have indicated that only 0.003 to 0.005 percent of total lead in soil is available for plant uptake and only about 3 percent of the lead taken up by the roots is translocated to other plant tissues (Kabata-Pendias and Pendias, 1992).

Lead generally does not bioconcentrate in fish tissue. Shellfish and algae may bioconcentrate lead; however, concentrations in organisms higher in the food chain are usually lower. Thus lead is not biomagnified in the food chain. A reported median bioconcentration factor for fish is 42 liters per kilogram (L/kg) (Agency for Toxic Substances and Disease Registry [ATSDR], 1991).

7.3.3 Exposure Pathways and Receptors

Under current conditions, on-site exposures do not appear to pose a significant risk. The shallow groundwater is not used near the site and public access is controlled by a fence and the wetlands. The landfill is no longer active and site workers do not normally visit this area. Workers involved in monitoring the SPDES outfall could be exposed to constituents in soil, surface water, or sediments. Such exposures would likely be limited to dermal contact; although, some incidental ingestion could occur. Overall, exposure would be limited by the short duration of contact with affected media and the generally low concentrations detected in soil and surface water. Although lead concentrations in sediment near the SPDES outfall are high, routine contact with the sediment by a site worker is not expected. Furthermore, exposure to lead would be low because lead is not absorbed readily across the skin or from the adult gastrointestinal tract (GI) (Goyer, 1991).

Off-site exposure is expected to be low under current or future conditions. Lead was detected in surface water in the wetland area. Surface water from the wetland ultimately discharges to Ley Creek; however, minimal sediment transport from the wetland to Ley Creek is expected. Wetlands function as natural filters for sediment/soil. The December 1994 lead concentration near the culvert at SS-6 (51.9 mg/kg) on the northern side of the landfill was about two orders of magnitude lower than that reported at SS-5 (5,110 mg/kg) near the SPDES outfall (Table 11) which indicates that lead concentrations observed in the December 1994 sampling event decreased rapidly with distance from the SPDES outfall. The lead results form the August 1995 sampling event, while not as dramatic as those from December 1994, show a similar trend of higher lead concentrations observed near the SPDES outfall (4000 mg/kg at SED-6, and 6010 mg/kg at SED-6A) than those observed on the opposite side of the wetlands (2020 mg/kg at SED-2A) and near the culvert (3380 mg/kg at SED-1).

The wetland area and Ley Creek is not expected to be routinely used for recreation or fishing. Although Ley Creek is a Class B stream, the Fish and Wildlife Habitat Impact

Analysis Report (Terrestrial Environmental Specialists, 1995) indicated that this area is of limited value as a habitat to fish and wildlife and did not support a substantial fish population to the highly industrialized/suburbanized nature of the Ley Creek watershed and the limited access to the area by the general public. Nevertheless, individuals fishing, wading, or swimming in Ley Creek, or the wetland area, could be exposed to lead. Therefore, a quantitative assessment of lead exposure is provided in the risk characterization section using USEPAs Integrated Exposure Uptake Biokinetic (IEUBK) model version 0.99d for lead (USEPA, 1994).

This model was designed to predict blood lead levels in young children following exposure to lead. USEPA has not developed an IEUBK model for adults. Although the IEUBK model is typically used to address lead in surface soil, it also may be used to evaluate other potential sources of exposure including: air, household dust, water, diet, and paint. It is not expected that children will routinely be exposed to surface-water at the site. The IEUBK model was used to provide a conservative estimate of potential risks.

The presumptive remedy for the site is capping the western portion of the site. The site is no longer used for the disposal of solid wastes, significantly reducing the amount of lead and other solids released to the environment. Capping will eliminate potential exposure pathways.

7.4 TOXICITY REVIEW

Inorganic lead is absorbed from the lungs and GI tract but very little is absorbed through the skin. GI absorption of lead varies according to the form of lead, age, and nutritional status. In young children, GI absorption may be as high as 40 to 50 percent with 30 percent retention. In adults, only 5 to 15 percent is absorbed and only about 5 percent is retained (Goyer, 1991).

Once absorbed, lead distributes to bone, soft tissues (primarily kidney, brain, and lung), and blood. More than 90 percent of the total body burden of lead is stored in bone with a half-life of more than 25 years. Lead in soft tissues has a half-life of about 40 days and generally does not accumulate with age. Almost all blood lead (PbB) is associated with the red blood cells with a half life of about 36 days (ATSDR, 1991).

Lead exposure has been associated with numerous toxic effects on various organs/systems including the nervous system, kidneys, blood, reproduction and development, and GI tract. Infants and young children are more susceptible to lead exposure than adults. Exposure is typically monitored by measuring PbB. Ten ug of lead per deciliter (ug/dL) of blood is the current benchmark level recommended by the USEPA and the Centers for Disease Control (CDC) for determining excess lead exposure in children.

7.5 RISK CHARACTERIZATION

Current and future exposures to on-site workers and off-site residents are not expected to pose an unacceptable risk based on the limited exposure potential and extent of release. Concentrations of VOCs detected in groundwater, soil, surface water, and sediment were below NYS standards and guidance values. Although several metals (total concentrations) exceeded groundwater standards, dissolved concentrations (with the exception of Monitor Well MW-4I) were below the standards. Metal concentrations in subsurface soil were generally within typical background ranges.

A direct comparison of total metal concentrations detected in surface water with surface water standards is not appropriate because the standards for most metals are based on the acid soluble form; however, based on total concentrations, lead and zinc are a potential concern.

To assess potential impacts of lead released to surface-water, the IEUBK model was used. As mentioned previously, this model was designed to predict PbB levels in young

children aged 6 months to 6 years. Exposure pathways identified for surface water and sediment included recreational use (fishing and swimming) of Ley Creek and possibly the wetland area. Young children would not reasonably be expected to swim in the creek or the wetland; however, they may ingest fish caught from this area. As a conservative measure, it was assumed that 5 to 10 percent of the total meat and fish diet of young children living near the site was from fish caught from Ley Creek. Furthermore, it was assumed that the average lead concentration in Ley Creek would be equal to the average lead concentration detected in wetland surface-water samples (samples SW-5, SW-6, and SW-12). This is a conservative assumption because lead concentrations in Ley Creek are expected to be lower than those detected in the wetlands due to sorption, attenuation, and dilution. The fish tissue concentration of lead (1.4 mg/kg) was calculated by multiplying the average surface water concentration (0.034 mg/L) by the bioconcentration factor of 42 L/kg (ATSDR 1991).

The IEUBK model was run using default exposure assumptions for exposure to lead in air, soil and dust, and water. Default concentrations are as follows: 0.1 micrograms per cubic meter (μ g/m³) for air, 200 mg/kg for soil, 150 mg/kg for household dust, and .004 mg/L for water. The dietary intake of lead was modified by including exposure from fish ingestion as 5 percent and 10 percent of the total meat diet.

The predicted geometric PbB levels in a population of young children were 4.7 ug/dL and 5.5 ug/dL based on a 5 percent and 10 percent diet fraction of fish caught from Ley Creek. At the five percent diet fraction, 95 percent of the exposed population would be expected to have a PbB concentration less than 10 ug/dL. Even at the 10 percent diet fraction level, 90 percent of the exposed population would have a predicted PbB less than 10 ug/dL. The output from the lead model is provided in Appendix H. This assessment indicates that even in the unlikely event that fish caught from Ley Creek and the wetland area near the site were an important local food source, risk from lead exposure would be below the USEPA and the CDC benchmark level.

8.0 SUMMARY AND CONCLUSIONS

Geraghty & Miller, Inc. conducted a focused RI at the Syracuse China site during the period November 1994 through October 1995. The purpose of the RI was to characterize the nature and extent of impacts at the site and to determine potential contaminant migration pathways, and to provide a basis for the completion of a focused FS.

The results of the RI have demonstrated the following:

- The geology at the site is comprised of glaciolacustrine deposits (silt, sand, clay, and gravel). A dense reddish brown till occurs between the glaciolacustrine deposits and the underlying bedrock.
- Groundwater flow in the first water-bearing unit (sandy silt) is north towards
 Ley Creek.
- Fill material on the western portion of the site consists of china scrap, gypsum molds, refractory materials, cinders, wood, and some fiberglass insulation. Fill material in this area ranges in thickness from 16 to 28 feet.
- Flammable concentration of gases were not detected during drilling operations conducted in fill materials at the site. However, an explosive gas survey will be conducted per Part 360 requirements as part of the Remedial Design, for the capping of the landfill.
- Sludge materials were encountered at several locations on the site. Thicknesses ranged from 4-inches to 11 feet.
- VOCs were not detected above quantitation limits in groundwater samples collected.

- Analytical results for metals in groundwater indicate that exceedences of the TOGS 1.1.1 standards were observed in both filtered and unfiltered metals samples. Analytical results reported for unfiltered samples were generally higher than results reported for the filtered samples, and more exceedences occurred from the unfiltered samples. The exceedenced noted for the unfiltered samples are due to the digestion of the suspended sediments in the unfiltered samples.
- VOCs were not detected above quantitation limits in soil samples with the exception of acetone, a common laboratory artifact.
- Metal concentrations detected in soil samples are within the range of eastern United States background concentrations with the exception of lead in one sample collected from boring SB-3. However, the lead concentration in this sample is within the typical range of lead concentrations in urban and suburban areas.
- VOCs were not detected above quantitation limits in surface-water samples.
- Lead was detected above NYSDEC surface-water standards in unfiltered metals samples SW-5 through SW-12. Zinc was detected above NYSDEC surface-water standards in unfiltered metals sample SW-8.
- VOCs were not detected above the quantitation limit for samples with the exception of acetone, a common laboratory artifact.
- PCBs were not detected above quantitation limits in samples collected from the landfill berms.
- Because of the detection of metals in the samples collected in the wetland

area, particularly lead, above NYSDEC sediment guidance levels, NYSDEC has determined that remediation of the wetlands will be required. Additionally, the RI and historic sampling results indicate that the ponds will also require remediation. It is expected that sampling will be conducted during the initial FS stage to better define the areal extent to which the wetlands will require remediation.

- The Report on the Exploratory Test Pits is complete and final. Results from the test pit excavations can be found in the Test Pit Report dated July, 1995.
- The results of the risk assessment indicate that overall, the exposure potential at the site appears limited to lead in sediments. Under current conditions, this exposure is limited to workers entering the site to conduct SPDES sampling. Exposures reasonably expected to occur under these conditions do not appear to pose an unacceptable risk.
- The results of the fish and wildlife habitat impact analysis report indicate that the site and its vicinity are of limited value as habitat to fish and wildlife due to the highly industrialized/urbanized nature of the area.

9.0 REFERENCES

- Agency for Toxic Substances and Disease Registry, 1991. Draft Toxicological Profile for Lead. Prepared by Clement International Corporation for U.S. Department of Health and Human Services.
- Bouwer, H. and R.C. Rice, 1976. A Slug Test Method for Determining Hydraulic Conductivity of Unconfined Aquifers with Completely or Partially Penetrating Wells. Water Resources Research, Vol. 12, No. 3, pp. 423-428.
- C & H Engineers, Inc. 1992. Letter to P.E. Harvard, Syracuse China Corporation, May 14, 1992.
- Fischer, D.W. and L.V. Richard. 1970. Geologic Map of New York State, Finger Lakes Sheet. New York State Museum and Science Service Map and Chart. Series No. 15.
- Freeze, R.A. and J.A. Cherry, 1979. Groundwater. Prentice-Hall. Inc., Englewood Cliffs, New Jersey, 604 pp.
- Geraghty & Miller, Inc. 1994a. Remedial Investigation and Feasibility Study Work Plan, Syracuse China Landfill, Syracuse China Manufacturing Company, Syracuse, New York. November 1994.
- Geraghty & Miller, Inc. 1994b. Field Sampling Plan Remedial Investigation/Feasibility Study Work Plan, Syracuse China Landfill, Syracuse, New York. November 1994.
- Geraghty & Miller, Inc. 1994c. Quality Assurance Project Plan Remedial Investigation/Feasibility Study Work Plan, Syracuse China Landfill, Syracuse, New York. Revision 1. November 1994.
- Geraghty & Miller, Inc. 1995a. Report on the Geophysical Survey, Syracuse China Landfill, Syracuse, New York. January 1995.
- Geraghty & Miller, Inc. 1995b. Exploratory Test Pit Work Plan, Syracuse China Landfill, Syracuse Manufacturing Company, Syracuse, New York. March 1995.
- Gerstman, Marc S. 1994. Letter to Thomas F. Walsh, Esq. dated September 6, 1994.
- Goyer, R.A., 1991. Toxic Effects of Metals. In: Casarett and Doulls Toxicology, the Basic Science of Poisons, 4th Edition. M.O. Amdur, J. Doull, and C.D. Klaassen, eds. Pergamon Press, pp. 623-680.

- Kabata-Pendias, A. and H. Pendias, 1992. Trace Elements in Soils and Plants, 2nd Edition. CRC Press, Boca Raton, Florida, 365 pp.
- Kantrowitz, I.H. 1970. Ground Water Resources in the Eastern Oswego River Basin, New York. State of New York Conservation Department Water Resources Commission, Basic Planning Report ORB-2.
- New York State Department of Environmental Conservation (NYSDEC), 1991. Water Quality Regulations Surface Water and Groundwater Classifications and Standards. New York State Codes, Rules, and Regulations, Title 6, Chapter X, Parts 700-705.
- NYSDEC, 1993a. Ambient Water Quality Standards and Guidance Values
- NYSDEC, 1993b. Technical Guidance for Screening Contaminated Sediments, Department of Environmental Conservation.
- NYSDEC, 1994. Determination of Soil Cleanup Objectives and Cleanup Levels. Technical and Administrative Guidance Memorandum HWR-94-4046, January 24, 1994.
- O'Brien & Gere Engineers, Inc. 1991. Solid Waste Management Plan. Syracuse China Corporation, Syracuse, New York.
- O'Brien & Gere Engineers, Inc. 1990. Preliminary Hydrogeologic Assessment. Syracuse China Corporation, Syracuse, New York, April 1990.
- Syracuse China Corporation. 1992. Letter to Leland Flocke, New York State Department of Environmental Conservation, May 14, 1992.
- Terrestrial Environmental Specialists, Inc., 1995. Fish and Wildlife Habitat Impact Analysis of the Syracuse China Landfill Site, Syracuse New York.
- Todd, D.K. (compiler), 1983. Ground Water Resources of the United States, Premier Press, Berkeley, California.
- United States Geological Survey (USGS), 1984. Element Concentrations in Soils and Other Surficial Materials of the Conterminous United States. USGS Professional Paper 1270. United States Government Printing Office, Washington, D.C.
- United States Environmental Protection Agency (USEPA), 1979. Water Related Environmental Fate of 129 Priority Pollutants. Office of Water Planning and Standards, Washington, D.C., USEPA 440/4-79-029.



- United States Environmental Protection Agency (USEPA), 1990. Streamlining the RI/FS for CERCLA Municipal Landfill Sites. Office of Solid Waste and Emergency Response, Washington, D.C. Directive: 9355.3-11FS.
- United States Environmental Protection Agency (USEPA), 1994. Guidance Manual for the Integrated Exposure Update Biokinetic Model for Lead in Children. Publication Number 9285.7-15-1. EPA/540/R-93/081. Office of Solid Waste and Engineering Response, Washington, D.C.

Table 1. Groundwater Elevation Data Collected January 5, 1995, Syracuse China Site, Syracuse, New York.

Monitoring Well	Measuring Point Elevation		Depth to Water**	0년 6억	March.	Groundwater Elevation*	OLT EN	Pie.
MW-1	413.78		19,29	rc.21	25.12	394.49	F14.71	392,14
MW-2	394.84		4.46	2.4%	1.50	390.38	3.912,3.5	3-0.79
MW-3	387.83		3.69	26.0	3.81	384.14	386	5 54.02
MW-4	385.59		5.15	2.66	$A , \leq \mathbb{Z}$.	380.44	382,93	395.50
MW-4I	385.40	1.3	5.33	.62	2.84 =	380.07	392,03	562,5Z
MW-5	390.40	2.3	4.15 2-	-77	ē.88 >	386.25	307.63	30€.02
MW-6	410.70	Š.	4.67		0. 4, 1	410.03	240, 8	
MW-7	394.67		7.51 3	€.3 V	4.61 -	387.16	2-11, 14,	390,60

7 - 41

Elevations in feet above mean sea level.

^{**} Feet below measuring point.

Table 2. Summary of Volatile Organic Compounds Detected in Groundwater Samples Collected January 5, 1995, Syracuse China Site, Syracuse, New York.

Parameter	Quantitation Limit	Sample ID:	MW-1	MW-2	MW-3	(Dup) MW-3	MW-4
Chloromethane					1711-3	141 44 -2	101 00 -4
Bromomethane	10						
	10						
Vinyl chloride Chloroethane	10					**	
	10		J	J	J	J	J
Methylene chloride	10		••				
Acetone	10						
Carbon disulfide	10				**		••
1,1-Dichloroethene	10			••		***	
1,1-Dichloroethane	10					••	••
1,2-Dichloroethene (total)	10						
Chloroform	10						
1,2-Dichloroethane	10						
2-Butanone	10		**	••			
1,1,1-Trichloroethane	10						
Carbon tetrachloride	10			••			
	10					••	
Bromodichloromethane	10						
1,2-Dichloropropane	10						
cis-1,3-Dichloropropene	10						
Trichloroethene	10		**				
Dibromochloromethane	10						
1,1,2-Trichloroethane	10						
Benzene	10			••			
trans-1,3-Dichloropropene							
Bromoform	10			••			
4-Methyl-2-pentanone	10			••			
1 modifi 2 petitatione	10						
2-Hexanone	10						
Tetrachloroethene	10						
1,1,2,2-Tetrachloroethane	10						
Toluene	10						
Chlorobenzene	10						
Ethylhanzana	10						
Ethylbenzene	10						
Styrene Vulene (total)	10						
Xylene (total)	10		-		0.7 J		

Concentrations reported in micrograms per liter (ug/L).

⁻ Analyte not detected.

J Estimated value.

Table 2. Summary of Volatile Organic Compounds Detected in Groundwater Samples Collected January 5, 1995, Syracuse China Site, Syracuse, New York.

Donomatas	Quantitation							
Parameter	Limit	Sample ID:	MW-41	MW-5	MW-6	MW-7	FB010595	TB010595
Chloromethane	10							
Bromomethane	10			~ ~	-			••
Vinyl chloride	10						••	
Chloroethane	10		J	J	J	J	J]
Methylene chloride	10			**				
Acetone	10		••			-		
Carbon disulfide	10						••	
1,1-Dichloroethene	10					••	••	•••
1,1-Dichloroethane	10							
1,2-Dichloroethene (total)	10							
Chloroform	10				***	••	1 J	
1,2-Dichloroethane	10						1.7	
2-Butanone	10							
1,1,1-Trichloroethane	10					••		
Carbon tetrachloride	10							
Bromodichloromethane	10				••	••		
1,2-Dichloropropane	10							*-
cis-1,3-Dichloropropene	10							
Trichloroethene	10							
Dibromochloromethane	10				_			
1,1,2-Trichloroethane	10							
Benzene	10						••	
trans-1,3-Dichloropropene	10		*=		_			
Bromoform	10				_		••	
4-Methyl-2-pentanone	10							
2-Hexanone	10					3		
Tetrachloroethene	10							
1,1,2,2-Tetrachloroethane	10							
Toluene	10							
Chlorobenzene	10							
Ethylbenzene	10					0.5.		
Styrene	10					0.5 J		
Xylene (total)	10				 1 J	9 J	-	

Concentrations reported in micrograms per liter (ug/L).

⁻⁻ Analyte not detected.

J Estimated value.

Table 3. Summary of Inorganic Parameters Detected in Groundwater Samples Collected January 5, 1995, Syracuse China Site, Syracuse, New York.

		. MW-1	W-1	X	MW-2	M	MW-3	MW-3 (MW-3 (Duplicate)	×	MW-4
Parameter	Sample ID: Dissolved	Dissolved	Total	Dissolved	Total	Dissolved	Total	Dissolved	Total	Dissolved	Total
Aluminum		0.012 U	13.7 J	0.032 BU	15.5 J	0.017 BU	41.5J	0.017 U	51.4 J	0.035 U	55.8 J
Antimony	•	0.038 U	0.038 U	0.038 U	0.038 U	0.038 U	0.038 U	0.038 U	0.048 B	0.038 U	0.038 U
Arsenic	Ŭ	0.001 U	0.005 B	0.001 U	0.007 BJ	0.002 B	0.049	0.002 B	0.062	0.001 U	0.027
Barium	•	0.034 B	0.147 B	0.021 B	0.097 B	0.03B	0.33	0.031 B	0.389	0.018 B	0.512
Beryllium	0	0.001 U	0.001 U	0.001 U	0.001 U						
Cadmium	0	0.002 U	0.002 U	0.002 U	0.002 U	0.002 U	0.002 U	0.002 U	0.002 B	0.002 U	0.005 B
Calcium		123	198	460	200	172	658	178	630	403	610
Chromium	0	0.002 U	0.016	0.002 U	0.015	0.002 U	0.05	0.002 U	0.059	0.002 U	0.062
Cobalt	0	0.003 U	0.012 B	0.003 U	0.008 B	0.003 U	0.039 B	0.003 U	0.043 B	0.003 U	0.048 B
Copper	0	0.006 BJ	0.053	0.007 BJ	0.042	0.003 BJ	0.086	0.002 U	0.097	0.002 U	0.135
Iron	0	0.015 U	20.7	0.018 U	20.9 J	1.12	70.2 J	1.16	81.4	0.032 U	95.8 J
Lead		0.023	0.016	0.001 U	0.011 U	0.002 U	0.176	0.003 U	0.254	0.003 U	0.051 J
Magnesium		33.4	74.6	51.4	82.2	44.3	206	45.7	661	23.7	99.4
Manganese	0	0.003 U	0.77	0.65	2.28	0.549	3.46	0.567	3.39	1.59	38.2
Mercury	0.	0.0002 U	0.0002 U	0.0002 U	0.0002 U						
Nickel	0	0.008 U	0.024 B	0.008 U	0.021 B	0.008 U	0.075	0.008 U	0.083	0.008 U	0.106
Potassium	0	0.517 U	4.81 B	0.517 U	5.9	0.517 U	7.98	0.517 U	8.9	2.92 B	9.37
Selenium	0	0.002 B	0.002 B	0.001 U	0.002 UJ	0.001 U	0.001 UJ	0.001 U	0.001 UJ	0.001 U	0.002 UJ
Silver	0	0.003 U	0.003 U	0.003 U	0.003 U						
Sodium		21.2	22.3	4	1,020	29.3	32.6	30.4	32.8	36	38.9
Thallium	0	0.001 U	0.001 UJ	0.001 UJ	0.001 UJ	0.001 UJ	0.001 BJ	0.001 UJ	0.001 UJ	0.001 UJ	0.001 UJ
Vanadium	0.	0.006 U	0.01 B	0.006 U	0.24 B	0.006 U	0.074	0.006 U	0.075	0.006 U	0.088
Zinc	0.	0.048 U	0.07 U	0.03 U	0.067 U	0.039 U	0.198	0.04 U	0.218	0.052	0.292
Cyanide		NR R	0.01 U	N R	0.01 U	N R	0.01 U	X R	0.01 U	N R	0.01 U

Concentrations reported in milligrams per liter (mg/L).

U Analyte analyzed for but not detected.

B Analyte result between instrument detection limit (IDL) and contract required detection limit (CRDL).

J Estimated value.

R Unusable result.

NR Not required.



Table 3. Summary of Inorganic Parameters Detected in Groundwater Samples Collected January 5, 1995, Syracuse China Site, Syracuse, New York.

		M	MW-4I	M	MW-5	M	MW-6	M	MW-7	FB01	FB010595
Parameter	Sample ID: Dissolved	Dissolved	Total								
Aluminum		62.1	51.8 J	0.360	6.76 J	6.27	95.9 J	0.012 U	9.58 J	0.58 B	0.049 B
Antimony	•	0.059 B	0.038 U	0.038 U	0.038 U	0.038 U	0.052 B	0.038 U	0.038 U	0.038 U	0.038 U
Arsenic		0.037	0.027 S	0.003 B	0.023	0.001 B	0.043	0.001 B	0.011	0.001 U	0.001 U
Barium	-	0.576 J	0.470 J	0.039 B	0.079 B	0.109 B	0.765	0.026 B	0.09 B	0.008 U	0.008 U
Beryllium	•	0.001 U	0.001 U								
Cadmium	J	0.004 B	0.002 U	0.004 B	0.003 B	0.002 U	0.003 B	0.002 U	0.002 U	0.002 U	0.002 U
Calcium		741	720	8.98	125	107	287	231	303	0.856 B	0.709 B
Chromium	•	0.144 J	0.096	0.002 U	0.012	0.005 B	0.132	0.002 U	0.016	0.002 U	0.002 U
Cobalt		0.054	0.042 B	0.003 U	0.005 B	0.007 B	0.092	0.005 B	0.011 B	0.003 U	0.003 U
Copper		0.197 J	0.155 J	0.008 BJ	0.009 BJ	0.035	0.356	0.002 U	0.02 BJ	0.002 U	0.002 U
Iron		106 J	85.2 J	0.716	9.89 J	0.008 U	139 J	2.34	17.2 J	0.128 J	0.114 J
Lead		×	~	0.003 U	0.007 U	0.007 U	990.0	0.004 U	0.216	0.001 U	0.001 U
Magnesium		165	157	28.9	45.8	29.2	221	14.3	37.2	0.163 B	0.014 B
Manganese		4.38 J	3.92 J	0.021 U	0.215	0.464	4.21	1.97	2.53	0.007 B	0.014B
Mercury	0	0.0002 B	0.0002 U	0.0002 U	0.0002 U						
Nickel	•	0.132 J	0.108 J	0.008 U	0.008 U	0.015 B	0.193	0.008 U	0.016 B	0.008 U	0.008 U
Potassium		28.5	28	8.7	9.01	4.06 B	25.6	4.08 B	6.53	0.517 U	0.517 U
Selenium	Õ		0.003 UJ	0.001 U	0.001 U	0.001 U	0.005 U	0.001 U	0.001 U	0.001 U	0.001 U
Silver	0	0.003 U	0.003 U								
Sodium		25.9	25.5	69.5	71.6	12.1	4	32.9	33.6	0.052 B	0.153 B
Thallium	0.	0.001 UJ	0.001 UJ	0.001 UJ	0.001 UJ	0.001 U	0.001 BJ	0.001 UJ	0.001 UJ	0.001 U	0.001 U
Vanadium	0	0.094 J	0.074 J	0.007 B	0.006 U	0.007 B	0.109	0.006 U	0.012 B	0.006 U	0.006 U
Zinc	0	0.377 J	0.294 J	~	~	0.114	0.461	0.037 U	0.052 U	0.009 B	0.017 B
Cyanide		N. R	0.01 U	NR	0.01 U	N. R	0.01 U	N. R.	0.01 U	Z Z	0.01 U

Concentrations reported in milligrams per liter (mg/L).

U Analyte analyzed for but not detected.

B Analyte result between instrument detection limit (IDL) and contract required detection limit (CRDL).

J Estimated value.

R Unusable result.

GERAGHTY & MILLER, INC.



	TOGS 1.1.1 Standard	MW-1 1/5/95	MW-2 1/5/95	MW-3 1/5/95	MW-4 1/5/95	MW-41 1/5/95	MW-5 1/5/95	MW-6 1/5/95	MW-7 1/5/95
Iron	0.3	·	ı	1.12	ı	106 J	0.72	7.44	2.34
Magnesium	35*	1	51.4	44.3	1	165	1	1	ı
Manganese	0.3	:	0.65	0.55	1.6	f †*†	1	9.46	1.97
Sodium	20	21.2	7	29.3	36	25.9	69.5	1	32.9
Zinc	0.3	1	ı	ŀ	1	3.78 J	ŧ	:	t

Concentrations reported in milligrams per liter (mg/L).

Guidance Value.

Standard not exceeded.

Estimated value.

Table 5. Summary of Volatile Organic Compounds Detected in Soil Samples, Syracuse China Site, Syracuse, New York

Parameter	Method Detection Limit	Sample ID: Sample Depth: Sample Date: Dilution Factor:	26-30 ft.	MW-41 14-18 ft. 11/30-94 1.08	MW-6 4-6 ft. 11/28/94 1.12	MW-7 14-16 ft. 12/1/94 1.20	SB-1 16-18 ft. 12/6/94 1.19	SB-2 14-16 ft. 12/6/94 1.14
Chloromethane	10						J	J
Bromomethane	10				†# ••		_	
Vinyl chloride	10							
Chloroethane	10					••		••
Methylene chloride	10						2 J	
Acetone	10		J	38 J	39 J	150 J	36 UJ	24 UJ
Carbon disulfide	10		••				••	
1,1-Dichloroethene	10			••				
1,1-Dichloroethane	10				••			
1,2-Dichloroethene (total)	10							
Chloroform	10			••			••	
1,2-Dichloroethane	10							••
2-Butanone	10		J	J	J	5 J	3 J	J
1,1,1-Trichloroethane	10							
Carbon tetrachloride	10				••			
Bromodichloromethane	10			••				
1,2-Dichloropropane	10							
cis-1,3-Dichloropropene	10			••				
Trichloroethene	10		2 J	••	••			
Dibromochloromethane	10			•-				
1,1,2-Trichloroethane	10			••				
Benzene	10			•-				
trans-1,3-Dichloropropene	10				••			
Bromoform	10				••		-	
4-Methyl-2-pentanone	10		J	J	J	J	J	J
2-Hexanone	10		J	_ J	J	J	J	J
Tetrachloroethene	10						_	
1,1,2,2-Tetrachloroethane	10		••				J	J
Toluene	10		21	3 J	2 J	4 J	12U	11U
Chlorobenzene	10							
Ethylbenzene	10							
Styrene	10							
Xylene (total)	10							



⁻⁻ Analyte not detected at or above the quantitation limit (method detection limit x dilution factor).

J Estimated value.

B Analyte also detected in associated blank.

U The compound was analyzed for but not detected at the specified detection limit, where the detection limit is raised above the contract required detection limit.

Table 5. Summary of Volatile Organic Compounds Detected in Soil Samples, Syracuse China Site, Syracuse, New York

						•	-,,,	1012
Parameter	Method Detection Limit	Sample ID: Sample Depth: Sample Date: Dilution Factor:	SB-3 22-24 ft. 12/6/94 1.43	SB-4 6-8 ft. 12/2/94 1.23	SB-5 2-4 ft. 12/2/94 1.28	Field Blank 11/28/94 1.00	Field Blank 11/30/94 1.00	Field Blank 12/1/94 1.00
Chloromethane	10		ij J		••	J	J	
Bromomethane	10		••		••		,	**
Vinyl chloride	10		••	••		J	J	
Chloroethane	10		••	••			,	
Methylene chloride	10		2 J					
Acetone	10	*	31 UJ	20 J	22 J	J	J	J
Carbon disulfide	10		••					
1,1-Dichloroethene	10				••		••	
1,1-Dichloroethane	10			••	••		••	••
1,2-Dichloroethene (total)	10		••					••
Chloroform	10						••	
1,2-Dichloroethane	10							••
2-Butanone	10		J	J	J	J	J	
1,1,1-Trichloroethane	10							
Carbon tetrachloride	10				••		••	
Bromodichloromethane	10							••
1,2-Dichloropropane	10						**	
cis-1,3-Dichloropropene	10		••					
Trichloroethene	10							
Dibromochloromethane	10		••			••		
1,1,2-Trichloroethane	10			••			••	
Benzene	10						••	
trans-1,3-Dichloropropene	10					••		
Bromoform	10		•-					
4-Methyl-2-pentanone	10		J	J	J	J	J	
2-Hexanone	10		J	J	J	J	J	
Tetrachloroethene	10							
1,1,2,2-Tetrachloroethane	10		J					
Toluene	10		14U	3 J	2 J			••
Chlorobenzene	10							
Ethylbenzene	10		•-					
Styrene	10							
Xylene (total)	10							

⁻ Analyte not detected at or above the quantitation limit (method detection limit x dilution factor).

J Estimated value.

B Analyte also detected in associated blank.

U The compound was analyzed for but not detected at the specified detection limit, where the detection limit is raised above the contract required detection limit.

Table 5. Summary of Volatile Organic Compounds Detected in Soil Samples, Syracuse China Site, Syracuse, New York.

Parameter	Method Detection Limit	Sample ID: Sample Date: Dilution Factor:	Field Blank 12/2/94 1.00	Field Blank 12/6/94 1.00	Trip Blank 11/30/94 1.00	Trip Blank 12/1/94 1.00	Trip Blank 12/2/94 1.00	Trip Blank 12/6/94 1.00
Chloromethane	10			••			J	
Bromomethane	10		••			••	,	
Vinyl chloride	10		••	••	••	••		
Chloroethane	10				••			
Methylene chloride	10			•-			••	
Acetone	10		J		J	J	J	J
Carbon disulfide	10		••			••		,
1,1-Dichloroethene	10				••		••	••
1,1-Dichloroethane	10		••		••		••	••
1,2-Dichloroethene (total)	10						••	
Chloroform	10						••	••
1,2-Dichloroethane	10							•-
2-Butanone	10				••		••	
1,1,1-Trichloroethane	10					••		•-
Carbon tetrachloride	10							
Bromodichloromethane	10				••			
1,2-Dichloropropane	10							
cis-1,3-Dichloropropene	10					••		
Trichloroethene	10		••					
Dibromochloromethane	10							
1,1,2-Trichloroethane	10					••		
Benzene	10							
trans-1,3-Dichloropropen	10				••			
Bromoform	10							
4-Methyl-2-pentanone	10						J	
2-Hexanone	10						•	
Tetrachloroethene	10				_			
1,1,2,2-Tetrachloroethane	10							
Toluene	10			2 J				
Chlorobenzene	10							
Ethylbenzene	10							
Styrene	10				••			
Xylene (total)	10							

⁻ Analyte not detected at or above the quantitation limit (method detection limit x dilution factor).

J Estimated value.

B Analyte also detected in associated blank.

U The compound was analyzed for but not detected at the specified detection limit, where the detection limit is raised above the contract required detection limit.

	Sample ID:	PMW-3I	MW-4I	WW-6	MW-7	SB-1	SB-2	SB-3	SB-4	SB-5
Darameter	Sample Depth:	26-30 ft.	14-18 ft.	4-10 ft.	14-16 ft.	16-18 ft.	14-16 ft.	4-6; 22-24 ft.	6-8 ft.	2-8 ft.
	Samuel Care.					1007	1000	100	14/7/21	17/7/
Aluminum		6,630	3,940	4,600	2,270	7,320	2,600	069'9	3,920	5,360
Antimony		8.2 UJ	8.2 UJ	8.4 UJ	8.9 UJ	9.1 UJ	8.6 UJ	9.4 UJ	9.5 UJ	9.5 UJ
Arsenic		2.0 B	2.7	3.6	1.6 B	5.9	3.3	1.0 BJ	4.4	2.4 B
Barium		33.3 B	29.3 B	37.7 B	6.4 B	57.2	32.8 B	19.7 B	38.2 B	22.8 B
Beryllium		0.27 B	0.21 U	0.26 B	0.23 U	0.29 B	0.26 B	0.25 U	0.25 U	0.25 U
Cadmium		0.43 U	0.43 U	0.44 U	0.47 U	0.48 U	0.45 U	0.50 U	0.50 U	0.50 U
Calcium		41,700 J	52,300 J	50,800 J	48.300 J	42,200 J	52,000 J	55,600 J	37,800 J	27,300 J
Chromium		10.1 J	5.2 J	11.1 J	4.7 J	10.5 J	6.2 J	3.3 J	6.2 J	6.6 J
Cobalt		4.6 B	3.9 B	5.9 B	3.7 B	7.2 B	5.4 B	2.9 B	3.3 B	4.4 B
Copper		8.4 U	7.7 U	15.4	6.91	16.4	16.4	7.9 U	10.2 U	10.6 U
Iron		12,100	8,740	11,700	6,350	16.800	10,500	3.410	8,340	9,150
Lead		2.3 J	3.5 J	3.2 J	4.4 J	6.8 J	11.6 J	426	3.8 J	29.9 J
Magnesium		17,200 J	14,000 J	13,600 J	16,700 J	14,800 J	21,500 J	4,910 J	15,100 J	9,250 J
Manganese		332 J	307 J	458 J	244 J	422 J	362 J	106 J	296 J	257 J
Mercury		0.11 U	0.10 U	0.10 U	0.094 U	0.11 U	0.094 U	0.12 U	0.12 U	0.11.0
Nickel		13.8	7.0 B	11.6	8.2 B	16.2	9.01	4.7 B	5.6 B	10 B
Potassium		986 B	813 B	589 B	311 B	846 B	681 B	868 B	402 B	630 B
Selenium		0.22 U	0.21 U	0.22 U	0.23 U	1.2 U	0.23 U	0.25 U	0.25 U	0.25 U
Silver		0.64 U	0.64 U	0.67 U	0.70 U	0.72 U	0.68 U	0.74 U	0.75 U	0.75 U
Sodium		80.1 B	73.0 B	76.8 B	75.3 B	117 B	114 B	1,140 B	102 B	161 B
Thallium		0.22 U	0.21 U	0.38 B	0.23 U	0.24 U	0.23 U	0.25 U	0.25 U	0.25 U
Vanadium		9.5 B	6.9 B	7.1 B	5.0 B	15.2	11.2 B	7.0 B	8.6 B	14.3
Zinc		22.7	28.4	24.0	14.7	30.3	25.6	36.7	20.0	22.6
Cyanide		0.54 UJ	0.51 UJ	0.53 UJ	0.57 UJ	0.58 UJ	0.55 UJ	0.62 UJ	0.60 UJ	0.60 UJ

Concentrations reported in milligrams per kilogram (mg/kg).

U Analyte analyzed for but not detected.

B Analyte result between instrument detection limit (IDL) and contract required detection limit (CRDL).

J Estimated value.

Table 7. Summary of Semivolatile Organic Compounds Detected in Soil Samples Collected December 6, 1994, Syracuse China Site, Syracuse, New York.

	Quantitation	Sample ID: Sample Depth:	SB-3 22-24 ft.
Parameter	Limit	Dilution Factor:	1.00
Phenol	470		
bis(2-Chloroethyl)ether	470		
2-Chlorophenol	470		••
1,3-Dichlorobenzene	470		
1,4-Dichlorobenzene	470		••
1,2-Dichlorobenzene	470		••
2-Methylphenol	470		
2,2'-oxybis(1-Chloropropane)	470		
4-Methylphenol	470		
N-Nitroso-di-n-propylamine	470		**
Hexachloroethane	470		
Nitrobenzene	470		
Isophorone	470		
2-Nitrophenol	470		
2,4-Dimethylphenol	470		
bis(2-Chloroethoxy)methane	470		
2,4-Dichlorophenol	470		
1,2,4-Trichlorobenzene	470		
Naphthalene	470		
4-Chloroaniline	470		
Hexachlorobutadiene	470		
4-Chloro-3-methylphenol	470		
2-Methylnaphthalene	470		
Hexachlorocyclopentadiene	470		J
2,4,6-Trichlorophenol	470		
2,4,5-Trichlorophenol	1,100		
2-Chloronaphthalene	470		
2-Nitroaniline	1,100		
Dimethylphthalate	470		×
Acenaphthylene	470		
2,6-Dinitrotoluene	470		
3-Nitroaniline	1,100		J

⁻ Analyte not detected at or above the quantitation limit.

J Estimated value.

Table 7. Summary of Semivolatile Organic Compounds Detected in Soil Samples Collected December 6, 1994, Syracuse China Site, Syracuse, New York.

Parameter	Quantitation Limit	Sample ID: Sample Depth: Dilution Factor:	SB-3 22-24 ft. 1.00
Acenaphthene	470		
2,4-Dinitrophenol	1,100		
4-Nitrophenol	1,100		
Dibenzofuran	470		
2,4-Ditnitrotoluene	470		
Diethylphthalate	470		
4-Chlorophenyl-phenylether	470		
Fluorene	470		
4-Nitroaniline	1,100]
4,6-Dinitro-2-methylphenol	1,100		
N-Nitrosodiphenylamine	470		
4-Bromophenyl-phenylether	470		
Hexachlorobenzene	470		
Pentachlorophenol	1,100		••
Phenanthrene	470	ii a	
Anthracene	470		
Carbazole	470		J
Di-n-butylphthalate	470		
Fluoranthene	470		11 J
Pyrene	470		11 J
Butylbenzylphthalate	470		
3,3'-Dichlorobenzidine	470		
Benzo(a)anthracene	470		
Chrysene	470		
bis(2-Ethylhexyl)phthalate	470		
Di-n-octylphthalate	470		
Benzo(b)fluoranthene	470		
Benzo(k)fluoranthene	470		ie
Benzo(a)pyrene	470		
Indeno(1,2,3-cd)pyrene	470		
Dibenz(a,h)anthracene	470		
Benzo(g,h,i)perylene	470		

⁻⁻ Analyte not detected at or above the quantitation limit.

J Estimated value.

Table 8. Summary of Volatile Organic Compounds Detected in Surface-Water Samples Collected December 7, 1994, Syracuse China Site, Syracuse, New York.

Parameter	Quantitation Limit	Cample ID	SW-5	CWA	CW =	007.0	(Dup
i arameter	LIIII	Sample ID:	2M-2	SW-6	SW-7	SW-8	SW-8
Chloromethane	10		••				
Bromomethane	10				••		
Vinyl chloride	10						1.7
Chloroethane	10						
Methylene chloride	10						
Acetone	10					**	
Carbon disulfide	10			••			
1,1-Dichloroethene	10				••		
1,1-Dichloroethane	10				••		
1,2-Dichloroethene (total)	10						
Chloroform	10		8 J			8 J	9 J
1,2-Dichloroethane	10						
2-Butanone	10						
1,1,1-Trichloroethane	10						
Carbon tetrachloride	10			••	••		
Bromodichloromethane	10					2 Ј	2 J
1,2-Dichloropropane	10						
cis-1,3-Dichloropropene	10				'		
Trichloroethene	10						
Dibromochloromethane	10						
1,1,2-Trichloroethane	10			••	••		
Benzene	10						
trans-1,3-Dichloropropene	10						
Bromoform	10						
4-Methyl-2-pentanone	10						
2-Hexanone	10					••	
Tetrachloroethene	10						
1,1,2,2-Tetrachloroethane	10						
Toluene	10						
Chlorobenzene	10						
Ethylbenzene	10						
Styrene	10						
Xylene (total)	10						

Concentrations reported in micrograms per liter (ug/L).

⁻ Analyte not detected.

J Estimated value.

Table 8. Summary of Volatile Organic Compounds Detected in Surface-Water Samples Collected December 7, 1994, Syracuse China Site, Syracuse, New York.

Parameter	Quantitation Limit	Sample ID:	SW-9	SW-10	SW-12	Field Blank	Trip Blank
Chloromethane	10			••	į		
Bromomethane	10					••	
Vinyl chloride	10				••		
Chloroethane	10			••			
Methylene chloride	10		••			~-	
Acetone	10		••				
Carbon disulfide	10			••		••	
1,1-Dichloroethene	10						
1,1-Dichloroethane	10						
1,2-Dichloroethene (total)	10					**	
Chloroform	10		9 J	10	8 J		1 J
1,2-Dichloroethane	10			••			
2-Butanone	10						
1,1,1-Trichloroethane	10						••
Carbon tetrachloride	10						
Bromodichloromethane	10		2 J	2 Ј	2 J		
1,2-Dichloropropane	10						
cis-1,3-Dichloropropene	10						
Trichloroethene	10						
Dibromochloromethane	10						
1,1,2-Trichloroethane	10						
Benzene	10						
trans-1,3-Dichloropropene	10						
Bromoform	10						
4-Methyl-2-pentanone	10						
2-Hexanone	10						
Tetrachloroethene	10						
1,1,2,2-Tetrachloroethane	10						
Toluene	10						
Chlorobenzene	10						
Ethylbenzene	10						
Styrene	10						_
Xylene (total)	10		*				

Concentrations reported in micrograms per liter (ug/L).

⁻ Analyte not detected.

J Estimated value.

12:94TBL.XLSTN 9

GERAGHTY & MILLER, INC.

Table 9. Summary of Inorganic Parameters Detected in Surface-Water Samples Collected December 7, 1994, Syracuse China Site, Syracuse New York.

Parameter	Sample ID:	SW-5	9-MS	SW-7	SW-8	(Dup) SW-8	6-MS	SW-10	SW-12
Aluminim		0.299	0.103 U	0.468	0.29	0.493	0.198 B	0.2	0.405
Antimony		0.038 U	0.038 U	0.038 U	0.038 U				
Arsenic		0 001 U	0.001 U	0.001 U	0.001 U	0.002 B	0.001 U	0.001 U	0.001 B
Rarinm		0.032 B	0.045 B	0.058 B	0.031 B	0.046 B	0.024 B	0.029 B	0.039 B
Beryllium		0.001 U	0.001 U	0.001 U	0.001 U				
Cadminm		0.002 U	0.002 U	0.002 U	0.002 U				
Calcium		42.5	97.5	82	43.2	62.2	30.3	37.8	52.2
Chromium		0 002 U	0.002 U	0.002 U	0.002 U	0.002 U	0.002 U	0.002. U	0.002 U
Cobalt		0.003 U	0.003 U	0.003 U	0.003 U				
Copper		0.016 B	0.002 B	0.007 B	0.01 B	0.005 B	0.006 B	0.002 B	0.004 B
·		0.093.11	0 206	0.01 U	0.098 U	0.143	0.177 U	0.13	0.148
1 430		0.023	0.03	0.04 J	0.02	0.031	0.023	0.022	.048J
Magnesium		7.81	13.7	3.36 B	8.01	11.2	90.9	7.56	0.048 J
Manganese		0.014 B	0.064	0.026	0.016	0.018	0.007 B	0.11 B	0.015
Mercury		0.0002 U	0.0002 U	0.0002 U	910.0				
Jestoji Jest		0 008 1	0.008 U	0.008 U	0.024 B	0.008 U	0.008 U	0.008 U	0.008 U
Potassium		1.5 B	3.09 B	6.41	1.840 B	2.6 B	0.856 B	1.54	2.05 B
Selenium		0.001 U	0.001 U	0.001 U	0.001 U				
Silver		0.003 U	0.003 U	0.003 U	0.035				
Sodium		44.2	31	18.8	43.8	61.4	26.3	43.3	52.6
Thallium		0.001 U	0.001 U	0.001 U	0.001 U				
Vanadium		0.008 B	0.006 U	0.006 U	0.006 U	0.006 U	0.006 U	0.006 U	0.006 U
Zinc		0.057 J	0.013 BJ	0.092 J	0.048 J	0.122 J	0.054 J	0.06 J	0.07 J
Cyanide		0.01 U	0.01 U	0.01 U	0.01 U				

Concentrations reported in milligrams per liter (mg/L).

U Analyte analyzed for but not detected.

B Analyte result between instrument detection limit (IDL) and contract required detection limit (CRDL). J Estimated value.

Table 10. Summary of Volatile Organic Compounds Detected in Sediment Samples, Syracuse China Site, Syracuse, New York.

Parameter	Method Detection Limit	Sample ID: Sample Depth: Sample Date: Dilution Factor:	SS-5 1 ft. 12/7/94 1.30	SS-6 1 ft. 12/7/94 1.39	SS-7 1 ft. 12/7/94 1.54	SS-8 1ft. 12/7/94 6.25	SS-9 1 ft. 12/7/94 2.13	SS-10 1 ft. 12/7/94 1.32	SS-11 1 ft. 12/1/94 1.39
Chloromethane	10		J	J	J	J	J	J	
Bromomethane	10				••				
Vinyl chloride	10						••		_
Chloroethane	10						••		_
Methylene chloride	10		2 J	2 J			3 J		••
Acetone	10		30 UJ	28 UJ	17 UJ	110 UJ	41 UJ	J	36 J
Carbon disulfide	10		4 J			14 J			J0)
1,1-Dichloroethene	10			••			••	••	_
1,1-Dichloroethane	10		••	••					-
1,2-Dichloroethene (total)	10		••			••			-
Chloroform	10			••					
1,2-Dichloroethane	10				••				
2-Butanone	10		J	J	J	22 J	7 J]	J
1,1,1-Trichloroethane	10				••				,
Carbon tetrachloride	10				••	••		-	-
Bromodichloromethane	10								_
1,2-Dichloropropane	10			••					
cis-1,3-Dichloropropene	10			••	••				_
Trichloroethene	10			•-		••	••	••	
Dibromochloromethane	10								
1,1,2-Trichloroethane	10						••		_
Benzene	10								_
trans-1,3-Dichloropropene	10				••		•-		_
Bromoform	10							_	_
4-Methyl-2-pentanone	10	7/2	J	J	J	J	J	J	J
2-Hexanone	10		J	J	J	J	J	J	J
Tetrachloroethene	10						,	,	,
1,1,2,2-Tetrachloroethane	10		J	J	J	J	J	J	
Toluene	10							_,	_
Chlorobenzene	10				••			-	_
Ethylbenzene	10								_
Styrene	10								••
Xylene (total)	10								_

Concentrations reported in micrograms per kilogram (ug/kg).

⁻ Analyte not detected at or above the quantitation limit (method detection limit x dilution factor).

J Estimated value.

B Analyte also detected in associated blank.

Table 10. Summary of Volatile Organic Compounds Detected in Sediment Samples, Syracuse China Site, Syracuse, New York.

Parameter	Method Detection Limit	Sample ID: Sample Depth: Sample Date: Dilution Factor:	SS-12 1 ft. 12/7/94 2.70	BM-1 1 ft. 12/1/94 1.59	BM-2 1 ft. 12/1/94 1.28	Field Blank 12/1/94 1.00	Field Blank 12/7/94 _1.00	Trip Blank 12/1/94 1.00	Trip Blank 12/7/94 1.00
Chloromethane	10		J		••		••	••	••
Bromomethane	10				••			••	
Vinyl chloride	10			••					
Chloroethane	10					••			
Methylene chloride	10			••					
Acetone	10		J	33 J	J	J	••	J	••
Carbon disulfide	10				••		••		••
1,1-Dichloroethene	10							••	•-
1,1-Dichloroethane	10								••
1,2-Dichloroethene (total)	10							••	
Chloroform	10								1 J
1,2-Dichloroethane	10				••		••		
2-Butanone	10		J	J	J				
1,1,1-Trichloroethane	10								
arbon tetrachloride	10						••	•-	
Bromodichloromethane	10								
1,2-Dichloropropane	10								
cis-1,3-Dichloropropene	10						••		
Trichloroethene	10				••				
Dibromochloromethane	10								••
1,1,2-Trichloroethane	10								••
Benzene	10								
trans-1,3-Dichloropropene	10							••	
Bromoform	10							••	
4-Methyl-2-pentanone	10		J	J	- J				••
2-Hexanone	10		J	J	J				
Tetrachloroethene	10								
1,1,2,2-Tetrachloroethane	10		J						
Toluene	10			4 J	2 J				
Chlorobenzene	10								
Ethylbenzene	10				**				
Styrene	10								
Xylene (total)	10						••	_	

12-94TBL-XLSTN 10

⁻ Analyte not detected at or above the quantitation limit (method detection limit x dilution factor).

J Estimated value.

B Analyte also detected in associated blank.

GERAGHTY & MILLER MICEN

	Sample ID:	SS-5	9-SS	2S-7	SS-8	6-SS	SS-10	SS-11	SS-12
	Sample Depth:	1 ff.	1 ft.	1 ft.	1 ft.	1 ft.	1 ft.	1 ft.	1 ft.
Parameter	Sample Date:	12/7/94	12/7/94	12/7/94	12/7/94	12/7/94	12/7/94	12/1/94	12/7/94
Aluminum		7,200	6,860	4,760	10,100	12,700	9,270	9,470	15.500
Antimony		11.6 UJ	10.2 UJ	11.6 UJ	43.9 UJ	13.2 UJ	18.6 UJ	10.5 UJ	23.2 UJ
Arsenic		1.6 B	3.2	0.40 B	5.2 B	2.8 B	3.2 B	0.28 U	7.5
Barium		56.7 B	50.7 B	109	61.2 B	113	64.1 B	120	89.8 B
Beryllium		0.30 U	0.51 B	0.30 U	1.2 U	0.45 B	0.57 B	0.28 U	0.61 U
Cadmium		2.1	0.54 U	0.61 U	2.3 U	1.2 B	0.98 U	0.55 U	1.2 U
Calcium		5,610 J	4,160 J	5,930 J	50,500 J	35,900 J	124,000 J	9,000 J	8.330 J
Chromium		6.0 J	13.5 J	4.0 J	14.2 J	18.3 J	11.0 J	3.2 J	28.6 J
Cobalt		3.5 B	5.8 B	4.6 B	9.2 B	12.1 B	5.0 B	2.4 B	10.1 B
Copper		36.4 J	3.4 BJ	6.9 BJ	76.0 J	31.7 J	11.1 BJ	6.3 U	154 J
Iron		2,260	16,100	563	5,500	6,520	6,330	583	4.900
Lead		5,110	51.9	639	1,560	3,280	899	3,060	3,740
Magnesium		1,160 BJ	2,380 J	272 BJ	3.460 BJ	10,300 J	17,200 J	399 JB	2,470 BJ
Manganese		36.3 J	315 J	11.11	73.4 J	176 J	f 681	14.1 J	61.2 J
Mercury		0.24	0.12 U	0.14	0.62	0.31	0.20 U	0.13 U	1.1
Nickel		7.0 B	5.8 B	2.4 U	9.2 U	7.4 B	3.9 U	3.2 B	39.4
Potassium		919 B	651 B	873 B	1,430 B	1,830	1,650 B	1,980	1,540 B
Selenium		0.64 B	0.27 U	0.30 U	1.5 B	0.35 U	0.49 U	0.28 U	2.0 B
Silver		9.1	0.81 U	1.5 U	4.6 U	3.2 U	1.5 U	0.83 U	31.8
Sodium		1,800	86.6 B	1,790	1,960 B	2,540	1,940 B	4,710	2,640 B
Thallium		0.30 U	0.27 U	0.30 U	1.2 U	0.35 U	0.49 U	0.28 U	0.61 U
Vanadium		11.1 B	20.1	2.6 B	8.9 B	16.5 B	23.3 B	2.5 B	22.6 B
Zinc		260	57.1	328	708	329	130	319	746
Cyanide		0.74 UJ	0.64 UJ	0.72 UJ	2.8 UJ	0.86 UJ	1.2 UJ	U. 67 UJ	2.3 J
		(24/2, 22)							

Concentrations reported in milligrams per kilogram (mg/kg).

U Analyte analyzed for but not detected.

B Analyte result between instrument detection limit (IDL) and contract required detection limit (CRDL).

J Estimated value.

Table 12. Summary of Polychlorinated Biphenyl Compounds Detected in Sediment Samples Collected December 1, 1994, Syracuse China Site, Syracuse, New York.

Parameter	Method Detection Limit	Sample ID: Sample Depth: Dilution Factor:	BM-1 1 ft. 1.33	BM-2 1 ft. 1.35
Aroclor-1016	33			
Aroclor-1221	67			
Aroclor-1232	33		••	
Aroclor-1242	33			
Aroclor-1248	33		**	
Aroclor-1254	33			••
Aroclor-1260	33			

⁻⁻ Analyte not detected at or above the quantitation limit (method detection limit x dilution factor).

Table 13. Metal Concentrations in Sediment and New York State Sediment Criteria, Syracuse China Site, Syracuse, New York.

		teria (mg/kg)	Number of Samples (Number of Samples Greater than Criteria		
	LEL	SEL	LEL	SEL		
Arsenic	6	33	1	0		
Chromium	26	110	1	0		
Copper	16	110	4	ı		
lead	31	110	8	7		
Mercun	0,15	1.3	4	ó		
				•		
Nickel	16	50	1	0		
Silver	i	2.2	,	2		
Zinc	120	270	7	5		

LEL Lowest effect level.
mg kg Milligrams per kilogram.

SEL Severe effect level.

Table 14. Calculated Hydraulic Conductivity Values for Monitoring Wells at the Syracuse China Site, Syracuse. New York.

Monitoring Well	Screened Unit	Hydraulic Conductivity (k)
MW-1	Upper	6.27 x 10 ⁻⁵
MW-2	Upper	1.35 x 10 ⁻⁴
MW-3	Upper	1.49 x 10 ⁻⁴
MW-4	Upper	2.03 x 10 ⁻³
MW-5	Upper	3.38×10^{-4}
MW-6	Upper	2.63 x 10 ⁻⁴
MW-7	Upper	2.44 x 10 ⁻⁴
MW-4I	Till	3.26 x 10 ⁻⁶
	Upper	2.44 x 10 ⁻⁴

Table 15. Summary of Total and Dissolved Metals Detected in Groundwater Samples Collected on August 17, 1995 at Syracuse China Landfill, Syracuse China Company, Syracuse, New York.

	Sample Location:	MW-1	MW-2	MW-3	MW-4	MW-41
Analyte	Sample Date:	8/17/95	8/17/95	8/17/95	8/17/95	8/17/95
Aluminum						
Total		1,770	4,680	51,400	1,790	55,400
Dissolved		2,480	5,050	2,370	656	6,460
Antimony		-		2,0.0	000	0,400
Total		33.0 U	33.0 U	34.9 B	33.0 U	49.7 B
Dissolved		5.5 B	5.1 B	4.0 B	3.0 U	5.0 B
Arsenic				.,,	0.00	3.00
Total		3.0 U	6.3 B	107	3.0 U	41.3
Dissolved		3.0 U	3.0 U	3.7 B	3.0 U	3.0 U
Barium			· ·	J., D	5.0 0	3.00
Total		49.9 B	55.4 B	403	40.3 B	590
Dissolved		46.2 B	45.6 B	45.4 B	24.0 B	58.4 B
Beryllium			.0.0 0	45.4 6	24.0 6	30.4 5
Total		1.0 U	1.0 ∪	5.1	1.0 U	6.6
Dissolved		1.0 U	1.0 U	1.0 U	1.0 U	1.3 U
Cadmium			7.00	1.0 0	1.0 0	1.5 0
Total		3.0 U	3.0 U	3.0 U	3.0 U	3.0 U
Dissolved		1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
Calcium				1.0 0	1.00	1.00
Total		150,000	450,000	656,000	390,000	792,000
Dissolved		136,000 J	380,000 J	157,000 J	369,000 J	400,000
Chromium		,	333,333 3	107,000 3	303,000 3	400,000
Total		5.2 B	7.5 B	67.4	3.8 B	132
Dissolved		4.0 B	6.3 B	3.7 B	1.9 B	9.3 B
Cobalt			0.00	3.7 B	1.9 6	э.э ь
Total		4.3 BJ	6.4 BJ	47.4 BJ	4.7 BJ	61.2 J
Dissolved		3.0 U	3.0 U	3.0 U	3.0 U	3.0 U
Copper		0.00	0.00	3.0 0	3.0 0	3.0 0
Total		18.0 U	27.6 U	124	14.9 U	226
Dissolved		2.0 U	3.8 U	2.0 U	2.0 U	236
Iron		2.00	5.5 0	2.00	2.0 0	2.7 U
Total		3,350	10,900	126,000	3 000	117.000
Dissolved		1,190	3,940	2,190	3,000	117,000
Lead		1,130	3,340	2,190	590	5,200
Total		4.4	8.9	213	6.6	00.4
Dissolved		3.1	3.5	5.7	0.6 2.8 B	99.1 4.7

U Analyte result less than instrument detection limit (IDL).

B Analyte result between IDL and contrct required detection limit (CRDL).

J Estimated.

⁻⁻ Analyte not analyzed for.

Table 15. Summary of Total and Dissolved Metals Detected in Groundwater Samples Collected on August 17, 1995 at Syracuse China Landfill, Syracuse China Company, Syracuse, New York.

A	Sample Location:	MW-1	MW-2	MW-3	MW-4	MW-41
Analyte	Sample Date:	8/17/95	8/17/95	8/17/95	8/17/95	8/17/95
Magnesium						
Total		41,500 J	70,400 J	207,000 J	24,300 J	174,000 J
Dissolved		35,600	54,000	43,500	24,000	48,700
Manganese			•		_ ,,,,,,,	70,7.00
Total		123 J	1,510 J	3,470 J	5,720 J	4,570 J
Dissolved		30.1	278	472	2,020	1,150
Mercury					-,	.,
Total		0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
Dissolved		0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
Nickel			0.200	0.20 0	0.200	0.20 0
Total		7.0 UJ	12.5 BJ	91.1 J	10.0 BJ	155 J
Dissolved		3.7 B	10.2 B	5.4 B	5.5 B	13.6 B
Potassium				0.10	3.3 B	13.0 B
Total		1,830	3,520	8,560	4,270	19,400
Dissolved		2,100	5,930	2,180	5,110	19,700
Selenium		_,	0,000	2,100	3,110	13,700
Total		5.0 B	2.0 U	5.8	2.0 U	5.5
Dissolved		4.1 B	2.0 U	2.5 B	2.0 U	2.0 U
Silver		6)	2.00	2.3 5	2.00	2.0 0
Total		2.5 BJ	2.0 U	2.0 U	2.0 U	2.0 U
Dissolved		1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
Sodium		.,,,	7.00	1.00	1.00	1.0 0
Total		14,900 J	51,600 J	43,500 J	40,400 J	30,700 J
Dissolved		14,700	48,300	33,400	38,700	26,800
Thallium		,	.0,000	33,400	30,700	20,800
Total		4.0 U	4.0 U	4.0 U	4.0 U	4.0 U
Dissolved		4.0 U	4.0 U	4.0 U	4.0 U	4.0 U
Vanadium			11.0 0	4.0 0	4.0 0	4.0 0
Total		1.6 U	16.1 B	93.0	1.0 U	96.7
Dissolved		1.0 U	11.5 B	8.5 B	1.0 U	15.3 U
Zinc			5	0.5 6	1.0 0	15.3 0
Total	ÿ.	73.9	85.1	261	53.5	419
Dissolved		18.8 BJ	16.1 BJ	14.9 BJ	23.8 J	
Cyanide				נט פ.דו	23.0 J	36.8 J
Total						
Dissolved					••	

U Analyte result less than instrument detection limit (IDL).

B Analyte result between IDL and contrct required detection limit (CRDL).

J Estimated.

⁻⁻ Analyte not analyzed for.

Table 15. Summary of Total and Dissolved Metals Detected in Groundwater Samples Collected on August 17, 1995 at Syracuse China Landfill, Syracuse China Company, Syracuse, New York.

				(MW-6 Rep)		
	Sample Location:	MW-5	MW-6	Rep-1	MW-7	FB
Analyte	Sample Date:	8/17/95	8/17/95	8/17/95	8/17/95	8/17/95
A 1						
Aluminum						
Total	85	622	41,600	46,600	7,500	28.0 B
Dissolved		575	3,040	4,320	3,130	
Antimony ·						
Total		33.0 U	33.0 U	33.0 U	33.0 U	33.0 U
Dissolved		5.3 B	4.0 B	3.9 B	5.2 B	
Arsenic						
Total		7.0 B	27.6	35.6	15.6	3.0 U
Dissolved		3.0 U	3.0 U	3.0 U	3.0 U	••
Barium						
Total		45.8 B	545	541	89.6 B	2.0 U
Dissolved		43.1 B	93.4 B	111 B	46.6 B	••
Beryllium						
Total		1.0 U	5.4	7.2	1.5 B	1.0 U
Dissolved		1.0 U	1.0 U	1.2 U	1.0 U	
Cadmium						
Total		3.0 U	3.0 U	3.0 U	3.0 U	3.0 U
Dissolved		1.0 U	1.0 U	1.0 U	1.0 U	
Calcium						
Total		88,400	477,000	518,000 J	299,000	202 B
Dissolved		87,800 J	92,200 J	90,000 J	185,000 J	
Chromium			,	00,000	100,000 \$	
Total		3.0 U	76.4	87.6	13.3	3.0 U
Dissolved		1.9 B	4.7 B	6.2 B	4.8 B	3.00
Cobalt				0.2 0	4.0 D	
Total		3.0 UJ	60.2 J	63.0 J	12.3 BJ	3.0 U
Dissolved		3.0 U	3.0 U	3.0 U		
Copper		5.5 5	0.00	3.0 0	3.0 U	
Total		7.1 U	276	260	20.0	2.4.
Dissolved		2.0 U	2.0 U	2.0 U	38.8	3.0 U
Iron		2.00	2.00	2.0 0	2.0 U	
Total		1,890	85,100	05 500	17.000	70.4-
Dissolved		627		95,500	17,800	70.1 B
Lead		027	2,090	2,950	2,340	
Total		3.4	E.C. C	F0.0	0.00	
Dissolved		3. 4 3.9	56.5	56.9	292	3.0 B
2.0001700		ა.უ	3.6	3.2	34.2	••

U Analyte result less than instrument detection limit (IDL).

B Analyte result between IDL and contrct required detection limit (CRDL).

J Estimated.

⁻⁻ Analyte not analyzed for.

Table 15. Summary of Total and Dissolved Metals Detected in Groundwater Samples Collected on August 17. 1995 at Syracuse China Landfill, Syracuse China Company, Syracuse, New York.

Analyte	Sample Location: Sample Date:	MW-5 8/17/95	MW-6 8/17/95	Rep-1 8/17/95	MW-7 8/17/95	FB 8/17/95
Magnesium						
Total		29,400 J	158,000 J	179,000 J	53,400 J	50.4 B
Dissolved		29,900	20,500	23,400	11,800	30.4 5
Manganese					,000	
Total		30.9 J	2,790 J	3,080 J	1,450 J	2.0 B
Dissolved		12.6 BJ	121 J	152	864	2.00
Mercury				. • •	004	
Total		0.20 U	0.20 B	0.20 U	0.20 U	0.20 U
Dissolved		0.20 U	0.20 U	0.20 U	0.20 U	0.20 0
Nickel				0.200	0.20 0	
Total		7.0 UJ	106 J	119 J	21.2 UJ	7.8 B
Dissolved		2.7 B	5.0 B	7.6 B	6.3 B	
Potassium			0.00	7.00	0.5 6	••
Total		9,010	10,100	10,100	5,970	681 U
Dissolved		11,300	2,660	3,480	6, 570	0010
Selenium		,	2,000	3,400	0,370	r
Total		2.0 U	6.0	6.9	3.3 B	2.0 U
Dissolved		2.0 U	2.0 U	2.0 U	2.0 U	2.0 0
Silver			2.00	2.00	2.0 0	••
Total		2.0 U	41.8 J	4.0 BJ	2.0 U	2.0 U
Dissolved		1.0 U	1.0 U	1.0 U	1.0 U	
Sodium			1.0 0	1.00	1.0 0	••
Total		68,000 J	19,300 J	21,700 J	38,300 J	42.0 U
Dissolved		62,500	17,400	15,200	34,100	
Thallium		02,000	17,100	13,200	34,100	••
Total		4.0 U	4.0 U	4.0 U	4.0 U	4.011
Dissolved		4.0 U	4.0 U	4.0 U	4.0 U	4.0 U
Vanadium			4.0 0	4.0 0	4.00	
Total		2.3 U	56.9	58.1	10 O D	4.0.11
Dissolved		3.3 B	3.0 U	3.7 U	18.9 B	1.0 U
Zinc		0.0 5	3.0 0	3.70	8.3 U	
Total		62.1	342	342	75 7	07.0
Dissolved		26.5 J	56.6 J		75.7 U	27.6
Cyanide		20.0 J	50.0 J	15.0 BJ	54.9 J	
Total						
Dissolved				••	••	

U Analyte result less than instrument detection limit (IDL).

B Analyte result between IDL and contrct required detection limit (CRDL).

J Estimated.

⁻⁻ Analyte not analyzed for.

Table 16. Summary of Total Metals and Cyanide Detected in Surface Water Samples Collected at Syracuse China Landfill, Syracuse China Company, Syracuse, New York.

Analyte	Sample Location: Sample Date:	SW-1 8/17/95	SW-2 8/17/95	SW-2A 8/17/95	SW-3 8/17/95
Aluminum		129 B	173 B		139 B
Antimony		33.0 U	33.0 U	••	
Arsenic		3.0 U	3.0 U		33.0 U
Barium		36.2 B	33.2 B		3.0 U
Beryllium		1.0 U	1.0 U	 	38.6 B
Cadmium		3.0 U	3.0 U		1.0 U
Calcium		63,100	36,200	••	3.0 U
Chromium		3.0 U	3.0 U	••	37,000
Cobalt		3.0 UJ	3.0 UJ		3.0 U
Copper		15.7 U	12.8 U	••	3.0 UJ
ron		269	301		6.5 U
Lead		51.3	79.9	2.100	194
Magnesium		9,320 J	73.3 7,190 J	2,100	41.3
Manganese		19.9 J	18.3 J	••	7,850 J
Mercury		0.20 U	0.20 U		18.9 J
Nickel		7.0 UJ		••	0.20 U
Potassium		2,050	7.0 UJ		7.0 UJ
Selenium		2,050 2.0 U	1,670		1,730
Silver			2.0 U	•-	2.0 U
Sodium		2.7 BJ	2.0 ∪	•-	2.0 U
Thallium		22,100 J	19,300 J		19,200 J
Vanadium		4.0 U	4.0 U	••	4.0 U
		7.1 U	3.1 B	••	2.4 B
Zinc		39.6	23.3	••	18.6 B
Cyanide		10.0 U	10.0 U	••	10.0 U

U Analyte result less than instrument detection limit (IDL).

B Analyte result between IDL and contrct required detection limit (CRDL).

J Estimated.

⁻⁻ Analyte not analyzed for.

Table 16. Summary of Total Metals and Cyanide Detected in Surface Water Samples Collected at Syracuse China Landfill, Syracuse China Company, Syracuse, New York.

Analyte	Sample Location: Sample Date:	SW-4 8/17/95	SW-4A 8/17/95	SW-5 8/17/95	SW-6 8/17/95
Aluminum		533	••	211	401
Antimony		33.0 U	••	33.0 U	33.0 U
Arsenic		6.4 B	••	3.0 U	3.0 U
Barium		52.0 B		36.2 B	39.6 B
Beryllium		1.0 U		1.0 U	1.0 U
Cadmium		3.0 U	••	3.0 U	3.0 U
Calcium		39,100		35,900	37,200
Chromium		4.2 B		3.0 U	3.0 U
Cobalt		3.0 UJ	••	3.0 U	3.0 U
Copper		9.0 U		8.1 U	8.6 U
Iron		2,360		94.8 B	178
Lead		315	103	42.7	101
Magnesium		8,130 J		8,090	8,300
Manganese		259 J		14.9 B	23.9
Mercury		0.20 U		0.20 U	0.20 U
Nickel		7.0 UJ		7.0 U	7.0 U
Potassium		2,140		2,540	1,960
Selenium		2.0 U		2.0 U	2.0 U
Silver		2.3 BJ		2.2 BJ	2.0 U
Sodium		19,600 J		18,500	18,900
Thallium		4.0 U		4.0 U	4.0 U
Vanadium		1.8 B		3.2 B	4.0 U
Zinc		52.4		46.7	53.6
Cyanide		10.0 U		10.0 U	10.0 U

U Analyte result less than instrument detection limit (IDL).

B Analyte result between IDL and contrct required detection limit (CRDL).

J Estimated.

⁻⁻ Analyte not analyzed for.

Table 17. Summary of Total Metals and Cyanide Detected in Sediment Samples Collected at Syracuse China Landfill, Syracuse China Company, Syracuse, New York.

Analyte	Sample Location: Sample Date:	SED-1	SED-2	SED-2A	SED-3
r trially to	Sample Date.	8/17/95	8/17/95	8/17/95	8/17/95
Aluminum		10,500	11,600	••	11,800
Antimony		2.4 UJ	4.2 BJ	••	4.3 UJ
Arsenic		44.3	64.1		48.3
Barium		86.4 B	148 B	••	135 B
Beryllium		0.81 U	1.1 U	==	1.4 U
Cadmium		2.5 B	3.2 B	••	3.6 B
Calcium		33,000	10,900		12,900
Chromium		32.1	29.8		32.0
Cobalt		4.6 B	4.6 B		5.1 B
Copper		80.4	64.8	**	88.0
Iron		25,700	26,500	•-	27,300
Lead		3,380	4,840	2,020	4,510
Magnesium		5,060	2,860		2,110
Manganese		158	86.6		166
Mercury		0.37 U	0.54 U	••	0.75 U
Nickel		14.2 B	13.0 B		15.5 B
Potassium		853	685 B		900 B
Selenium		4.4	5.8		4.4 B
Silver		4.1 B	5.1 B		4.9 B
Sodium		1,120	1,010 B		1,380 B
Thallium		3.2 U	4.3 U		5.7 U
Vanadium		48.1	44.6 B		41.3 B
Zinc		599 J	796 J		722 J
Cyanide		R	° R	**	R

Concentrations reported in milligrams per kilogram (mg/kg).

U Analyte result less than instrument detection limit (IDL).

B Analyte result between IDL and contrct required detection limit (CRDL).

J Estimated.

⁻⁻ Analyte not analyzed for.

R Rejected result

Table 17. Summary of Total Metals and Cyanide Detected in Sediment Samples Collected at Syracuse China Landfill, Syracuse China Company, Syracuse, New York.

Analyte	Sample Location: Sample Date:	SED-4 8/17/95	SED-4A 8/17/95	SED-5 8/17/95	SED-6 8/17/95	SED-6A 8/17/95
Aluminum		8,080	T.	12,000	10,800	••
Antimony		6.3 UJ		2.0 UJ	1.4 UJ	••
Arsenic		41.1		5.7 B	4.5 B	••
Barium		128 B	••	80.4 B	67.0 B	••
Beryllium		2.1 U	••	0.66 U	0.46 U	••
Cadmium		3.7 B	••	1.8 B	2.2 B	
Calcium		9,950	••	19,300	8,800	••
Chromium		20.6 B		27.6	16.9	
Cobalt		3.8 B		7.9 B	6.1 B	
Copper		57.6	••	110	137	
lron		17,600		5,840	4,170	
Lead		3,720	617	2,580	4,000	6,010
Magnesium		1,690 B		3,480	2,510	
Manganese		1,540	••	187	60.2	••
Mercury		1.0 U		0.83 J	0.83 J	
Nickel		19.0 B	••	17.2 B	14.4 B	
Potassium		519 B		1,340	1,180	••
Selenium		6.8 B	••	1.3 U	1.5 B	
Silver		2.1 U		15.7	35.0	
Sodium		949 B	••	2,100	2,520	
Thallium		8.4 U		2.6 U	1.8 U	
Vanadium		45.2 B		21.4 B	21.8 B	
Zinc		775 J		596 J	612 J	•-
Cyanide		R		R	R	

Concentrations reported in milligrams per kilogram (mg/kg).

U Analyte result less than instrument detection limit (IDL).

B Analyte result between IDL and contrct required detection limit (CRDL).

J Estimated.

⁻⁻ Analyte not analyzed for.

R Rejected result

Table 18. Summary of the Dissolved Metals Concentrations in Groundwater Samples Collected on August 17, 1995, Exceeding the New York State Department of Environmental Conservation Division of Water Technical and Operational Guidance Series (TOGS 1.1.1) Ambient Water Quality Standards and Guidance Values, Syracuse China Site, Syracuse, New York.

	TOGS 1.1.1 Standard	MW-1 8/17/95	MW-2 8/17/95	MW-3 8/17/95	MW-4 8/17/95	MW-41 8/17/95	MW-5 8/17/95	MW-45 8/17/95	MW-7 8/17/95
Iron	0.3	1.19	3,94	2.19	0.59	5.2	0.627	2.09	2.34
Magnesium	35*	35.6	54.0	43.5	ı	18.7	ı	1	I
Manganese	0.3	1	1	0.472	2.02	1.15	ı	I	0.864
Sodium	20	ł	18.3	33.4	38.7	26.8	62.5	ı	34.1
Zinc	0.3	I	i	ŀ	;	ı	1	1	,*

Guidance Value.

Standard Not Exceeded.

Parameter	TOGS 1.1.1 Standard	MW-1 1/5/95	MW-2 1/5/95	MW-3 1/5/95	MW-3 (Duplicate) 1/5/95	MW-4 1/5/95	MW-4I 1/5/95	MW-5 1/5/95	MW-6 1/5/95	7-WW 1/5/95
Arsenic	0.025	;	1	0.049	0.062	0.027	0.027	:	0.043	1
Copper	0.2	;	;	;	;	;	ł	;	0.356	ŀ
Iron	0.3	20.7	20.9 J	70.2 J	81.4	95.8 J	85.2 J	9.89	139 J	17.2 J
Lead	0.025	ł	:	0.176	0.254	0.051 J	i	1	990.0	0.216
Magnesium	35*	74.6	82.2	206	661	99.4	157	45.8	221	37.2
Manganese	0.3	0.77	2.28	3.46	3.39	38.2	3.92 J	1	4.21	2.53
Sodium	20	22.3	1,020	32.6	32.8	38.9	25.5	71.6	;	33.6
Vanadium	0.014	;	0.24 B	0.074	0.075	0.088	0.074 J	ł	0.109	1
Zinc	0.3	ł	1	;	1	ı	1	ŀ	0.461	1

B Analyte result between instrument detection limit (IDL) and contract required detection limit (CRDL).

Estimated value.

-- Standard not exceeded.

Guidance value.


Table 20. Summary of Total (Unfiltered) Metals Concentrations in Groundwater Samples Collected on August 17, 1995, Exceeding the New York State Department of Environmental Conservation Division of Water Technical and Operational Guidance Series (TOGS 1.1.1) Ambient Water Quality Standards and Guidance Values, Syracuse China Site, Syracuse, New York.


									(MW-6 Rep)	i a
	Sample Location: MW-1	MW-1	MW-2	MW-3	MW-4	MW-41	MW-5	9-WM	Rep-1	MW-7
Analyte	Sample Date: 8/17/95	8/17/95	8/17/95	8/17/95	8/17/95	8/17/95	8/17/95	8/17/95	8/17/95	8/17/95
Arsenic		:	ł	0.107	:	0.0413	:	0.0276	0.0356	:
Copper		:	:	:	:	0.236	;	0.276	0.260	:
Iron		3.35	10.9	126	က	117	1.89	85.1	95.5	17.8
Lead		:	1	0.213	:	0.0991	;	0.0565	0.0569	0.292
Magnesium	۲	41.5 J	70.4 J	207 J	;	174 J	;	158 J	179 J	53.4 J
Manganese	ø	:	1.51 J	3.47 J	5.72 J	4.57 J	:	2.79 J	3.08 J	1.45 J
Sodium		:	51.6 J	43.5 J	40.4)	30.7 J	68 J		21.7 J	38.3 J
Vanadium		:	0.0161 B	0.093	1	0.0967	:	0.0569	0.0581	0.0189 B
Zinc		;	;	:	:	0.419	:	0.342	0.342	;


B Analyte result between IDL and contrct required detection limit (CRDL).


J Estimated.


-- Standard not exceeded.











APPENDIX A

SOIL BORING AND WELL CONSTRUCTION LOGS

Boring/Well	PMW-11 Project No.	·	AY0146.002				Page	10	ſ1
Site									
Location Syra	cuse China Landfill	Drill	ing Started	11/29	/94	Drilling C	Completed	11/29	9/94
Total Depth Drilled	34	_ feet	Hole Diameter	6	inches		Sample/ Device	Split-Spoon Shelby	•
Length and Diameter of Coring Device	z 24" Split-Spoon	2-inch ir	iside diameter			Sampling	Interval	2	leet .
Land-Surface Elevation	411.53	feet		Surveyed	X Estimated		Datum	Mean sea le	·vel
Drilling Fluid Used	None				Drilling	Method	4.25-inch	Hollow-Stem	Auger
Drilling Contractor	Parratt-Wolff			Driller	G. Lansing	3	Helper	K. White	
Prepared By J. Ga	ardner				Hammer Weight	140	Hammer Drop	30	inches

Sample/C (feet below i		Core .	Fime/Hydraulic Pressure or	OVM		
•		Recovery	Blows per 6	Field	OVM	
From	To	(feet)	Inches	Cuttings	Sampling	Sample/Core Description
0	2	10°	3-5, 4-4	0 00	0 00	Light brown Silt, little fine to medeium sand, trace fine gravel, moist, medium
						compact, organics top 2°
2	4	20°	3-5, 5-5		0 00	Light brown-tan Silt, some fine sand, cinders, moist, medium compact-soft.
4	6	22*	Woh-1, 2-5	0.00	0 00	Tan sitty fine Sand, moist, soft.
6	8	20°	6-7, 6-5		<1	Tan salty fine Sand, moist, soft wet.
8	10	24*	3-5, 5-6		<1	Tan silty find Sand, moist, soft, wet.
10	12	18*	7-9, 5-5		<1	Tan 12 by Sand, little fine to medium gravel, soft, moist-wet.
12	14	11"	3-4, 3-6	0 00	0.00	Tan sity Sand little fine to medium gravel, soft, moist-wet.
14	16	22*	6-8.9-6		0.00	Tan sity fine Sand, moist-wet, soft
16	18	24*	12-14, 13-19			Tan silty fine Sand, moist-wet, soft
18	20	24"	10-13, 19-25		0 00	Tan 19 by fine to medium Sand, moist-wet, medium compact.
20	22	20°	14-18, 26-32	0 00	0.00	Tan silty fine to medium Sand, moist-wet, more compact.
22	24	22°	22-30, 41-60		0 00	Tan silty fine to medium Sand, moist-wet, more compact.
24	26	24'	23-22, 20-45		0.00	Tan salty fine to medium Sand, moist-wet, more compact.
26	28	18"	22-32, 43-47		0.00	Tan Silt and Sand, moist-wet, medium compact.
28	30	20*	22-25, 41-60		0.00	Tan-brown, silty fine to medium Sand, moist, medium compact.
30	32	18*	12-24, 21-32	<u> </u>	0 00	Top 14°, Tan-brown silty fine Sand, moist, medium compact. Bottom 4°; fine to
				<u> </u>	 	med um to coarse Sand, little silt, trace fine gravel, moist-wet, medium compact.
32	34	18"	39-33, 30-50/4	0.00	0 00	Red green Silt, some fine to medium to coarse sand, little fine gravel, moist-
		<u> </u>			 	dry very compact (till-like).
34	36			0,00	-	Shelby tube attempted - No sample recovered.
36	38	L	50/3	0 00	0.00	Red Silk, little fine sand above weathered red fine grained shale.

Boring/Well	PMW-31 Project No	<u> </u>	AY0146.00)2			Page	lof_	2
Site Location Syr	acuse China Landfill	Drill	ing Started	11/30	0/94	Drilling	Completed	11/30/9	14
Total Depth Drilled	30	feet	Hole Diameter	6	inches		of Sample/ ng Device	Split-Spoon S	Sampler
Length and Diameter of Coring Device	er 24" Split-Spoor	2-inch ir	side diameter			Samplin	g Interval	2	feet
Land-Surface Elevation	384	feet		Surveyed	X Estimated		Datum	Mean sea leve	1
Drilling Fluid Used	None				_ Drilling	Method	4.25" Holl	low-Stem Auge	r
Drilling Contractor	Parratt-Wolff			Drille	r <u>G. Lansin</u>	g	Helper	K. White	
Prepared By J. C	Gardner				Hansmer Weight	140	Hammer Drop	30	inches

	ore Depth and surface		Fime/Hydraulic Pressure or Blows per 6	OVM Field	OVM	
Prom	То	(feet)	Inches	Cuttings	Sampling	Sample/Core Description
	2	1.	1-2, 2-1		0 00	China scrap, wood fragments
2	4	3*	3-1, 1-3		0 00	Organics, wood chips, black silt, little fine sand, moist, soft
4	6	4.	5-3, 6-4		0.00	Light brown-tan Silt, little fine sand, china scrap, loose, wet
6	8	8.	Woh-1 5', 2	0 00	0.00	Light brown Sill, little clay, trace fine sand, soft, moist-wet
8	10	10°	3-3, 3-6		0 00	Top 8° light brown Silk little clay, trace fine sand, soft, moist-wet. Above 2°;
						red brown Silt, some fine to medium to coarse sand, little clay, moist, very
						compact (Till-like)
10	12	10°	8-7, 7-8		000	Red/brown Silt, little fine to medium to coarse sand, little clay, moist, medium
						compact (Till-like)
12	14	12"	16-21, 25-29	0 00	0 00	Red/brown Silt, little fine to medium to coarse sand, little clay, moist, more
						compact (Till-like)
14	16	18*	12-15, 12-16		0.00	Top 16° red/brown Silt, little fine to medium to coarse sand, little clay, moist,
	ļ					very compact. Bottom 2" borwn-gray silty fine to medium Sand, moist, loose.
16	18	20*	9-8, 13-20		0.00	Brown/gray fine to medium Sand, little silt, moist, compact.
18	20	24*	21-22, 57-89	000	0.00	Brown/gray fine to medium Sand, little silt, moist, very compact.
20	22	22*	12-14, 34-56		0.00	Very fine silty Sand, moist, very compact.
22	24.5	20°	38-45, 80		0.00	Brown silty fine to medium Sand, trace fine gravel, moist, very compact.
24	26	10"	30-38, 24-27		0 00	Red-brown silty fine to medium to coarse Sand and Gravel, moist, very compact
	ļ					(Till-like).
26	28	8.	29-27, 84		0.00	Silty Sand and Gravel moist, very compact above red Silt, some fine to medium
<u> </u>	ļ		ļ		ļ	sand, little gravel, moist, very compact (Till-like).
28	29	6°	36-70		17.0	Red Silt, some fine to medium to coarse sand, little fine to medium gravel, moist,
			<u> </u>			very compact (Till-like).

SAMPLE/CORE LOG (Cont.d)

Boring/Well	PMW-31	Pa	ige 2 of 2
Prepared by	J. Gardner		

Sample/Cor (feet below lar Prom	re Depth nd surface)	Core Recovery (feet)	Time/Hydraulic Pressure or Blows per 6 inches	OVM Fleid Cuttings	OVM Sampling	Sample/Core Description
30	32	20*	38-69			Top 15° red Silt, some fine to medium to coarse sand, little fine to medium gravel,
	ļ		· · · · · · · · · · · · · · · · · · ·			moist, very compact (Till-Like). Bottom 5°, Oreen weathered shale - Artesian
		 				Water flowing up through augers Artesian flowing at about 50 gpm.
			··	ļ		12/1/94 Artesian flowing at about 20 gpm. Grouted with coment plug 12/1/94.
						No monitoring well installed.
	-	<u> </u>				
				1		
		 	N N	 		
	 				 	
	 					
		-			 	
	 	-		+		
-	 	-		-		
	1				 	
	-			-	-	
		-		-	 	
				 	-	
				 		

Boring/Well	MW-41 Project No		AY0146.002			Page	1 of1_
Site Location Syre	icuse China Landfill	Dril	ling Started	11/29/	94	Drilling Completed	11/30/94
Total Depth Drilled	18	feet	Hole Diameter	6	inches	Type of Sample/ Coring Device	Split-Spoon Sampler
Length and Diamete of Coring Device	24" Split-Spoon	∕2-inch i	nside diameter			Sampling Interval	2 feet
Land-Surface Elevation	383.91	feet	x Xs	urveyed (Estimated	Datum	Mean sea level
Drilling Fluid Used	None				Drilling	Method 4.25	" Hollow-Stem Auger
Drilling Contractor	Parratt-Wolff			Driller	G. Lansing	Helpe	r K. White
Prepared By J. G	ardner				Hammer Weight	Hamme 140 Drop	

Sample/C			lime/Hydraulic	!		
(feet below l	and surface	Core	Pressure or	OVM		
From	т.	Recovery	Blows per 6	Fleld	OVM	
r rom	To	(feet)	Inches	Cuttings	Sampling	Sample/Core Description
0	2	10"	W-2, 2-3	0.00	0.00	Top 4°; Dark brown Silt, some fine to medium sand, trace fine gravel, moust,
						compact, organics. Bottom 6°, China scrap-fragments
2	4	16°	4-6, 3-3	-	0.00	Dark brown Silt, China-scrap fragments, (fill) Bottom 3°; Dark black Silt, some
						fine sand, moist, soft.
4	6	18*	WOH-1.5', 3	0.00	0.00	Light brown Silt, little fine sand, little clay, moist-wet, soft
- 6	8	20*	2-1, 2-1		0.00	Light brown Silt, little fine sand, little clay, moist-wet, soft
- 8	10	12*	2-2, 2-2		0.00	Light brown Silt, little fine sand, little clay, wet, soft.
10	12	12"	1-4, 7-12		0.00	Light brown-red Sift, some fine to medium to coarse sand, little fine to medium
						gravel, moist, compact (Till-like)
12	13	10°	31-54	0.00	0.00	Light brown-red Silt, some fine to medium to coarse sand, little fine to medium
						gravel, moist, compact (Till-like).
14	15.5	10°	30-33, 57		0.00	Light brown-red Silt, some fine to medium to coarse sand, little fine gravel,
						(various lithologies) moist, very compact. (Till-like).
16	18	12*	48-52, 57-51	0.00	0.00	Light brown-red Sift, some fine to medium to coarse sand, little fine gravel,
						(various lithologies) moist, very compact. (Till-like).
18	20	12°	26-31, 52-38		0.00	Light brown-red Sift, some fine to medium to coarse sand, little fine gravel,
		-				(various lithologies) moist, very compact. (Till-like). Sample collected for
					<u> </u>	Hydraulic Conductivity testing
					ļ	
L	L					

Boring/Well	MW-6 Project No.		AY0146.00	2			Page	1 0	
Site Location Syrac	use China Landfill	_ Drill	ing Started	11/21	3/94	Drilling C		11/28	
Total Depth Drilled	16	_ feet	Hole Diameter	6	inches		Sample' Device	Split-Spoor	n Sampler
Length and Diameter of Coring Device	24" Split-Spoon	2-inch is	iside diameter			Sampling	Interval	2	feet
Land-Surface Elevation	413.14	_foet	X	Surveyed	Estimated		Datum	Mean sea le	
Drilling Fluid Used	None				Drilling	Method	4.25*	Hollow-Stem	
Drilling Contractor	Parratt-Wolff			Driller	G. Lansing	3	Helper	K. White	
Prepared By J. Gar	dner				Hanvmer Weight	140	Hammer Drop		inches

Sample/Confect below to		Core Recovery (feet)	Time/Hydraulic Pressure or Blows per 6 inches	OVM Fleid Cuttings	OVM Sampling	See Life Book of
0	2	10°				Sample/Core Description
·		10	3-4, 1-1	70	0.00	Dark brown-black Silt, little fine to medium sand, little fine gravel, moist, loose-
				(background)		medium compact.
2	4	15*	2-5, 4-3	7.0	<1	Top 6" dark brown-black Silt, little fine to medium sand, little fine gravel, moist,
						loose-medium compact. Above, tan-orange Silt, little fine to medium to coarse
						sand, moist, medium comapet, non-stratified
4	6	14*	10-11, 12-15		<1	Tan-orange Silt, little fine to medium to coarse sand, medium compact,
						wet, non-stratified
6		17"	12-15, 19-21		0.00	Tan-orange silty Sand, trace fine gravel, most-wet, medium compact.
8	10	20°	6-13, 19-24		<1	Tan-orange silty Sand, trace fine gravel, most-wet, medium compact.
10	12	12*	9-12, 29-33		<1	Top 4° Tan-orange, salty Sand, trace fine gravel, moest-wet, medium compact.
						Bottom 8° becoming more compact, less mosst. (Till-like)
12	14	12"	30-28, 35-41	7.0	<1	Light brown-orange Sift, some fine to medium to coarse gravel, little fine to
						medium sand, compact, unstratified, moist
14	16	20*	20-20, 32-35		<1	Light brown-orange Silt, some fine to medium to coarse gravel, little fine to
	E#					medium sand, compact, unstratified, moist
16	17.5		30, 32, 75		<1	
					-1	Light brown-orange Silt, some fine to medium to coarse gravel, little fine to
			<u> </u>			medium sand, compact, unstratified, moist
						
						
Ll						

Boring/WellN	IW-7 Project No.		AY0146.002				Page		_1_
Site Location Syracus	e China Landfill	Drilli	ing Started	12/1/5	94	Drilling C	ompleted	127	м
Total Depth Drilled	14	feet	Hole Diameter	6	inches	Type of Coring	Sample/ Device	Split-Spoor	Sampler
Length and Diameter of Coring Device	24" Split-Spoon/2	?-inch in	side diameter	į.		Sampling	Interval	2	feet
Land-Surface Elevation	393.21	feet	Xs	Surveyed	Estimated		Datum	Mean ses les	d
Drilling Fluid Used	None		· · · · · · · · · · · · · · · · · · ·		Drilling	Method	4.25"	Hollow-Stem	Auger
Drilling Contractor	Parratt-Wolff		3	Driller	G. Lansing		Helper	K. White	
Prepared By J. Gard	ner				Hanuner Weight	140	Hammer Drop	30	inches

Sample/Co		1 Core	Finie/Hydraulic Pressure or	OVM		
From	То	Recovery (feet)	Blows per 6 inches	Field Cuttings	OVM Sampling	Sample/Core Description
0	2	0.0	3-2, 1-1			Chuna scrap
2	4	5*	2-2, 1-1	0.00	0.00	Light brown Silt, little fine sand, little fine to medium gravel, moist, soft, some
						china scrap
4	6	8.	W-2, 2-3	0.00	0 00	Light brown Silt, little fine sand, little fine to medium gravel, moist, sec., some
						сыпа эстар.
6	8	24*	3-1,1-1		0.00	Brown clayey Silt, trace fine sand, trace fine gravel, moist-wet, soft to seff
-						/bottom 6" more clavey)
8	10	0.0	WOH-1.5', 2	0 00		No recovery, wash and scrap material
10	12	24*	2-1, 1-2		0 00	Brown-gray clayer Silt, trace fine sand, wet, soft.
12	14	15*	8-9, 8-8		1.1	Brown-gray silty fine to medium Sand, some gray silt, fine laminations, moist-wet,
14	16	12°	19-22, 70	0.00	1.1	Top 8° Brown-gray silty fine to medium Sand, some gray silt, fine languations, moist-
						wet, medium compact. Bottom 4°, Red-brown Silt, some fine sand, little fine gravel,
			·			moist, compact (Till-like).
	- · · ·		×			
				 .		
L	L	<u> </u>		L	<u></u>	

				S	AMPLE/	CORE L	0G					
	Boring/Well	SB	-1 Project	No	AY0146.00	2		·	Page	1	of _	1
	Site Location	Syracuse	China Landfill	Drilli	ng Started	12/5/9	4	Drilling (Completed		2/5/94	
	Total Depth I	Orilled	20	feet	Hole Diameter	66	inches		f Sample/ g Device	Split-S _[ioon Sa	ımpler_
	Length and D of Coring De		24" Split-Sp	oon/2-inch in	side diameter	-		Sampling Interval		2		feet
	Land-Surface Elevation	: 		foot		Surveyed [Estimated		Datum			
	Drilling Fluid	Used	None				Drilling	ng Method 3.25" F		Hollow-Stern Auger		ger
	Drilling Cont	ractor	Parratt-Wolf	<u>r</u>		Driller	G. Lansin	g	Helper	K. White	:	
	Prepared By	J. Gardne	<u>r</u>		~	127	Hammer Weight		Hammer Drop	30		inches
	Core Depth land surface To		Time/Hydraulic Pressure or Blows per 6 Inches	LEL Drill Cuttings	OVM Sampling		Sa	umple/Cor	e Descripti	ion		
0	2	8.	2-3, 3-3	0 00	0.00	White china scr						
2	4	22*	3-4, 6-5	0.00	0 00	Pink-tan-brows		ATHE IN Trace	silt ftsomen	14		
4	6	5,	3-2, 2-2	0.00	0.00	China scrap, gv						
6		20°	4-6, 6-3	0.00	000							
						Gypsum, fiberg						-,
	10	204	3-5, 4-4	0.00	0,00		lass mediation	conders, ref	ractory scrap,	wood fragm	ents,	
	 	-				black clayev m	sternal (odor)					
10	12	15*	8-3, 3-3	0.00	0 00	China scrap, go	psum, asulatio	on.				-
12	. 14	6			06	China scrap, go	osum. ensulatio	on.				
14	16	15"	1-2, 4-4	0 00	0.00	Top 2° gypsum	china scrap B	ottom 13° bi	own silt, little	e fine to me	dium sa	nd
	<u> </u>		ļ		ļ	moist, medium	compact.					
16	18	24*	8-6, 7-5	0.00	04	Brown-gray cla	wev silt. trace f	ine sand, me	oist, wet, med	ium compa	t	
18	20	24"	4-5, 4-3	0.00	0.6	Brown-gray cl	ever sik, trace f	line sand, me	oist, wet, med	lium compa	at (more	;
						clayey, wet).						
	1											
		-										
	1	†							· · · · · · · · · · · · · · · · · · ·			
	1											
	1		 	 	 	-						
	_		-	-	 	+						

Boring/Well	SB-2 Project No		AY0146.002				Page	1 of	1
Site Location Sy	racuse China Landfill	Drill	ing Started	12/5/94		Drilling C	Completed	12/6/	94
Total Depth Drillo	d <u>30</u>	feet	Hole Diameter	5	_ inches		Sample/ Device	Split-Spoon	Sampler
Length and Diame of Coring Device	ter24" Split-Spoon	2-inch in	side diameter		·	Sampling	interval	2	feet
Land-Surface Elevation		feet	Surveye	a [Estimated		Datum		
Drilling Fluid Use	d None				- Drilling	Method	3.25"	Hollow-Stem	Auger
Drilling Contracto	Parratt-Wolff		D	riller	O. Lansing		Helper	K. White	
Prepared By J. (Gardner				Hammer Weight	140	Hammer Drop	30	inches

Sample/C (feet below !	ore Depth and surface	Core	Fime/Hydraulic Pressure or	LEL		
From	To	Recovery (feet)	Blows per 6 Inches	Drill Cuttings	OVM Sampling	Sample/Core Description
		11111		Cuttings	Damping	Sample/Cure Description
0	2	3*	1.1, 2.3	0.0	0.0	China scrap, refractory scrap
2	4	20⁴	4-4,5-5	0.0	0.0	China scrap, gypsum, refractory scrap
4	6	18"	6-7, 7-5	0.0	0.0	China scrap, gypsum, refractory scrap
6	8	7*	2-3, 2-2	0.0	00	China scrap, gypsum, refractory scrap
- 8	10	8.	4-1, 2-3	0.0	00	China scrap, gypsum, refractory scrap
10	12	6*	2-1, 2-2	0.0	0.0	China scrap, gypsum, refractory scrap
12	14	4*	2-1, 1-6	0.0	0.0	Top 2° China scrap, gypsum, refractory scrap Bottom 2° brown silt, little fine
						sand, moist-wet, soft.
14	16	18*	6-1, 7-4	0.0	0.0	Brown-red Silt, little fine to medium sand, little medium to coarse gravel,
						wet, moist, soft.
16	18	0.0	50-50/3	00	<u> </u>	Gravel fragment in nose of spoon
18	20	16"	4-3, 2-2	0.0	0.0	Top 8° Brown-red Sift, little fine to medium sand, little medium to coarse gravel,
						wet, moist, soft. Bottom 8°; china scrap, gypsum, refractory scrap.
20	22	3*	2-3, 2-2	0.0	0.0	Silt, china scrap.
22	24	8.	2-2, 3-3	0.0	0.0	China scrap, silt, refractory scrap, gypsum.
24	26	8"	4-3, 2-2	0.0	0.0	China scrap, silt, refractory scrap, gypsum.
26	28	0.0	1-2, 7-8	0.0		Wet, china scrap fragments
28	30	2*	3-4, 5-6	0.0	0.0	Brown silty fine to medium sand, medium compact, moist.
			ļ			
					ļ	

Boring/Well	SB-3 Project No.		AY0146.00)2			Page	1	of <u>1</u>
Site Location Syrac	ruse China Landfill	_ Drilli	ng Started	12/5/	94	Drilling C	ompleted	12	15/94
Total Depth Drilled	24	_ feet	Hole Diameter	6	inches	Type of Coring	Sample/ Device	Split-Spo	on Sampler
Length and Diameter of Coring Device	24" Split-Spoon/	2-inch in	side diameter			Sampling	Interval	2	feet
Land-Surface Elevation		_ feet		Surveyed	Estimated		Datum		
Drilling Fluid Used	None				Drilling	Method	3.25"	Hollow-Ste	m Auger
Drilling Contractor	Parratt-Wolff			Drille	G. Lansing	8	Helper	K. White	
Prepared By J. Ga	urdner		V.		Hammer Weight	140	Hammer Drop	30	inches

	ore Depth and surface		lime/Hydraulic Pressure or Blows per 6	LEL Drill	OVM.	
From	То	(feet)	Inches	Cuttings	Sampling	Sample/Core Description
0	2	4"	3-4, 6-8	0.00	0.00	White china scrap, sopsum.
2	4	12°	4-4, 7-7	0.00	0.00	White china scrap, wet soft gypsum,
4	6	22°	6-4, 4-3	0.00	0.00	White china scrap, wet soft gypsum, refractory scrap.
6	8	10"	6-6, 8-9	0.00	0 00	China scrap, little gypsum, above 4° brown Silt, some fine to medium to coarse
						sand, china fragments incorporated in silt, medium compact.
-	10	20°	8-7, 4-4	0.00	0.00	White-tan china scrap, brown silt, gypsum.
10	12	6*	2-2, 2-2	0.00	0.00	Gypsum, black organic fragments (wood), refractory fragments.
12	14	5*	2-2, 3-3	0.00	0.00	Gypsum, black organic fragments (wood), refractory fragments.
14	16	10°	1-2, 1-2	0.00	0.00	China scrap, gypsum, black organics.
16	18		3-4, 4-5	0.00	000	Wood fragments, china fragments.
18	20	5*	3-2, 3-3	0.00	0.2	White-gray gypsum, china scrap, wood fragments.
20	22	18"	1-2, 2-1	0.00	0.00	China scrap (painted), gypsum, black organic silt, fabric, refractory pins (wet at 21').
22	24	20*	9-13, 18-17	0.00	0.00	Top 1° china fragments, Bottom 19° red-brown Silt, some fine to medium to
						coarse sand, trace fine gravel, compact
1					<u> </u>	
		 				

SAMPLE/CODE LOC

				3/	AMPLE/	COREL	UG		
	Boring/Well	SB	-4 Project	No	AY0146.00	2		Page	l of 1
	Site						· · · · · · · · · · · · · · · · · · ·	8*	
	Location _	Syracuse (China Landfill	Drillin	ng Started	12/2/5	04	Drilling Completed	12/2/94
	Total Depth [8	feet	Hole Diameter	2	inches	Type of Sample/ Coring Device	Split-Spoon Sampler
	Length and Do of Coring Des		24" Split-Sp	oon/2-inch ins	ide diameter			Sampling Interval	2 feet
	Land-Surface Elevation			feet		Surveyed	Estimated		
	Drilling Fluid	Used	None						ch Hollow-Stem Auger
	Drilling Contr	actor	Parratt-Wolf	Γ		Driller	G. Lansing	Helper	D. Waters
	Prepared By	J. Gardner					Hammer Weight	Hammer	
Sample/(feet below	Core Depth land surface To	Core Recovery (feet)	Time/Hydraulic Pressure or Blows per 6 Inches	t LEL Drill Cuttings	OVM Sampling	T	Sa	ample/Core Descrip	tion
	2	16"	2-3, 5-4	0.0	00	Top 3° china s	crap, above 13°	brown Silt, little fine to	medium sand, trace fine
	<u> </u>			 		gravel, china s	व्यक् रिक्ट्यालांड		
2	4	8"	2-3, 3-3		00	White-gray slu	dge		
4	6	18"	1-1, 2-3	00	00	Brown silt and	fine sand, trace	fine gravel, wet, medius	n compact.
6		30.	2-2, 3-5	<u> </u>	00	Brown silt and	fine sand, trace	fine gravel, wet, medium	n compact, little clay
						 			
	 								
						ļ			·
	 				<u> </u>				
				25					
			41						
		-							
						1			

Boring/Well	B-5 Project No.	AY0146	002	Page	1of1_
Site Location Syracus	e China Landfill	_ Drilling Started	12/2/94	Drilling Completed	12/2/94
Total Depth Drilled	14	Hole feet Diameter	6inches	Type of Sample/ Coring Device	Split-Spoon Sampler
Length and Diameter of Coring Device	24" Split-Spoon 7	2-inch inside diamete	f	Sampling Interval	2feet
Land-Surface Elevation		_fcet [Surveyed Estimated	Datum	
Drilling Fluid Used	None		Drilling	Method 4.25"	Hollow-Stem Auger
Drilling Contractor	Parratt-Wolff		Driller G. Lansin	g Helper	K. White
Prepared By J. Gard	ner		Hansmer Weight	Hammer 140 Drop	30 inches

Sample/Co		Core	lime/Hydraulic Pressure or	LEL		
From	T-	Recovery	Blows per 6	Drill	OVM	
From	To	(feet)	Inches	Cuttings	Sampling	Sample/Core Description
0	2	13*	2-3, 3-4	0.0	0.0	Top 4" organics, china acrap, silt above 6" brown sandy Silt, moist, medium
						compact above 3° pink-white studge and china scrap
2	4	22*	2-1, 1-2	0.0	0.0	Top 18" sludge above 4" black silt, trace of fine sand, moist, loose
4	6	22*	3-3, 4-4		<1	Brown clayer silt, little fine to medium sand, moist, medium compact, little
						china fragments.
- 6		20°	3-7, 9-11		1.0	Brown silty fine to medium Sand, little fine gravel, moist-wet, medium compact
8	10	-				NO SAMPLE TAKEN
10	12	18"	1-4, 5-5	0.0	00	Brown silty fine to medium Sand, little fine gravel, moist-wet, medium compact.
12	14	18"	13-16, 24-24		0.0	Brown silty fine to medium Sand, little fine gravel, moist-wet, medium compact
					 	
		<u> </u>			 	
					<u> </u>	
			12a			
		ļ				
	l		<u></u>			

Boring/Well	SB-6 Pr	oject No.		AY0146.0	002			Page	1d	1
Site Location Syra	cuse China Land	61t	Drilli	ing Started	12/	1/94	Drilling C	ompleted	12/14	94
Total Depth Drilled	6		feet	Hole Diameter	2	inches	Type of Coring	Sample/ Device	Split-Spoon	Sampler
Length and Diamete of Coring Device		it-Spoon/2	inch in	side diameter	· · · · · · · · · · · · · · · · · · ·		Sampling	Interval	2	fect
Land-Surface Elevation	Į.		feet	Е	Surveyed	Estimated		Datum		
Drilling Fluid Used	None					Drilling	Method	S	plit-Spoon onl	y
Drilling Contractor	Рагтац	Wolff			Drille	er G. Lansin	g	Helper	K. White	
Prepared By J. G	ardner					Hammer Weight	140	Hammer Drop	30	inches

Sample/Core Depth (feet below land surface) From To		Time/ilydraulic Core Pressure or Recovery Blows per 6 (feet) Inches		OVM Drill Cuttings	OVM Sampling	Sample/Core Description
0	2	4"	4-6, 2-2	0.00	0.00	China scrap.
2	4	14*	2-1, 1-1	0.00	0 00	Top 3° china scrap, middle 4° sludge, Bottom 7° brown-black silt, trace of fine
<u> </u>						sand, moist, medium compact
-						
ļ						
	-	1				
		<u> </u>			<u> </u>	
				1.0		
	ļ					
	<u> </u>					
	<u></u>		<u></u>			

Boring/Well	SB-7	Project No.		AY0146.00	2			Page	1 of	1
Site Location	Syracuse Cl	nina Landfill	_ Drill	ing Started	12/14	94	Drilling C	onvpleted	12/1/5	4
Total Depth D	Prilled	6	_ feet	Hole Diameter	2	inches	Type of Coring	•	Split-Spoon	Sampler
Length and Dr of Coring Dev		24" Split-Spoon/	2-inch ir	side diameter	•		Sampling	Interval	2	feet
Land-Surface Elevation	E		_feet		Surveyed	Estimated		Datum		
Drilling Fluid	Used	None				Drilling	Method	Sp	lit- Spoon Onl	y
Drilling Contr	ractor	Parratt-Wolff		····	Driller	G. Lansing		Helper	K. White	
Prepared By	J. Gardner					Harnmer Weight	140	Hammer Drop	30	inches

Sample/Core (feet below land	e Depth d surface) To	Core Recovery (feet)	Time/Hydraulic Pressure or Blows per 6 inches	OVM Drill Cuttings	OVM Sampling	Sample/Core Description
	2	7"	2-2. 2-2	0 00	0.00	China scrap.
2	4	0.0	4-6, 9-8	0.00	0.00	China scrap (ragment.
4	6	6'	2-1, 3-2	0 00	000	Black-brown silt, little fine sand, wet, loose
		 				
	· · · · · · · · · · · · · · · · · · ·					
					ļ	
					-	
					-	
					 	
		-				
					 	
			<u></u>	<u> </u>		

				Sr	AIVAL ESEA	COREL	U U				
	Boring/Well	SB-1	Project 1	No	AY0146.002	2			Page	1 of	1
	Site Location	Syracuse C	hine Landfill	Drillin	g Started	12/2/5)4	Drilling (12/2	
	Total Depth D	rilled		feet	Hole Diameter	2	inches		Sample/ Device	\$plit-Spoor	Sampler
	Length and Di- of Coring Devi		24° Split-Spo	on/2-inch insi	ide diameter			Samplin	interval	2	foot
	Land-Surface Elevation	•		feet		Surveyed	X Estimated		Datum	Mean sea le	•
	Drilling Fluid	Used	None				Drilling	Method		Spoon Sample	
	Drilling Contra	actor	Parratt-Wolff			Driller	G. Lansing	3	Helper	D. Waters	
	Prepared By	J. Gardner					Hammer Weight	140	Hammer Drop	30	incher
	/Core Depth w land surface To		Time/Hydraulic Pressure or Blows per 6 inches	OVM Drill Cuttings	OVM Sampling		S	iample/Ce	re Descrij	otion	
0	2	12*	1-2, 2-4	0.00	0 00	Gray-tan clay	cy sludge.		-		
2	4	20*	3-5, 6-7	0 00	0.00	Grav-tan clay	ev sludge, little	sılt			
4	6	10°	5-3, 3-5	0.00	0.00	Top 5° gray-t	an claves studge	, little sit.	enttom 5° bro	own silty fine sai	nd, moist,
		ē			W	soft, loose					
6	8	10"	6-8, 9-5	0 00	0 00	Brown silty (ine sand moist	soft, loose			
							<u> </u>				
			<u> </u>			<u> </u>	···				
	_	 							···		
		<u> </u>									
		ļ				ļ					
				ļ			-				
			<u> </u>								

				SAMPLE	CORE I	LOG						
E	Boring/Well	SB-9	Project No.	AY0146.0	02			Page	1			
	ite									- " -		
I	Location Syracuse China Landfill Dril		lling Started	12/2	/94	Drilling (Completed	12/2/94				
7	Total Depth Dri	illed		Hole Diameter	2	inches		Sample/ Device	Split-Sp	oon Si	ampler	
	ength and Dia f Coring Device		4" Split-Spoon/2-inch	inital at								
	and-Surface		4 Spitt-Spoots 2-inch	inside diameter			Sampling	Interval	2		feet	
E	levation		feet		Surveyed	Estimated		Datum	Mean sea	level		
	Drilling Fluid U		lone			Drilling	Method		plit-Spoon			
	Drilling Contrac	ctorF	arratt-Wolff		Driller	G. Lansing			K. White			
	repared by	J. Gardner				Hammer		Hammer				
_	· · · · · · · · · · · · · · · · · · ·	z. Oarunet		T ₁		Weight _	140	Drop	30		inches	
Sample/C (feet below l	ore Depth and surface)	Core	Time/Hydraulic Pressure or	OVM								
Prom	То	Recovery (feet)	Blows per 6	Drill	M/O							
o] ,			Cuttings	Sampling	T		ample/Co				
		 	1-3, 5-4	0.00	0 00	Top 1° organics a	above 4° wh	ite-gray slud	ge above 2°	ctena se	стар,	
2	1-1-	20*	3-4, 6-8	0.00	0 00	Top 12° sludge a	nd china scr	ap above 8°	brown silty f	ine san	d, moist,	compact
	6	6°	9-7, 4-3	0.00	0.00	Brown silty fine	sand, moist,	compact				
		- 										
	_											
				2								·
												
												
	 	-										
	-			ū.								
												
	 								····			
												
				-	 							

SAMPIE/CODE LO

			S	AMPLE	CORE 1	JOG				
Boring/Well	8B-10	Project No.		AY0146.0	02			Page	l of	1
Site Location Sys	racuse Ch	ina Landfill	_ Drill	ing Started	12/2	94	Drilling (Completed	12/2/	
Total Depth Drillo	d Samp	oled to 12 feet	_ feet	Hole Diameter	6	inches		Sample/ Device	Split-Spoon	Sampler
Length and Diamet of Coring Device	ler ——	24" Split-Spoon/	2-inch ir	sidediameter			Sampling	Interval	2	feet
Land-Surface Elevation			_ feet		Surveyed	Estimated		Datum		
Drilling Fluid Used		None				Drilling	Method		Sampler Only	
Drilling Contractor	•	Parratt-Wolff			Drille			Helper	K. White	
Prepared By J. (Gardner	······································		<u>-</u>		Hammer Weight	140	Hammer Drop	30	inches
	T Core covery	Inie/Hydraulic Pressure or Blows per 6	OVM Drill	OVM						

10	Sample/C (feet below i 	ore Depth and surface To	Core Recovery (feet)	Time/Hydraulic Pressure or Blows per 6 inches	OVM Drill Cuttings	OVM Sampling	
2 4 10" 2-2, 2-2 0.00 0.00 White-tan sludge 4 6 10" 2-3, 3-2 0.00 0.00 White-gray-brown sludge 6 8 20" 1-1, 2-2 0.00 0.00 White-gray-brown sludge 8 10 18" 1-1, 2-3 0.00 0.00 White-gray-brown sludge 10 12 18" 2-2, 4-9 0.00 0.00 Top 15" sludge, bottom 3" red silt, little fine to medium sand, trace fine gravel,							
4 6 10° 2-3, 3-2 0.00 0.00 White-gray-brown studge 6 8 20° 1-1, 2-2 0.00 0.00 White-gray-brown studge 8 10 18° 1-1, 2-3 0.00 0.00 White-gray-brown studge 10 12 18° 2-2, 4-9 0.00 0.00 Top 15° studge, bottom 3° red silt, little fine to medium sand, trace fine gravel,				1.2, 4.4	0.00	0 00	Brown silty sludge (renk-white clayey material)
6 8 20" 1-1, 2-2 0.00 0.00 White-gray-brown studge 8 10 18" 1-1, 2-3 0.00 0.00 White-gray-brown studge 10 12 18" 2-2, 4-9 0.00 0.00 Top 15" studge, bottom 3" red silt, little fine to medium sand, trace fine gravel,	2	4	10°	2-2, 2-2	0.00	0.00	White-tan sludge
8 10 18" 1-1, 2-3 0.00 0.00 White-grav-brown studge 10 12 18" 2-2, 4-9 0.00 0.00 Top 15" sludge, bottom 3" red salt, little fine to medium sand, trace fine gravel,	4	6	10°	2-3, 3-2	0.00	0 00	White-gray-brown studge
10 12 18° 2-2, 4-9 0.00 Top 15° sludge, bottom 3° red silt, little fine to medium sand, trace fine gravel,	66	1	20*	1-1, 2-2	0 00	0.00	White-gray-brown skudge
10p 15' sludge, bottom 3' red silt, little fine to medium sand, trace fine gravel,	- 8	10	18"	1-1, 2-3	0.00	0.00	White-gray-brown studge
medium compact, most (Till) medium compact,	10	12	18*	2-2, 4-9	0.00	0 00	Top 15° sludge, bottom 3° red silt, little fine to medium sand, trace fine gravel,
							
							

Boring/Well SB-	11 Project No		AY0146.0	002		 	Page	of	1
- · · · -	China Landfill	_ Drill	ing Started _	12/2	1/94	Drilling (Completed	12/2/	94
Total Depth Drilled	12	feet	Hole Diameter	2	inches		Sample/ g Device	Split-Spoon	Samoles
Length and Diameter of Coring Device	24" Split-Spoon	2-inch ir	side diameter				Interval	2	
Land-Surface Elevation		feet		Surveyed	Estimated		Datum	Mean sea lev	feet
Drilling Fluid Used	None			•	_ Drilling	Method		Spoon Sample	
Drilling Contractor	Parratt-Wolff			Drille			Helper	K. White	Chiy
Prepared By J. Gardner					Hammer Weight	140	Hammer Drop		inches

Sample/Core of below land From	surface) To	Core Recovery (feet)	Time/Hydraulic Pressure or Blows per 6 inches	OVM Drill Cuttings	OVM	
				Curings	Sampling	Sample/Core Description
0	2	6'	2-3, 8-8	0		White-gray sludge
2	4	3*	2-2, 1-2	0	0	Plant fragments sub-organics
4	6	NR	2-2, 3-3	0	0	No basket in spoon. Wet
6		8.	2-2, 2-2	0	0	Brown-gray claves salt, trace fine sand, sludge
8	10	NR	1-1, 2-2	0	0	
10				<u> </u>	· · · · · ·	No basket, wet spinon
10	12	12'	1-4, 10-14	0	0	Brown Six and Gravel, trace fine sand, little clay, wet.
					·	
			- N	**		
						
						-

WELL CONSTRUCTION LOG (UNCONSOLIDATED)

	Project AY0146.002 Well MW-41
∏ ↑ 1.7 ft.	Town/City Syracuse
Land Surface	County Onondaga State NY Permit No.
Edito Odriace	
8 inch diameter	Land-Surface Elevation and Datum 383.91 feet X Surveyed
drilled hole	X ouveyed
	USGS Estimated Installation Date(s) 11/29/94 and 11/30/94
Well Casing	Drilling Method 4 1/4" Hollow Stem Auger
2 inch diameter,	Drilling Contractor Parratt Wolff
PVC	Drilling Fluid None
	TVOITS
	Development Technique(s) and Date(s)
Backfill	Bailer, 12/6/94
X Grout 95/5	
10.5 ft.*	Fluid Loss During Drilling None gallons
	Water Removed During Development 4.5 gallons
Bentonite slurry	Static Depth to Water 15.57 feet below M.D.
12.5 ft.* x pellets	Pumping Depth to Water Dry feet below M.P.
	Pumping Duration 0.25 hours
13.0 ft.*	Yield gpm Date 12/6/94
Well Screen	Specific Capacity gpm/ft.
2 inch diameter	Well Purpose Monitoring Well
Gravel Pack	
Gravel Pack X Sand Pack Formation Collapse	Donald Till 1464
Formation Collapse	Remarks Till at 10 feet. Red/brown very turbid water.
I I officiation collapse	Well recharging very slowly.
18.0 ft.	
Measuring Point is	
Top of Well Casing	
Unless Otherwise Noted.	
* Depth Below Land Surface	Prepared by J. Gardner
•	Tourdior

WELL CONSTRUCTION LOG (UNCONSOLIDATED)

	Project <u>AY0148.002</u>	Nell MW-6
	Town/City Syracuse	
1.9 ft.	County Onondaga State	NY
Land Surface	Permit No.	
	Land-Surface Elevation	
8 inch diameter	and Datum 413.14 feet	X Surveyed
drilled hole	USG\$	Estimated
	Installation Date(s) 11/28/94	
Well Casing	Drilling Method 4 1/4" Hollow Stem Au	er
2 inch diameter,	Drilling Contractor Parratt Wolff	, , , ,
PVC	Drilling Fluid None	· · · · · · · · · · · · · · · · · · ·
	Development Technique(s) and Date(s)	
Backfill	1 1/2" Whaler Pump	
X Grout 95/5		
2.0 ft.*	Fluid Loss During Drilling None	gallons
2	Water Removed During Development 35	
Bentonite Slurry	1 0 1 1 0 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	eet below M.P.
4.5 ft.* x pellets	Pumping Depth to Water 14.0	eet below M.P.
	Pumping Duration 3 total hours	eet below IVI.P.
5.0 ft.*	Yield max 1.5 gpm Date 12/6/9	4 40/7/04
	Specific Capacitygpm/ft.	4, 12///94
Well Screen	gpilling.	
2 inch diameter	Well Purpose Monitoring Well	
PVC 10 slot	Working Well	
Gravel Pack		
X Sand Pack	Remarks Water clearing after approving	antalı.
Formation Collapse	trater eleganing after approxim	nately
2 inch diameter PVC 10 slot Gravel Pack X Sand Pack Formation Collapse 15.0 ft.	25 gallons pumped from well	
15.0 ft.		
15.5 ft.		
Measuring Point is		
Top of Well Casing		
Unless Otherwise Noted.		
* Depth Below Land Surface	Prepared by	
Fill Bolott Calla Outlace	Prepared by J. Gardner	

WELL CONSTRUCTION LOG

(UNCONSOLIDATED)

	Project AY0146.002	Well MW-7
□↑ 1.64 ft.	Town/City Syracuse County Onondaga Sta	ate NY
Land Surface	Permit No.	ne NY
	Land-Surface Elevation	
8 inch diameter	and Datum 393.21 feet	X Surveyed
drilled hole	USGS	Estimated
	Installation Date(s) 12/1/94	<u></u>
Well Casing	Drilling Method 4 1/4" Hollow Stem	Auger
2 Inch diameter,	Drilling Contractor Parratt Wolff	
PVC	Drilling Fluid None	
	Douglasmant Tasksis (1) and D. (1)	
Backfill	Development Technique(s) and Date(s) 1 1/2" Whaler Pump	
X Grout 95/5	I 1/2 VVIIalei Punip	
33.0		
2.0 ft.*	Fluid Loss During Drilling None	gallons
	Water Removed During Development	23 gallons
Bentonite slurry	Static Depth to Water 4.64	feet below M.P.
4.0 ft.* x pellets	Pumping Depth to Water 14.5	feet below M.P.
	Pumping Duration 2 ho	urs
5.0 ft.*	Yield max 1.5 gpm Date 12/	6/94
Well Comes	Specific Capacitygpm/ft.	
Well Screen 2 inch diameter	Mall Burners	
PVC 10 slot	Well Purpose Monitoring Well (shallow)	·
1 1 10 10 NOT		
Gravel Pack		
X Sand Pack	Remarks Water cleaning after appro	nyimately
X Sand Pack Formation Collapse	20 gallons removed.	Annatory
15.0 ft.		
15.0 ft.		
10.0 11.		
Measuring Point is		
Top of Well Casing		
Unless Otherwise Noted.		
* Depth Below Land Surface	Prepared by J. Gardner	

APPENDIX B

SURFACE-WATER SAMPLING LOGS

Project/No.	AY0146.013				Page 1	of 1
Site Location	Syracuse, New Yo	rk			Date	12/7/94
Site/Well No.	PSW-6		Coded/ Replicate No.			
Weather	25 degrees, snow	ing	Time Sampling Began	9:20	Time Sampling Completed	-
			EVACUATIO	N DATA		
Description of M	leasuring Point (MP)		Grab sample str	eam		
Height	of MP Above/Below Lan	d Surface	101	MP Elevation		
Total S	Sounded Depth of Well I	Below MP		Water-Level Eleva	tion	
Held	Depth to Water I	Below MP	91	Diameter of Casin	a	
Wet	Water Colun	nn in Well	× ×	Gallons Pumped/B Prior to Sampling	ailed	
	Gallons	s per Foot				
	Gallo	ns in Well		Sampling Pump In (feet below land s	take Setting urface)	
Evacuation Met	hod					
		SAMDI	INC DATA/EI	ELD PARAMETI		
		SAMIFE	ING DATA/FI	ELD PARAIVIETI	EN S	
Color Clear	Odor None		Appearance		Temperature	11.1 °C
Other (specific i	on; OVA; HNU; etc.)	1	Turbidity < 50			
Specific Conduc	ctance, umhos/cm	410		pH	5.77	
Sampling Metho	od and Material	C ean gla				
			Container Desc	ription		
Constituents	Sampled	From Lab		G&M	Prese	rvative
Metal		500 mL	plastic			HNO ₃
Cyanide						
		500 mL p	olastic		-	NaOH
VOCs		40 mL gla	ass			None
Remarks						
Sampling Perso	nnel J. Gardne	er		-		
	<u> </u>					
	GAL./FT. 1-1-4 = 0.0	16	WELL CASING		4.	
	1-1/2" = 0.0		2-1/2" = 0.26	3° 0 37 3-1/2° - 0.50	4° C 65 6° = 1.47	

Project/No.	AY0146	.013				Page 1	of 1
Site Location	Syracuse	, New Yo	·k			Date	12/7/94
Site/Well No.	PSW-6			Coded/ Replicate No.		***************************************	
Weather	25 degre	es, snowi	ng	Time Sampling Began	1:15	Time Sampling Completed	
				EVACUATIO	N DATA		
Description of M	easuring Point	(MP)		Culvert at Facto	ory Ave.		
Height o	of MP Above/E	Below Land	i Surface		MP Elevation		
Total S	ounded Depth	of Well 8	elow MP		Water-Level Elev	vation	
Held	_ Depth t	to Water B	elov/ MP		Diameter of Cas	100	×
Wet	_ Wa	ater Colum			Gallons Pumped Prior to Sampling	/Bailed	
		Gallons	per Foot		Compile C		
		Gallor	is in Well		Sampling Pump (feet below land	Intake Setting surface)	
Evacuation Meth	od						
			SAMPLI	NG DATA/FI	ELD PARAMET	TERS	
Color Clear	Odor 1	Vone		Appearance		Temperature	5 "C
Other (specific ic	on; OVA; HNU	; etc.}	Turbdity <	50			
			·				
Specific Conduct	ance, umhos/	cm	440		_ PH_	5.77	
Sampling Method	d and Material		Clean glas	s jar			
				Container Desc	ription		
Constituents S	ampled		From Lab	X or	G&M	Preser	vative
Metal			500 mL p	lastic	7.		HNO ₃
Cyanide			500 mL pl	astic			NaOH
VOCs			40 mL gla	ss	•		Vone
Remarks							
Sampling Person	nel	J. Gardner					
			·	WELL CASH	VO		
	GAL./FT. 1	·1/4" = 0.06		WELL CASING	VOLUMES 3° = 0° 37	A* - A c*	
	1	-1/2" = 0.09		2-1 2° + 0 26	3-1/2" 6 50	4" = 0 65 6" = 1,47	

Project/No.	AY0146.013			Page 1	of1
Site Location	Syracuse, New Yor	k		Date	12/7/94
Site/Well No.	PSW-7	Coded/ Replicate N	lo.		
Weather	25 degrees, snowin	Time Samp ng Began	10 30	Time Sampling Completed	
		EVACUA	ATION DATA		Š.
Description of Me	asuring Point (MP)	Grab pond	1		
Height of	MP Above/Below Land	i Surface	MP Elevation		
Total So	unded Depth of Well B	elow MP	Water-Leve Eleva	tion	
-leld	Depth to Water B	elow MP	Diameter of Casin	9	
Wet	Water Colum	nn in Well	Gallons Pumped/B Prior to Sampling		
	Gallons	per Foot	Sampling Pump In	unka Sattina	
	Gallo	ns in Well		surface)	
Evacuation Metho	od				
Color Clear	Odor None	SAMPLING DAT	A/FIELD PARAMET		4 °C
Other (specific io	n; OVA; HNU; etc.)	SC = 345 pH = 5. Turbidity < 50	82		· · · · · · · · · · · · · · · · · · ·
Specific Conduct	ance, umhos/cm	345	Ha	5.82	
Sampling Method	d and Material	Decon-glass jar			
Constituents S	ampled	Container	Description or G&M	Prese	rvative
Metal		500 mL plastic			HNO ₃
Cyanide		500 mL plastic			NaOH
VOCs		40 mL glass			None
Remarks					
Sampling Person	nel J. Gardne	er			
	GAL./FT. 1-1/4" = 0.0	WELL CA	SING VOLUMES		

Project/No.	AY0146.013					Page 1	of	1
Site Location	Syracuse, New Yo	ork				Date	 12/7/ 94	
Site/Well No.	PSW-8		Coded/ Replicate No.	DUP				
Weather	25 degrees, snow	ing	Time Sampling Began	10:30		Time Sampling Completed	· · · · · · · · · · · · · · · · · · ·	
			EVACUATIO	N DATA	1			
Description of Me	easuring Point (MP)		Grab - from pon	d				
	f MP Above/Below Lar		-	MP Elevation				
	ounded Depth of Well			Water-Level Elevat				
Held	_ Depth to Water	Below MP		Diameter of Casing	•			
Wet	_ Water Colum			Gallons Pumped/Ba Prior to Sampling	ailed			
	Gallon	s per Foot		Sampling Burns (
	Gallo	ns in Well		Sampling Pump Int (feet below land su	ake Se urfacei	etting		
Evacuation Metho	od							
		SAMPLI	NG DATA/FII	ELD PARAMETE	RS			
Color Clear	Odor None		Appearance	***************************************		Temperature	12	"C
Other (specific io	n; OVA; HNU; etc.)	Turbidity •	< 50					
Specific Conduct	ance, umhos/cm	390		PH	6.09			
Sampling Method	and Material	Clean glas	s jar					
			Container Descr	iption				
Constituents S	ampled	From Lab	X or	G&M		Preserv	ative	
Metal		500 mL p	lastic			н	NO ₃	
Cyanide		500 mL pl	astic				вОН	
VOCs		40 mL gla	ss					
Remarks						IV	one	
Sampling Personr	nel J. Gardne	r						···-
			· · · · · · · · · · · · · · · · · · ·	40				
			WELL CASING	VOLUMES			_	
	GAL./FT. 1-1/4" = 0.0	6	2° 0.16	3° 0.37		4" + 0.65		
	1-1,2° ± 0.0	9	2-1/2* = 0.26	3-1/2" + 0.50		6° = 1.47		

Project/No.	AY0146.0	013				Page 1	-1	
Site Location	Syracuse,	New Yo	rk			Date	of	
Site/Well No.	PSW-9			Coded/ Replicate No.			12/7/94	P*
Weather	25 degree	es, snowi	ng	Time Sampling Began	12:30	Time Sampling Completed		
December of M				EVACUATION				
Description of M				Grab sample fro	om Pond 3			
	of MP Above/Be				MP Elevation			
Total S Held	ounded Depth (Water-Level Eleva	tion		
11610	_ Depth to	Water E	Below MP		Diameter of Casin	9		
Wet	_ Wai		n in Well		Gallons Pumped/B Prior to Sampling			
		Gallons	per Foot		Sampling Pump In	taka Sattina		
		Gallor	ns in Well		(feet below land s	urface)		
Evacuation Meth	od							
			SAMPL	ING DATA/FI	ELD PARAMETE	ERS		
Color Clear	Odor No	one		Aspearance		Temperature	12	"C
Other (specific ic	on; OVA; HNU;	etc.)	Turbidity	< 50				C
		 -						
Specific Conduct	ance, umhos/c	m	250		_ pH_	6.1		
Sampling Method	d and Material		Clean glas	s _j ar				
_				Container Desc	ription			
Constituents S	ampled		From Lab	X or	G&M	Preser	vative	
Metal			500 mL p	lastic		H	INO ₃	
Cyanide			500 mL pl	astic				
VOCs			40 mL gla	ss			aOH Ione	
Remarks			······································				ione	
Sampling Person	nel J.	Gardner						
				WELL CASING	VOLLIMES			
		/4° = 0.06		2" + 5,16	VOLOMES 3° ± 6 _: 37	4° = 0.65		
	1.1	/2" = 0.09		2-121 126	3-1/2" - 0.50	6° = 1.47		

Project/No.	AY0146.013				Page 1	_ of _	1
Site Location	Syracuse, New Y	ork			Date	12/7/94	
Site/Well No.	PSW-10		Coded/ Replicate No.				
Weather	25 degrees, snow	ring	Time Sampling Began	11:30	Time Sampling Completed		
	54.		EVACUATIO	N DATA			
Description of Me	asuring Point (MP)	G	rab pond 4				
Height of	MP Above/Below La	nd Surface		MP Elevation			_
Total So	unded Depth of Well	Below MP		Water-Level Elevatio			
Held	Depth to Water	Below MP		Diameter of Casing			
Wet	Water Colu	nın in Well		Gallons Pumped/Bail Prior to Sampling			
	Gallor	s per Foot		6			
	Galle	ons in Well		Sampling Pump Intal	ke Setting face)		
Evacuation Metho	od						
Color Clear	Odor None	SAMPLI	NG DATA/FI	ELD PARAMETER	Tomas	12	°С
Other (specific ion	n; OVA; HNU; etc.)						
Specific Conducta	ance, umhos/cm	380		pH	6.16		
Sampling Method	and Material	Clean glas	s jar				
			Container Desc	ription			
Constituents Sa	ampled	From Lab	X or	G&M	Preserv	vatīve	
Metal		500 mL p	lastic			NO ₃	
Cyanide		500 mL pl	astic	7,17,17	N	aOH	
VOCs		40 mL gla	ss	·		lone	
Remarks					4		
Sampling Personr	nel J. Gardn	er	*				
			WELL CASING	VOLUMES		_	
	GAL./FT. 1-1/4" = 0.	06	2" = 0.16	3* = 0.37	4" = 0.65		

roject/No.	AY0146.	013				Page 1	of	1
ite Location	Syracuse	, New York				Date	12/7/94	
ite/Well No.	PSW-12			Coded/ Replicate No.				
eather .	25 degre	es, snowing	3	Time Sampling Began	2:00	Time Sampling Completed		
				EVACUATIO	N DATA			
scription of Me	asuring Point	(MP)		Stream grab sa	mple			
Height o	f MP Above/6	Below Land	Surface		MP Elevation			
Total Sc	ounded Depth	of Well Be	low MP		Water-Level Elevation	n		
əld	Depth	to Water Be	low MP		Diameter of Casing			
Vet Water Column in Well			n in Well		Gallons Pumped/Baile Prior to Sampling	ed		
			per Foot		Sampling Pump Intal	ke Setting lace)		
vacuation Meth								
olor Clear		None J; etc.)		Appearance		Temperature	12	,c
Specific Conduc	tance, umhos	s/cm	380		рН	6,2	-	
Sampling Metho	d and Materia	al	Clean gla	iss jar				
				Container Des	cription			
Constituents S	Sampled		From Lai	<u> </u>	r G&M	Prese	rvative	
Metal		_	500 mL	plastic		W	HNO ₃	
yanide		-	500 mL	plastic			NaOH	
/OCs	·	_	40 mL g	lass			None	
Remarks		"a						
Sampling Persor	nnel	J. Gardner				1		
				WELL CACINI	3 VOLUMES			
	GAL./FT.	1-1/4" = 0.06	•	WELL CASING	3" = 0.37	4" = 0.65		
		1-1/2" = 0.08		2-1/2" = 0.26	3-1/2" = 0.50	5" = 1.47		

Project No.		AY01	46.017	· · · · · · · · · · · · · · · · · · ·	Page 1	of	1
Site Location		Syracuse China.	Syracuse, New Yo	rk	Date	8/17/95	
Site Well No.		SW-1	Coded Replicate No				
Veather	90°		Time Sampling Began	3,50	Time Sampling Completed		
			EVACUATIO	N DATA			
Description of Me	easuring Point (MP)	Stream				
Heig	tht of MP Above Be	elow Land Surface		MP Elevation			
Tota	al Sounded Depth o	of Well Below MP		Water-Level Elevation		·····	
leld		Water Below MP		Diameter of Casing			_
Vet	at	er Column in Well		Gallons Pumped Baile Prior to Sampling	d		
		Gallons per Foot					_
		Gallons in Well		Sampling Pump Intake (feet below land surfa-			
Evacuation Metho	od Čle	ar glass jar lab bonl	es				
Color Clear Other (specific ion	r Odor n: OVA; HNU; etc	None	Appearance	Clear	Temperature	C	
		Turbidis	= 7 7 N'IUs			£0	_
Specific Conducts	ance, umhos em	675		PH	7 o		
Sampling Method	d and Material						
Constituents Sa	ampled	From Lab	Container Descr	nption r G&M		* 010	
		i Tom Lab			Preser	vative	
AL - Total Inorg	ganics		500 ml plas	tic	Н	NO ₃	
Cyanide			500 ml plas	stic	N	аОН	
Remarks							
Sampling Person	inel J. (Gardner L. Westbay			2		_
			WELL CASI	NG VOLUMES		_	
	GAL./FT. 1-1	/4° = 0.06 /2° = 0.09	2° = 0.16	3° = 0.37	4* = 0.66		
	1-1	12 = U.US	2-1.2" + 0.26	3-1/2" = 0.50	6° = 1.47		

Project/No. AY0	146.017	***	Page	of1
Site Location Syracuse China	a, Syracuse, New Yo	ork	Date	8/1 <i>7/</i> 95
Site Well No SW-2	Coded Replicate No.			
Weather	Time Sampling Began	1 10	Time Sampling Completed	5.00
	EVACUATIO		Completed	3.00
Description of Measuring Point (MP)	Stream			
Height of MP Above Below Land Surface		MP Elevation		
Total Sounded Depth of Well Below MP		Water-1 evel Elevation		
Held Depth to Water Below MP		Diameter of Casing		
Wet ater Column in Well		Gallons Pumped Bailed Prior to Sampling		
Gallons per Foot		Compliant Development		
Gallons in Well		Sampling Pump Intake S (feet below land surface)	etting	
Evacuation Method				
Color Water Clear Odor Sewage Other (specific ion; OVA; HNU; etc.)	Appearance	Clear	Temperature	C
Turbidity	- 8.11		·	
Specific Conductance, umhos cm 400		PII	31	
Sampling Method and Material	92			
Constituents Sampled From Lab	Container Descri	option G&M	Presen	vative
TAL - Total Inorganics	500 ml plast	tic	н	NO ₃
Cyanide	500 ml plast	tic	N	аОН
Remarks	500 ml plast	tic	N:	
		tic	N:	

Project/No.	AYO	146.017		Page 1 of			
Site Location	Syracuse China	i, Syracuse, New Yo	ık	Date	8/17/95		
Site/Well No	SW-2A	Coded Replicate No.					
Weather	Clear, 90's	Time Sampling Began	5.00	Time Sampling Completed	5:15		
		EVACUATIO	N DATA				
Description of Me	easuring Point (MP)	Stream	······································				
Heig	tht of MP Above Below Land Surface		MP Elevation				
Tota	il Sounded Depth of Well Below MP		Water-Level Elevation	on			
eld	Depth to Water Below MP		Diameter of Casing				
Vet	ater Column in Well		Gallons Pumped Ba Prior to Sampling		 		
	Gallons per Foot		Sampling Pump Inta	ale. Canan			
	Gallons in Well		(feet below land sur				
Evacuation Metho	nd						
oner (specific to	n, OVA; HNU; etc.) Turbidity	v = 43 8					
Specific Conduct	ance, umhos em 500)		7.21			
Sampling Method	d and Material						
		Container Descr					
Constituents Sa	ampled From La	ıb <u>X</u> ο	r G&M	Prese	native		
Lead		500 ml plas	stic	<u>+</u>	fNO ₃		
Remarks							
Sampling Person	inel J. Gardner L. Westba	Ņ.					
		WELL CASI	NG VOLUMES		-		
	GAL./FT. 1-1/4" = 0.06 1-1/2" = 0.09	2" = 0.16	3* = 0.37	4° = 0.65			
	1-1/2 = 0.08	2-1/2" = 0.26	3-1/2° = 0.50	6" = 1,47			

Project No.			AYOI	46.017			l'age 1	of I
Site Location		Syrac	use China.	Syracuse, New Yo	rk		Date	8/17/95
Site Well No.		SW-3		Coded Replicate No.				
Weather	90's		*	Time Sampling Began	5 20		Time Sampling Completed	5:35
				EVACUATIO	N DATA	9		
Description of Mea	suring Point	(MP)		Stream				
	t of MP Abo				MP Elevation			
	Sounded De	pth of Well B	Below MP		Water-Level Elev	ation		
Held	Dep	th to Water F	lelow MP	· · · · · · · · · · · · · · · · · · ·	Diameter of Casi	-		
Wet		ater Colum			Gallons Pumped Prior to Sampling			
		Gallons	s per Foot		Sampling Pump	Intake Sett	no	
		Gallor	is in Well		(feet below land s			
Evacuation Method	ı							
Color Water Cle	ar Odor			NG DATA/FIE	ELD PARAMET		Temperature	30° C
Other (specific ion,	OVA; INU	etc)					-	
			Turk Jity	50				
Specific Conductor	nce, umhos cr	n	650		— pH.	7.29		
Sampling Method	and Material			W-421-7		<u></u>		
Constituents Sam	npled		From Lab	Container Descri	ption G&M		Preser	vative
TAL - Total Inorga	nics			500 ml plas	tic		Н	NO ₃
Cyanide				500 ml plas	tic		N	aOH
D I								
Remarks								
Sampling Personne	el	J. Gardner L	Westbay		· · · · · · · · · · · · · · · · · · ·			
	GAL./FT.	1-1.4" = 0.06		WELL CASI	NG VOLUMES		4° = 0.65	
		1-1/2" = 0.09		2-1,2" = 0.26	3-1/2" = 0.50		6" = 1,47	

Project No.	AY0146.017			l'age 1 of		
Site Location	Syracuse China	, Syracuse, New Yo	rk	Date	8/17/95	
Site Well No.	SM.⁴	Coded Replicate No				
Weather	Sunny, 90's	Time Sampling Began	5 40	Time Sampling Completed	6.00	
_ = =		EVACUATIO	N DATA			
Description of Mo	easuring Point (MP)	Stream			· · · · · · · · · · · · · · · · · · ·	
	tht of MP Above Below Land Surface		MP Flevation			
	al Sounded Depth of Well Below MP		Water-Level Elevation			
Held	Depth to Water Below MP		Diameter of Casing			
Wet	ater Column in Well		Gallons Pumped Bailed Prior to Sampling			
	Gallons per Foot Gallons in Well		Sampling Pump Intake Se (feet below land surface)	_		
Evacuation Metho	od		,			
		NO DATA (ELE	10.04044555			
	SAIVIFLI	NG DATA/FIE	ELD PARAMETERS			
Color Clear W	ater Odor None	Appearance	Clear	Temperature	28° C	
Other (specific ion	n; OVA; HNU, etc.)					
	Turbidity	= 38,5				
Specific Conducts	ance, umbos em 480		ր 11 7 -	15		
Sampling Method	Land Material	· · · · · · · · · · · · · · · · · · ·	·			
,						
Constituents Sa	impled From Lab	Container Deseri				
	•		G&M	Preser	vative	
TAL - Total Inorg	ganics	500 ml plas	tic	Н	NO ₃	
Cyanide		500 mt plas	tic	и	аОН	
Remarks						
Sampling Persons						
Sampling Persons	nel J. Gardner/L. Westbay					
		WELL CASI	NG VOLUMES		_	
	GAL./FT. 1-1/4" = 0.06	2° = 0.16	3° = 0.37	4" = 0.65		
	1-1/2* = 0.09	2-1/2" = 0,26	3-1/2" = 0.60	6" = 1.47		

Description of Measuring Point (MP) Stream Height of MP Above Relow Land Surface Total Sounded Depth of Well Below MP Beld Depth to Water Below MP Gallows Pumped Bailed Proof to Sampling Wet after Column in Well Gallows per Foot Gallows in Well Gallows in Well Sampling Pump Intake Setting (feet below land surface) SAMPLING DATA/FIELD PARAMETERS Color Orange Clear Oldor None Appearance Stagmant organe Temperature 22° C Other (specific ion; OVA, HSU, etc.) Turbidity = 45.1 Specific Conductance, umbus em 570 pil 1 18 Sampling Method and Material Constituents Sampled From Lab X or Gi&M Presentative Lead 500 int plastic HNOs. WELL CASING VOLUMES WELL CASING VOLUMES	Project No.	^	AY0146.01°			of 1
Sweather Sunny, 90% Sweather Time Sampling Began 5-40 Completed 5-50	Site Location	Syracuse Cl	nina, Syracuse, New Yo	rk	Date	8/17/95
Sunns, 90's Regan 5-40 Completed 5-50	Site Well No.	SW-4A				
Description of Measuring Point (MP) Height of MP Above Below Land Surface	Weather	Sunns, 90's		5:40	-	5-50
Height of MP Above Below Land Surface MP Elevation Total Sounded Depth of Well Below MP Duameter of Casing Gallons Pumped Bailed Prior to Sampling Pump Intake Setting (Sallons in Well Creet below land surface) Exacuation Method SAMPLING DATA/FIELD PARAMETERS Color Orange Clear Odor None Appearance Stagnant organic Temperature 22" Cother (specific ion; OVA, HNU, etc.) Turbidity = 45.1 Specific Conductance, umbos cm 570 pH 7.18 Sampling Method and Material Constituents Sampled From Lab X or G&M Preservative Lead 500 ml plastic HNOs. Remarks Sampling Personnel J. Gardner L. Westbay WELL CASING VOLUMES	Description of M	Joseph Point (MD)		N DATA		- 55
Total Sounded Depth of Well Below MP						
Held Depth to Water Below MP Dameter of Casing Gallons Pumped Bailed Prior to Sampling Gallons per Foot Sampling Pump Intake Setting (teet below land surface) Exacuation Method SAMPLING DATA/FIELD PARAMETERS Color Orange Clear Odor None Appearance Stagnant organic Temperature 22° Cother (specific ion; OVA, HNU, etc.) Turbidity = 45.1 Specific Conductance, unhos em 570 pll 7.18 Sampling Method and Material Constituents Sampled From Lab X or G&M Preservative Lead 500 ntl plastic HNO ₃ Remarks Sampling Personnel J. Gardner L. Westbay WELL CASING VOLUMES				MP Elevation		
Wet ater Column in Well Prior to Nampling Gallons per Foot Sampling Pump Intake Setting (feet below land surface) SAMPLING DATA/FIELD PARAMETERS Color Orange Clear Odor None Appearance Stagnant organic nutters sheen on surface Turbidity = 45.1 Specific Conductance, unhos em 570 pll 1 is Sampling Method and Material Constituents Sampled From Lab X or G&M Preservative Lead 500 nul plastic HNO ₃ WELL CASING VOLUMES WELL CASING VOLUMES			····	Water-Level Elevation		
Gallons per Foot Sampling Pump Intake Setting (feet below land surface) SAMPLING DATA/FIELD PARAMETERS Color Orange Clear Oldor None Appearance Stagnant organic matter, sheen on surface Turbidity = 45.1 Specific Conductance, unhos cm 570 pll 7.18 Sampling Method and Material Constituents Sampled From Lab X or G&M Preservative Lead 500 ml plastic HNO, Remarks Sampling Personnel J. Gardner L. Westbay WELL CASING VOLUMES	Held	Depth to Water Below I	MP			
Sampling Pump Intake Setting (feet below land surface)	₩et	ater Column in W	/ell		:d	
SAMPLING DATA/FIELD PARAMETERS Color Orange Clear Odor None Appearance Stagnant organic matter, sheen on surface Temperature 22° C Other (specific ion; OVA, HNII, etc.) Turbidity = 45.1 Specific Conductance, umbos cm 570 pH 7.18 Sampling Method and Material Container Description Constituents Sampled From Lab X or G&M Preservative Lead 500 ml plastic HNO ₃ Remarks Sampling Personnel J. Gardner/L. Westbay WELL CASING VOLUMES		Gallons per F	ool			
SAMPLING DATA/FIELD PARAMETERS Color Orange Clear Odor None Appearance Stagnant organic matter, sheen on surface Other (specific ion, OVA, HNU, etc.) Turbidity = 45.1 Specific Conductance, umhos cm 570 pll 18 Sampling Method and Material Container Description Constituents Sampled From Lab X or G&M Preservative Lead 500 ml plastic HNO3 Remarks Sampling Personnel J. Gardner/L. Westbay WELL CASING VOLUMES		Gallons in W	/ell			
Color Orange Clear Odor None Appearance Stagnant organic matter, sheen on surface Turbidity = 45 1 Specific Conductance, umbos cm 570 pH 718 Sampling Method and Material Container Description Constituents Sampled From Lab X or G&M Preservative Lead 500 ml plastic HNO3 Remarks Sampling Personnel J. Gardner/L. Westbay WELL CASING VOLUMES	Evacuation Meth	nud				
Sampling Method and Material Container Description Constituents Sampled From Lab X or G&M Preservative Lead 500 ml plastic HNO3 Remarks Sampling Personnel J. Gardner L. Westbay WELL CASING VOLUMES		on; OVA, HNU; etc.)				C
Constituents Sampled From Lab X or G&M Preservative Lead 500 ml plastic HNO3 Remarks Sampling Personnel J. Gardner-L. Westbay WELL CASING VOLUMES	Specific Conduc	ctance, umhos em	570	pil	7.18	
Constituents Sampled From Lab X or G&M Preservative Lead 500 ml plastic HNO3 Remarks Sampling Personnel J. Gardner-L. Westbay: WELL CASING VOLUMES	Sampling Metho	od and Material				
Remarks Sampling Personnel J. Gardner L. Westbay WELL CASING VOLUMES	Constituents S	Sampled From		•	Preser	native
Sampling Personnel J. Gardner/L. Westbay WELL CASING VOLUMES	Lead		500 ml pla	stic	1-	INO ₃
Sampling Personnel J. Gardner/L. Westbay WELL CASING VOLUMES		<u> </u>				
WELL CASING VOLUMES	Remarks	20				
GAL/FT	Sampling Perso	nnel J. Gardner/L. Wes	tbay			
11A1 /P1 114* 000 01 010		CALGE		NG VOLUMES		-
2 = 0.16 3° = 0.37 4° = 0.65 1-1/2° = 0.09 2-1/2° = 0.26 3-1 2° = 0.50 6° = 1.47			2° = 0.16 2-1/2° = 0.26	3° = 0.37	4" = 0.65	

Project/No.	AY0146 017			Page 1	_ of _ I		
Site Location		Syracı	ise China,	Syracuse, New Yo	rk	Date	8/17/95
Site Well No.		SW-5		Coded Replicate No	-	-	
Weather	90's			Time Sampling Began	6 20	Time Sampling Completed	6 40
5				EVACUATIO	N DATA		
Description of Mea	sumng Point (MP) _		tream			
		e Below Land			MP Elevation		
		th of Well Bo			Water-Level Elevat	ion	
Held	Dept	h to Water Bo	low MP		Diameter of Casing	***************************************	
W'et		ater Column	in Well		Gallons Pumped Barior to Sampling	ailed	
			per Foot				#
			s in Well		Sampling Pump Int (feet below land su		
Evacuation Method	s		_				
		S	AMPLI	NG DATA/FIE	ELD PARAMET	ERS	
Color Clear	Odor	None		Appearance	Clear	Temperature	27"C
Other (specific ion:	OVA; HNU;	cic_)					
		<u></u>	Turbidity	= 13,65			
Specific Conductar	nce, umhos en	n .	480		11_	7 7	
Sampling Method	and Material	-					
				Container Descr	iption		
Constituents San	npled		From Lab	X or	G&M	Presci	vative
TAL - Total Inorga	nics			500 ml plas	stic		īno,
Cyanide				500 ml plas	stic		laOH
Remarks				•			
Sampling Personne	el	J. Gardner L.	Westbay				
		·		WELL CASI	NG VOLUMES		
	GAL./FT.	1-1/4" = 0.06		2° 0.16	3° - 0.37	4* = 0.65	
		1-1/2" = 0.09		2-1/2* + 0,26	3-1.2* = 0.50	6" = 1.47	

Project/No.		AY0146.017		l'age 1 of		
Site Location	Syracuse	China, Syracuse, New Yo	ork	Date	8/17/95	
Site Well No	SW-6	Coded Replicate No				
Weather	90's	Time Sampling Began	6.45	Time Sampling Completed	7 00	
		EVACUATIO	N DATA			
Description of Mea	suring Point (MP)	Stream				
Height	Lof MP Above Below Land S	urface	MP Elevation			
Total	Sounded Depth of Well Belo	w MP	Water-Level Elevation			
Held	Depth to Water Belo	w MP	Diameter of Casing			
Wet	ater Column is	ı Well	Gallons Pumped Bailed Prior to Sampling			
	Gallons pe	r Foot	6 1 to 1 1 1 1 1			
	Gallons in	n Well	Sampling Pump Intake Se (feet below land surface)	lting		
Evacuation Method	l					
Other (specific ion:	OVA, HNU, etc.)	rbidity 10.87				
Specific Conductar	nce, umhos cm	440	p!t	25		
Sampling Method a	and Material					
						
		Container Descr	nption			
Constituents San	npled Fr		nption r G&M	Presen	sative	
			r G&M		vative NO ₃	
Constituents San TAL - Total Inorga Cyanide		om Lab X or	r G&M	н		
TAL - Total Inorga		om Lab X of	r G&M	н	NO ₃	
TAL - Total Inorga		om Lab X of	r G&M	н	NO ₃	
TAL - Total Inorga	nnics	500 ml plas	r G&M	н	NO ₃	
TAL - Total Inorga Cyanide Remarks	nnics	500 ml plas 500 ml plas	r G&M	н	NO ₃	
TAL - Total Inorga Cyanide Remarks	nnics	500 ml plas 500 ml plas	r G&M	н	NO ₃	

Project/No.	AY0146.017				Page 1	of 1			
Site Location		Syracu	se China,	Syracuse, New Yo	rk		Date	8:17:95	
Site/Well No.		SW-6A		Coded Replicate No.					
Weather	965			Time Sampling Began	7 00	-	Time Sampling Completed	7.15	
				EVACUATIO	N DATA				
Description of Mea	suring Point ((MP) _				·			
Heigh	t of MP Abov	e Below Land	Surface	r	MP Elevation		6		
Total	Sounded Dep	oth of Well Be	low MP		Water-Level Ele	sation			
Held	Dep	th to Water Be	low MP		Diameter of Cas	nuā			
Wet		ater Column	m Well		Gallons Pumped Prior to Samplin				
		Gallons p	per Foot		S1 . D	1 . 1			
		Gallons	in Well		Sampling Pump (feet below land		-		
Evacuation Method	·	_							
		SA	MPLIN	IG DATA/FIE	LD PARAME	TERS			
Color	Odor			Appearance			Temperature	FC	
Other (specific ion:	OVA. HNU	etc)							
Specific Conductar	ice, umhos ci	n			P!	!			
Sampling Method	and Material	-		Disposable Baile	er (Tetlon); Polypro	pylene Rop	e.		
				Container Descr	iption				
Constituents San	ipled	I	From Lab	X or	G&M	-	Preser	vative	
				DRY - NO S	SAMPLE	_			
						-			
Remarks						_			_
Sampling Personne	el	J. Gardner L.	Westbay						
				WELL CASI	NG VOLUMES				
	GAL./FT.	1-1/4" = 0.06		2° = 0:16	3. * 0'3		4" = 0.65		
		1-1/2" + 0.09		2-1/2" = 0.26	3-1/2" = 0.5	ε	6* = 1.47		

APPENDIX C PERMEABILITY TESTING RESULTS



Transcript III				
eport				
Date:	January	4,	1995	

Test Start
Date December 6, 1994

Project No: B-94379 / Proje	ct Title: Syracuse China, Syracuse, New York, Project #A40146.009
	D#: 6302 / Test Sample Location: MW-41
	Type of Sample: Undisturbed X Remolded
•	/Percent Compaction:
Dry Unit Weight (PCF): Maximum: Init	Moisture Content (% of Dry Weight): al: 140.9 Optimum: Initial: 6.5
Initial Height (cm): 9.25	Initial Diameter (cm): 3.50 Initial Gradient: 22.8
	(B Value)(%): 94 Permeant Liquid Used: Deionized Water
essure (PSI): 71.0	Test (head) Tail (back) Pressure (PSI): 65.0
Final Degree Of Saturation (B Value)(%):	/Final Dry /Final
Final Height (cm): 9.15	Final Final Moisture Content Uiameter (cm): 3.45 (% of Dry Weight): 8.8
	Final Four Determinations k (cm/sec)
1.52 x 10 ⁻⁸	1.44×10^{-8} 1.45×10^{-8} 1.45×10^{-8}
Mean Value of Final Four C	Consecutive Determinations:
Coefficient of Permeability k (cm/sec): 1.47 x 10	8 Project Specifications:
Notes:	



Report	t			
Date:	January	4,	1995	

Test Start
Date ____December 6, 1994

Project No: B-94379 / Project	ct Title: Syracu	se China, Syracus	se, New York,	Project #A40146.005
ST No:/Lab	D#: 6301	Test Sample Loca	otion: MW-31	
Depth/Lift/Elev.: 30.0'-32.0	Type of Sampl	e: Undisturbed	X Remo	lded
Method of Compaction:		/Percent (Compaction:	
Dry Unit Weight (PCF): Maximum: Initi				
Initial Height (cm): 10.00				ent:21.1
Initial Degree of Saturation	(B Value)(%):	96 / Perm	eant Liquid Us	Deaired ed: Deionized Water
onfining ressure (PSI): 71.0	/Test (head) /Pressure (PS	SI):68.0	/ Tail (back) _/ Pressure (PS	65.0
Final Degree Of Saturation (B Value)(%):	94 /Fir	nal Dry nit Weight (PCF):	123.0 Fi	nal adient: 21.0
Final Height (cm): 10.03	Final Diameter (cm)	3.65	Final Moisture (% of Dry Weig	Content 13.3
	Final Four Dete	erminations k (cm	/sec)	
9.56 x 10 ⁻⁹	9.57×10^{-9}	9.59 x 10	9.6	1 × 10 ⁻⁹
Mean Value of Final Four C	onsecutive Deter	rminations:		
Coefficient of Permeability k (cm/sec): 9.58 x 10	-9	Project Specifications:		
Notes:				
3				
				· —-



aport			
Date:	4,	1995	

Test Start
Date December 6, 1994

Project No: B-94379 / Proje	ect Title: Syracuse China, Syracuse, New York, Project #A40146.00
ST No:/Lab	ID#: 6302 / Test Sample Location: MW-41
	Type of Sample: Undisturbed X Remolded
	/Percent Compaction:
Dry Unit Weight (PCF): Maximum: Initi	Moisture Content (% of Dry Weight): tial: 140.9 Optimum: Initial: 6.5
Initial Height (cm): 9.25	Initial Diameter (cm): 3.50 Initial Gradient: 22.8
Initial Degree of Saturation	Deaired (B Value)(%): 94 Permeant Liquid Used: Deionized Water
	Test (head) Pressure (PSI): 68.0 Tail (back) Pressure (PSI): 65.0
	Final Dry Final Gradient: 23.1
Final Height (cm): 9.15	Final Moisture Content
	Final Four Determinations k (cm/sec)
1.52 x 10 ⁻⁸	$1.44 \times 10^{-8} \qquad 1.45 \times 10^{-8} \qquad 1.45 \times 10^{-8}$
Mean Value of Final Four C	Consecutive Determinations:
Coefficient of Permeability k (cm/sec): 1.47 x 10	Project Specifications:
Notes:	



eport					
Date:	January	4,	1995		

Test Start
Date December 6, 1994

Project No: B-94379 / Proje	ct Title: Syracuse China, Syracuse, New York, Project #A40146.00
ST No:/Lab	D#: 6301 / Test Sample Location: MW-31
Depth/Lift/Elev.: 30.0'-32.0	Type of Sample: Undisturbed X Remolded
Method of Compaction:	/Percent Compaction:
Dry Unit Weight (PCF): Maximum: Initi	al: 126.8 Moisture Content (% of Dry Weight): Document
Initial Height (cm): 10.00	Initial Diameter (cm):3.60
Initial Degree of Saturation	(B Value)(%): 96 Permeant Liquid Used: Deionized Water
onfining ressure (PSI): 71.0	Test (head) Pressure (PSI): 68.0 Tail (back) Pressure (PSI): 65.0
Final Degree Of Saturation (B Value)(%):	94 Final Dry Final Gradient: 21.0
Final Height (cm): 10.03	Final Final Moisture Content Graph of the content Final Moisture Content 13.3
	Final Four Determinations k (cm/sec)
9.56×10^{-9}	$9.57 \times 10^{-9} \qquad \qquad 9.59 \times 10^{-9} \qquad \qquad 9.61 \times 10^{-9}$
Mean Value of Final Four C	onsecutive Determinations:
Coefficient of Permeability k (cm/sec): 9.58 x 10	
Notes:	
P	

APPENDIX D GROUNDWATER SAMPLING LOGS

Project/No.	AY0146	3.013		······		Page1 of1			
Site Location	Syracus	e, New York	K			Date	1/5/95		
Site/Well No.	MW-1			Coded/ _Replicate No.	MS/MSD			-	
Weath e r .				Time Sampling Began	2:00	Time Sampling Completed	12:30		
			•	EVACUATIO	ON DATA			2	
Description of Me	asuring Poir	nt (MP)		тос					
Height of	MP Above.	Below Land	Surface	2.25	MP Elevation	413.78			
Total So	Total Sounded Depth of Well Below MP			24.25	Water-Level Elevation	394.49			
Held Depth to Water Below MP			elow MP	19.29	Diameter of Casing	2"			
Wet	. •	Vater Colum	n in Well	4.96	Gallons Pumped/Bailed Prior to Sampling	3.0			
		Gallons	per Foot	0.16	Sampling Pump Intake	Setting			
		Gallon	s in Well	0.79	(feet below land surfa-				
Evacuation Metho	od	Centrifugal	pump and	i polyethylene tub	oing				
Color Lt. brown Other (specific ion	5.1	None U; etc.)	Turbidity	Appearance > 200	Turbid	Temperature	7.6	*c	
	n; OVA; HN	U; etc.)	Turbidity			Temperature	7.6	*c	
Other (specific ion	n; OVA; HN	U; etc.)	740		рН6		7.6	*c	
Other (specific ion	n; OVA; HN	U; etc.)	740	> 200	pH 6		7.6	°c	
Other (specific ion	ance, umho	U; etc.)	740	> 200 iller / polypropyler Container Desc	pH 6			°c	
Other (specific ion Specific Conducto Sampling Method	ance, umho	U; etc.)	740 Teflon ba	> 200 iller / polypropyler Container Desc	pH 6. ne rope cription	32 Preserv		°C	
Other (specific ion Specific Conducta Sampling Method Constituents Sampling Sampl	ance, umho	U; etc.)	740 Teflon ba	> 200 iller / polypropyler Container Desc X or	pH 6. ne rope cription	Preserv	vative	°c	
Other (specific ion Specific Conducts Sampling Method Constituents Sampling Metal	ance, umho	U; etc.)	740 Teflon ba From Lab 500 mL	> 200 iller / polypropylet Container Desc X or plastic	pH 6. ne rope cription	Preserv	vatíve	°c	
Other (specific ion Specific Conducts Sampling Method Constituents Sampling Metal Cyanide	ance, umho	U; etc.)	740 Teflon ba From Lab 500 mL	> 200 iller / polypropylet Container Desc X or plastic	pH 6. ne rope cription	Preserv	vatīve NO ₃	°c	
Other (specific ion Specific Conducts Sampling Method Constituents Sampling Method Constituents Sampling Method Constituents Sampling Method	ance, umho	U; etc.)	740 Teflon ba From Lab 500 mL 600 mL g	> 200 iller / polypropyler Container Desc X or plastic plastic	pH 6. ne rope cription	Preserv	vatīve NO ₃	°c	
Specific Conductor Sampling Method Constituents Sometal Cyanide VOCs Remarks	ance, umho	U; etc.) s/cm al	740 Teflon ba From Lab 500 mL 600 mL g	> 200 diler / polypropyler Container Desc X or plastic plastic dass	pH 6. ne rope cription r G&M	Preserv	vatīve NO ₃	*c	
Specific Conductor Sampling Method Constituents Sometal Cyanide VOCs Remarks	ance, umho	U; etc.) s/cm al	740 Teflon ba From Lab 500 mL 600 mL g	> 200 iller / polypropyler Container Desc X or plastic plastic	pH 6. ne rope cription r G&M	Preserv	vatīve NO ₃	°c	

Project/No.	AY0146.013				Page 1	of 1
Site Location	Syracuse, New Yo	ork			Date	1/5/95
Site/Well No.	MW-1		Coded/ Replicate No.	MS/MSD		
Weather	20 degrees, clear		Time Sampling Began	1:30	Time Sampling Completed	2:15
			EVACUATIO	N DATA	Ñ	
Description of Me	easuring Point (MP)		тос	· · · · · · · · · · · · · · · · · · ·		
	f MP Above/Below Lan		2.76	MP Elevation	394.84	.
Total Sc	ounded Depth of Well I	Below MP	12.86	Water-Level Elevation	390.38	3
Held	_ Depth to Water (Below MP	4.46	Diameter of Casing	2" 2"	
Wet	Water Colum	nn in Well	8.40	Gallons Pumped/Bailed Prior to Sampling	5 gallon	s
	Gallons	per Foot	0.16	Samalina D	- 8	
	Gallo	ns in Well	1.34	Sampling Pump Intake (feet below land surface	Setting :e)	
Evacuation Metho	od <u>Centrifug</u> a	l pump				
		SAMPL	ING DATA/FII	ELD PARAMETERS		
		_	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	LED I MIMIETERS		
Color Brown	Odor None		Appearance	Slightly turbid	Temperature	6.8 °C
Other (specific io	n; OVA; HNU; etc.)	Turbidity	> 200 NTUs			
Specific Conduct	ance, umhos/cm	1740		pH 5,;	76	
Sampling Method	and Material	Teflon bai	ler / polypropylen	e rope		
			Container Descr	ription	*	
Constituents S	ampled	From Lab	X or	G&M	Preserva	ative
Metal		500 mL p	olastic		Н	NO ₃
Cyanide		500 mL p	lastic	2		ОН
VOCs		40 mL gla	ISS			one
Remarks						ATC .
Sampling Personr	nel <u>G. Mattisc</u>	on & J. Gard	dner			
	GAL./FT. 1-1/4" = 0.06	;	WELL CASING	VOLUMES 3" = 0.37	4. 0.55	•
	1-1/2" = 0.09		2-1/2" = 0.26	3-1/2" = 0.50	4° = 0,65 6° = 1,47	

Project/No.	AY0146.013		· · · · · · · · · · · · · · · · · · ·		Page	ge 1 of	of	1
See Location	Syracuse, New Y	ork			Date		1/5/95	
Sne Well No.	MW-1		Coded/ Replicate No.	MS/MSD				
Weather	20 degrees, clear		Time Sampling Began	2:15	Time Sam Completed		2:45	
			EVACUATIO	N DATA				
Description of M	feasuring Point (MP)	•	Top of PVC			· · · · · · · · · · · · · · · · · · ·		
Height	of MP Above/Below La	nd Surface	3.03	MP Elevation		387.83		
Total S	Sounded Depth of Well	Below MP	12.41	Water-Level Elevation		384.14		
Depth to Water Below MP Water Column in Well		2 3.69 Diameter of Casing	2"	2*				
		8.72	Gallons Pumped/Bailed Prior to Sampling		5 gallons			
	Gallor	s per Foot	0.16					
	Galle	ons in Well	1.50	Sampling Pump Intake (feet below land surfac	Setting			
Evacuation Meth	hod Centrifugal pump	and polyeth	ivlene tubina					
Other (specific i	on; OVA; HNU; etc.)	Turbidity	> 200 NTUs					-
Specific Conduc	ctance, umhos/cm	1020		pH6.2	29			
Sampling Metho	od and Material	Teflon ba	iler and polypropy	lene rope				
			Container Desc	ription				
Constituents !	Sampled	From Lab	X or	G&M		Preserva	live	
Metal	· · · · · · · · · · · · · · · · · · ·	500 mL	plastic			HN	0,	
Cyanide		500 mL p	plastic			NaC)H	
VOCs		40 mL gl	ass			No	ne	
Remarks			-					
Sampling Persor	nnel <u>G. Mattis</u>	on & J. Gar	dner					
	0.41 (57		WELL CASING	VOLUMES				
	GAL./FT. 1-1/4" = 0.0		2" = 0.16	3° = 0.37	4" = 0.65			
			2-1/2" = 0.26	3-1/2" = 0.60	6" + 1.47			

Project/No.	AY014	6.013				Page	1 of 1
Site Location	Syracus	se, New Yo	rk			Date	1/5/95
Site/Well No.	MW-1			Coded/ Replicate No.	MS/MSD		
Weather	20 deg	rees, clear		Time Sampling Began	3:30	Time Samplin Completed	4:00
				EVACUATIO	ON DATA		
Description of M	easuring Poil	nt (MP)		тос			
Height o	of MP Above	/Below Land	d Surface	3.05	MP Elevation	38	5.69
Total S	ounded Dept	h of Well B	lelow MP	13.10	Water-Level Elevation	38	30.44
Held	Depth	to Water B	elow MP	5.15	Diameter of Casing	2* 2*	
Wet Water Column in Well		7.95	Gallons Pumped Bailed Prior to Sampling	4 (gallons		
		Gallons	per Foot	0.16			
		Gallor	ns in Well	1.27	Sampling Pump Intake S (feet below land surface	etting	
Evacuation Meth	od	Centrifuga	pump / po	Hyethylene tubing			
			SAMPL	ING DATA/FI	ELD PARAMETERS		
Color Brown	Odor	Yes		Appearance	Very turbid	Temperatu	ure <u>7.9</u> °C
Other (specific io	on; OVA; HN	U; etc.)	Turbidity	> 200 NTUs			
Specific Conduct	tance, umho	s/cm	1520		pH 5.8	7	
Sampling Method	d and Materi	al	Tellon ba	iler / polypropyleri	e rope		
				Container Desc	ription		_
Constituents S	Sampled		From Lab	X or	G&M	Pre	eservative
Metal	·	_	500 mL	plastic			HNO ₃
Cyanide		-	500 mL p	lastic			NaOH
VOCs		_	40 mL gla	ess			None
Remarks							
Sampling Person	nel	G. Mattiso	n & J. Gar	dner			
				WELL CASING	VOLUMES		
	GAL./FT.	1-1/4" = 0.06		2* = 0.16	3' + 0 37	4" = 0.65	
		1-1/2" = 0.09		2-1/2" = 0.26	3-1 2" ± C 5C	6" = 1.47	

Project/No.	AY014	6.013			Page 1	of	1
Site Location	Syracus	se, New York			Date	1/6/95	
Site/Well No.	MW-1	-	Coded/ Replicate No.	MS/MSD	P		
Weather	20 deg	ees, clear	Time Sampling Began	4:00	Time Sampling Completed	4:30	
			EVACUATIO	N DATA			
Description of Me	asuring Poir	nt (MP) TOC					
Height of	f MP Above	Below Land Surfa	ace <u>1.49</u>	MP Elevation	385.40		
Total Sc	ounded Dept	h of Well Below	MP 19.81	Water-Level Elevation	380.07		
Held	Depth	to Water Below	MP 5.33	Diameter of Casing	2* 2*		
Wet	. v	Vater Column in V	Vell 14.48	Gallons Pumped/Bailed Prior to Sampling	7 gallon	6	
		Gallons per F	oot <u>0.16</u>				
		Gallons in V	Vell2.31	Sampling Pump Intake ! (feet below land surface			
Evacuation Metho	od	Centrifuga pump	o / tubing				
Calar Bar			MPLING DATA/FII	ELD PARAMETERS			
Color Brown	Odor		Appearance	Turbid	Temperature	8.2 °	,C
Other (specific io	n; OVA; HN	U; etc.)	Turbidity > 200 N	ITUs			
Specific Conducta	ance, umhos	s/cm17	700	_ pH 5.8	2		
Sampling Method	and Materia	al Teflo	on bailer / polypropylen	e rope			
			Container Descr	rintion			
Constituents Sa	ampled	From		G&M	Preserva	ative	
Metal		500	mL plastic				
Cyanide					HN	103	
		500	mL plastic		Na	ОН	
VOCs		40 m	nL glass		No	ne	
Remarks		Metals sample n	ot filtered due to froze	n filter; sample sent with	preservative.		
Sampling Personr	nel	G. Mattison & J	. Gardner				
			29				
	CAL #77		WELL CASING	VOLUMES	-	•	
	GAL./FT.	1-1/4" = 0.06 1-1/2" = 0.09	$2^{\circ} = 0.16$ $2 \cdot 1/2^{\circ} = 0.26$	3° = 0.37	4° = 0.65		
				3-1/2" = 0.50	6" = 1;47		

Project/No.	AY0146.013				Page 1	_ of _	1
Site Location	Syracuse, New Y	ork			Date	1/5/95	
Site/Well No.	MW-1		Coded/ Replicate No.	MS/			
Weather	20 degrees, sunn	Y	Time Sampling Began	11:00	Time Sampling Completed	11:30	
20			EVACUATIO	ON DATA			
Description of Me	easuring Point (MP)		тос				
	f MP Above/Below La		3.34	MP Elevation	390.40		_
Total Sc	ounded Depth of Well	Below MP	13.20	Water:Level Elevation	386.25		
Held Depth to Water Below MP		4.15	Diameter of Casing	2"			
Wet	Water Colu	mn in Well	9.05	Gallons Pumped/Bailed Prior to Sampling	4.5		
	Gallor	s per Foot	0.16	Sampling Prime letelie 6	· · · · · · · ·		
	Gallo	ons in Well	1.50	Sampling Pump Intake S (feet below land surface	elling e)		
Evacuation Metho	odCentrifug	al pump					
Color Brown	Odor None	SAIVIFL	Appearance	ELD PARAMETERS Turbid	Temperature	8.7	٩C
Other (specific io	n; OVA; HNU; etc.)	Turbidity	> 200 NTUs		····		·-
Specific Conduct	ance, umhos/cm	820		pH 6.4	2		
Sampling Method	and Material	Teflon ba	iler / polypropyler	ne rope		_	
			Container Desc	ription			
Constituents S	ampled	From Lab	X or	G&M	Preserv	ative	
Metal		500 mL	plastic		н	NO,	
Cyanide		500 mL p	plastic	8		ю	
VOCs	·	40 mL gla	ass		N	one	
Remarks		v					
Sampling Personr	nel <u>G. Mattis</u>	on & J. Gar	dner				
			WELL CASING	VOLUMES	· · · · · · · · · · · · · · · · · · ·	_	
	GAL./FT. 1-1/4" = 0.0		2° = 0.16	3° + 0.37	4 - = 0.65		
	1-1/2" = 0.0	79	2-1.2* = 0.26	3-1/2*	6" := 1.47		

Project/No.	AY0146.013				Page 1	of .	1
Site Location	Syracuse, New Yo	rk			Date	1/5/95	
Site/Well No.	M.V-1		Coded/ Replicate No.	MS/			
Weather	20 degrees, clear		Time Sampling Began	10:45	Time Sampling Completed		11:15
			EVACUATIO	N DATA			
Description of Me	easuring Point (MP)		Top of PVC Cas	sing			
Height o	of MP Above/Below Lan	d Surface	1.56	MP Elevation	414.7	0	
Total Se	ounded Depth of Well I	Below MP	16.82	Water-Level Elevation	410.0	3	
Wet Depth to Water Below MP		4.67 Diameter of Casing		2" 2*			
		12.15	Gallons Pumped Bailed Prior to Sampung	6			
	Gallon	s per Foot	0.16				
	Gallo	ns in Well	1.90	Sampling Pump Intake S (feet below land surface	. 1		
Evacuation Meth	od Centrifuer	al numn / n	olyethylene tubing				
Color Red/Brow	on; OVA; HNU; etc.)	Turbidity	Appearance > 200 NTUs	Turbid	Temperature	4.4	°C
Specific Conduc	tance, umhos/cm d and Material	500 Teflon ba	ailer / polypropyle	p∺5.7 ne rope	8	7	
			Container Desc	cription			
Constituents :	Sampled	From La		r G&M	Prese	rvative	
Metal		500 mL	plastic			HNO₃	
Cyanide		500 mL	plastic			NaOH	
VOCs		40 mL g	lass			None	
Remarks							
Sampling Person	nnel <u>G. Mattis</u>	son & J. Ga	nrdner				
			WELL CASING	2 VOLLIMES			
	GAL./FT. 1-1/4" 0	06	WELL CASING	3° C 27	4" - 0 65		
	1-1/2" = 0.	09	2-1/2" - 0.26	3/1 21 - 0 50	6" - 1.47		

	AY0146.013				Page 1	of	1
Site Location	Syracuse, New Yo	ork			Date	1/5/95	
Site/Well No.	MW-1		Coded/ Replicate No.	MS/ ··			
Weather	20 degrees, sunny	<u>′</u>	Time Sampling Began	3:00	Time Sampling Completed	3:30	
			EVACUATIO	N DATA			
Description of Me	esuring Point (MP)		тос				
Height of	MP Above/Below Lar	nd Surface	1.46	MP Elevation	394.6	57	
Total So	ounded Depth of Well	Below MP	16.95	Water-Level Elevation	387.1	16	
Held Depth to Water Below MP		Below MP	7.51	Diameter of Casing	2- 2-		
Wet	. Water Colur	nn in Well	9.44	Gallons Pumped/Bailed Prior to Sampling	5 gall	ons	
	Gallon	s per Foot	0.16		_		
	Gallo	ns in Well	1.50	Sampling Pump Intake (feet below land surface			
Evacuation Metho	nd Centrifue:	al numn / no	elyethylene tubing				
Color Brown	Odor None		Appearance	Very turbid	Temperature	9.6	°C
	Odor <u>None</u> n; OVA; HNU; etc.)	Turbidity	Appearance > 200 NTUs	Very turbid	Temperature	9.6	°C
	n; OVA; HNU; etc.)	Turbidity		Very turbid		9.6	°C
Other (specific ion	n; OVA; HNU; etc.)	1040		рН5.9		9.6	°C
Other (specific ion	n; OVA; HNU; etc.)	1040	> 200 NTUs	pH 5.9		9.6	°C
Other (specific ion	ance, umhos/cm	1040	> 200 NTUs iler / polypropyler Container Desc	pH 5.9	93	9.6	°C
Other (specific ion Specific Conducte Sampling Method	ance, umhos/cm	1040 Teflon ba	> 200 NTUs iler / polypropyler Container Desc X or	pH 5.9 ne rope ription	93		°C
Other (specific ion Specific Conducts Sampling Method Constituents Sampling	ance, umhos/cm	1040 Tellon ba	> 200 NTUs iler / polypropyler Container Desc X or	pH 5.9 ne rope ription	Prese	ervatīve	°C
Other (specific ion Specific Conducts Sampling Method Constituents Sampling Metal	ance, umhos/cm	Teflon ba	> 200 NTUs iler / polypropyler Container Desc X or plastic	pH 5.9 ne rope ription	Prese	ervatīve HNO ₃	°C
Other (specific ion Specific Conducts Sampling Method Constituents Sampling Metal Cyanide	ance, umhos/cm	Teflon ba From Lab 500 mL	> 200 NTUs iler / polypropyler Container Desc X or plastic	pH 5.9 ne rope ription	Prese	ervative HNO ₃ NaOH	°C
Other (specific ion Specific Conducts Sampling Method Constituents Sampling Method Cyanide VOCs	ance, umhos/cm I and Material	Teflon ba From Lab 500 mL	> 200 NTUs iler / polypropyler Container Desc X or plastic plastic	pH 5.9 ne rope ription	Prese	ervative HNO ₃ NaOH	°C
Other (specific ion Specific Conducts Sampling Method Constituents Si Metal Cyanide VOCs Remarks	ance, umhos/cm I and Material	1040 Teflon ba From Lab 500 mL 500 mL gl	> 200 NTUs iler / polypropyler Container Desc X or plastic plastic	pH 5.9 ne rope ription G&M	Prese	ervative HNO ₃ NaOH	°C

Project/No.		AYG		Page1	of1	
Site Location	Syracu	se China	Syracuse, New Yor	<u>k</u>	Date	8/17/95
Site Well No.	MW-I		Coded Replicate No.			
Weather	Clear, 85"		Time Sampling Began	10:40	Time Sampling Completed	11:00
			EVACUATIO	N DATA		
Description of Me	easuring Point (MP)		Тор	of Casing		
He	ight of MP Above/Below Land	Surface		MP Elevation		
To	otal Sounded Depth of Well Bo	low MF	24.26	Water-Level Elevation	1	
Held	Depth to Water B	low MF	20.75	Diameter of Casing	2"	
Wet	Water Column	n in Wel	3.51	Gallons Pumped Baile Prior to Sampling		illons
	Gallons	per Foot	0 16			
	Gallon	s in We!	0.56	Sampling Pump Intak (feet below land surfa		
Evacuation Meth	od Disposable Ba	iler (Te5 a	n: Polypropylene f	lope		
Color Light	n; OVA; HNU; etc.)		Appearance	Turbid	Temperature	C
	•	Turbida	= 130			
Specific Conduct	tance, umhos cm	10%		Нղ	7 39	
Sampling Metho	d and Material		Disposable Baile	er (Tellon): Polypropylen	ie Rope:	
			Container Descr	iption		
Constituents Sa	ampled	From Lan		r G&M	Pre	senative
TAL - Total Inor	ganics(no cyanide)		500 ml plas	itic		HNO ₃
TAL - Dissolved	Inorganics(no cyanide)		500 ml plas	ilic	U	npreserved
Remarks			-			
Sampling Person	nnel J. Gardner L.	Westbay				
			WELL CASI	NG VOLUMES		
	GAL./FT. 1-1/4° = 0.08		2" = 0.16	3° = 0.37	4° = 0.65	
	1-1/2" = 0.09		2-1/2" = 0.26	3-1/2° = 0.50	6" = 1.47	

Project/No	ΑΥ0	146 017	· · · · · · · · · · · · · · · · · · ·	Page 1	ર્ભા
Site Location	Syracuse China	i. Syracuse: New Yo	ork	Date	8:17/95
Site Well No	MW-2	Coded Replicate No			
Weather	Sunny, Clear, 85°	Time Sampling Began	11.40	Time Sampling Completed	12:00
		EVACUATIO	N DATA		
Description of Me	asuring Point (MP)	Тог	of Casing		
Heigh	ht of MP Above Below Land Surface		MP Elevation		
Tota	I Sounded Depth of Well Below MP	12.88	Water-Level Elevation		
Held	Depth to Water Below MP	5,91	Diameter of Casing	2"	
Wet	ater Column in Well	6.97	Gallons Pumped Bailed Prior to Sampling	3.3 gall	ons
	Gallons per Foot	0.16			
	Gallons in Well	1.12	Sampling Pump Intake S (feet below land surface)	etting	
Evacuation Method	d Disposable Bailer (Tell	on): Polypropylene	Rope		
Color Light tun Other (specific ion	red Odor None	Appearance	ì urbid	Temperature	C
	Turbidity	= 200			
Specific Conducta	nce, umhos cm 2300		pH7	20	
Sampling Method	and Material	Disposable Baile	r (Tetlon): Polypropylene R	ope.	
		Container Descri	ption		
Constituents San	mpled From Lab	X or	G&M	Present	ative
TAL - Total Inorga	anics(no cyanide)	500 ml plasi	iic	Н	Ю,
TAL-Dissolved Inc	organics(no cyanide)	500 n	nl plastic		served
Remarks		1/			
Sampling Personne	el J. Gardner L. Westbay				
	GAL./FT. 1-1/4" = 0.06 1-1/2" = 0.09	WELL CASIN 2" = 0.16 2-1/2" = 0.26	NG VOLUMES 3" = 0.37 3-1 2" = 0.50	4" + 0.65 6" = 1.47	

Project/No.	AY0146.017			Page 1	_ of1	
Site Location	Syracuse China, Syracuse, New York			Date	8/17/95	
Site Well No.	MW-3	Coded Replicate No.				
Weather	Sunny, Clear, 90"	Time Sampling Began	12 05	Time Sampling Completed	12:35	
		EVACUATIO	N DATA			
Description of M	casuring Point (MP)	Тог	of Casing		··	
Heig	ght of MP Above Below Land Surface		MP Elevation			
Tota	al Sounded Depth of Well Below MP	11.90	Water-Level Elevation			
Held	Depth to Water Below MP	4,19	Diameter of Casing	2"		
Wet	ater Column in Well	7.71	Gallons Pumped Bailed Prior to Sampling	3.7 ga	llons	
	Gallons per Foot	0.16		=		
	Gallons in Well	1.23	Sampling Pump Intake Se (feet below land surface)	etting		
Evacuation Metho	od Disposable Bailer (Tetl	on); Polypropylene	Rone.			
			LD PARAMETERS	···		
			TO I ANAMETERS			
Color Gray Br	own Odor None	Appearance	Turbid	Temperature		
Other (specific to	n, OVA; HNU, etc. /				-	
	Turbidity	200				
Specific Conducts	ance, umhos cm 1280		llq	.)7		
Sampling Method and Material Disposable Bailer (Tetlon); Polypropylene Rope.						
		Container Descri				
Constituents Sa	ampled From Lab				Preservative	
TAL - Total Inorg	ganics(no cyanide)	500 ml plas	500 ml plastic		HNO ₃	
TAL-Dissolved In	norganics(no cyanide)		500 ml plastic			
	norganies (no evanue)	JOO mi pias	ис	Unp	reserved	
Remarks						
					(25)	
Sampling Person	nel J. Gardner/L. Westbay	-				
		WELL CASI	NG VOLUMES		_	
	GAL./FT. 1-1/4" = 0.06	2" - 0.16	3° - 0.37	4" = 0.66		
	1-1.2° C 09	2-1.2* 0.26	3-1/2" - 0.50	6" 1,47		

Project/No.	AY01		Page 1	ofI	
Site Location	Syracuse China	Syracuse, New Yor	rk	Date	8 17/95
Site Well No.	MW-4	Coded Replicate No.			
Weather	Sunny, Clear, 90"	Time Sampling Began	12.50	Time Sampling Completed	1:10
		EVACUATIO	N DATA		
Description of Mea	asuring Point (MP)	Тор	of Casing		
Heigh	nt of MP Above/Below Land Surface	-	MP Elevation		
Total	Sounded Depth of Well Below MP	13.11	Water-Level Elevation		
Held	Depth to Water Below MP	5.42	Diameter of Casing	2"	
Wct	ater Column in Well	7 69	Gallons Pumped Bailed Prior to Sampling	3,7 gal	lons
	Gallons per Foot	0.16	Complete Description of		
	Gallons in Well	1.23	Sampling Pump Intake S (feet below land surface)		
Evacuation Method	d Disposable Bailer (Tef.	on); Polypropylene :	Rope.		
	SAMPLI	NG DATA/FIE	LD PARAMETERS		
Color Light ta		Appearance	Slightly Turbid	Temperature	C
Other (specific ion	; OVA; HNU; etc.)				
	Turbidin	= 140			
Specific Conducta	nce, umhos cm 2056		pH7	20	
Sampling Method	and Material	Disposable Baile	r (Tetlon); Polypropylene R	ope.	
		Container Deseri	ption		
Constituents Sar	mpled From Lab	X or	G&M	Preser	vative
TAL - Total Inorg	anics (no cyanide)	500 ml plasi	tic	н	NO ₃
TAL - Dissolved I	norganics (no cyanide)	50-1 ml plastic			eserved
					·
Remarks		·	(4)	12	
Sampling Personn	J. Gardner/L. Westbay	16			
		WELL CASE	NC VOLUMES	~	-
	GAL./FT. 1-1/4* = 0.06	2° + 0,16	NG VOLUMES 3° - 0.37	4" = 0.65	
	1-1/2" = 0.09	2-1,2" = 0,26	3-1/2* = 0.50	6" = 1,47	

Project No.		AY014		Paget	_ of _ I	
Site Location	Syracus	se China.	Syracuse, New Yo	rk	Date	8/17/95
Site/Well No	MW-41		Coded Replicate No.		***************************************	
Weather	Sunny, Clear, 90°		Time Sampling Began	1.10	Time Sampling Completed	1-50
			EVACUATIO	N DATA		
Description of Mea	suring Point (MP)		Тор	of Casing		
Heigh	nt of MP Above/Below Land 9	Surface		MP Elevation		
Total	Sounded Depth of Well Belo	ow MP	19.80	Water-Level Elevation		
Held	Depth to Water Belo	ow MP	3 62	Diameter of Casing	2"	
Wet	ater Column	in Well	16 18	Gallons Pumped Bailed Prior to Sampling	7.8 ga	llons
	Gallons p	er Foot	0.16	Samalina Dunin Leater C	S. 445.	
	Gallons	in Well	2.59	Sampling Pump Intake S (feet below land surface)		
Evacuation Methox	j Tetlon bailer ar	nd polypro	opylene rope			
				LD PARAMETERS		
	0			LD TANAIVIETENS	•	
Color Red Brow	wn Odor None		Appearance	Furbid	Temperature	15" C
Other (specific ion:	OVA: HNU, etc.)					
	Tı	urbidity =	199 NTU			
Specific Conductor	nce, umhos cm	1980		H_	7.0	
Sampling Method	and Material To	etlon baile	er and polypropyle	ne rope		
			Container Descri	Olion		
Constituents San	npled Fi	rom Lab		G&M	Preser	vative
TAL - Total Inorga	nnics (no evanide)		500 ml plasi	ic		
±						NO ₃
	norganics (no cyanide)		500 ml plastic		Unpr	eserved
Field Blank			500 ml plasi	ic	Н	NO ₃
Remarks						
Sampling Personne	el J. Gardner L. V	Vestbay				
	GAL./FT. 1-1/4° = 0.06		WELL CASIN	NG VOLUMES 3° = 0.37	4 0.65	
	1-1/2" = 0.09		2·1/2° ± 0.26	3-1 2" = 0.60	6" = 1.47	

Project/No.	AY0		Page 1	of 1			
Site Location	Syracuse China	. Syrocuse, New Yo	rk	Date	8/17-95		
Site Well No.	MW-5	Coded Replicate No.					
Weather	Clear, 85°	Time Sampling Began	1116	Time Sampling Completed	11:30		
		EVACUATIO	ON DATA				
Description of Me	asuring Point (MP)	Тор	of Casing				
Heigi	ht of MP Above Below Land Surface		MP Elevation				
Tota	Il Sounded Depth of Well Below MP	13,19	Water-Level Elevation				
Held	Depth to Water Below MP	5.30	Diameter of Casing	2"			
Wet	ater Column in Well	7.89	Gallons Pumped Bailed Prior to Sampling				
	Gallons per Foot	0.16	Complian Day 1				
	Gallons in Well	1.26	Sampling Pump Intake So (feet below land surface)	ating			
Evacuation Metho	od Disposable Bailer (Tetl	on): Polypropylene	Rone				
			LD PARAMETERS				
Color Lt. tan-g Other (specific ior	ray Odor None ni OVA; HNU, etc. ; Turbidity	Appearance = 96.2	Slightly Turb 2	Temperature	C		
Specific Conducta	nnce, umhos em 1140		pH7	40			
Sampling Method	and Material	Disposable Baile	r (Tetlon): Polypropytene Ro	ine.			
		Container Descr	inten				
Constituents Sa	mpled From Lat		· G&M	Prese	rvative		
TAL - Total Inorg	ganies (no cyanide)	500 ml plas	tic 5				
				HNO3			
TAL - Dissolved I	Inorganies (no cyanide)	500 ml plastic		Unp	reserved		
							
Remarks							
Sampling Person	nel J. Gardner L. Westbay						
	GAL./FT. 1:12" x 0.06	WELL CAST 2" + 0.16	NG VOLUMES	4° - 0.65	_		
	1-1,2" + 0,09	2-1,2* + 0 26	3-1.2" - 0.50	6" 1.47			

Project/No.	AYO		Page 1	of <u> </u>	
Site Location	Syracuse China	Syracuse, New Yo	ork	Date	8/17/95
Site/Well No.	MW-6	Coded Replicate No.	Rep. I		
Weather	85"	Time Sampling Began	9 50	Time Sampling Completed	10:30
		EVACUATIO	ON DATA		
Description of Me	asuring Point (MP)	Top	of Casing.		
Heigh	ht of MP Above/Below Land Surface		MP Elevation		
Tota	I Sounded Depth of Well Below MP	16.36	Water-Level Elevation		
Held	Depth to Water Below MP	3.85	Diameter of Casing	2-	
Wet	ater Column in Well	12 51	Gallons Pumped Bailed Prior to Sampling	ه و النام ال	กร
	Gallons per Foot	0.16			
	Gallons in Well	2.00	Sampling Pump Intake So (feet below land surface)	etting	
Evacuation Metho	d Disposable Bailer (Tetle	on); Polypropylene	Rope.		
			LD PARAMETERS		
	O A WILL	TO DATA/ITE	LD FARAINE LERS		
Color Red Bro	wn Odor None	Appearance	Turbid	Temperature	17" C
Other (specific ion	i; OVA; HNU; etc.)				
	Turbidits	≅ 77. 2			
Specific Conducta	nce, umhos em 73/3		pll7	03	
Sampling Method	and Material	Disposable Baile	er (Tetlon): Polypropylene Ro	nne	
		Container Descri	x. xx	.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
Constituents Sar	mpled From Lab		·G&M	Preser	entiva
TAL - Total Inorg	anics (no evanide)	500 ml plas	lie.		
22		1972 90			NO,
TAL - Dissolved I	norganics (no cyanide)	500 ml plastic		Unpr	eserved
					
Remarks					
Sampling Personn	J. Gardner/L. Westbay				
		WELL CASE	NG VOLUMES		_
	GAL./FT. 1-1/4" = 0.06	2° = 0.16	3° = 0.37	4° = 0.65	
	1-1/2" = 0.09	2-1.2" = 0.26	3-1/2* = 0.50	6" = 1,47	

Project/No.		Y0146 017		l'age 1	of1
Site Location	Syracuse Cl	iina, Syracuse, New Yo	rl	Date	8417495
Site Well No.	MW-7	Coded Replicate No	-		
Weather	85°	Time Sampling Began	2 30	Time Sampling Completed	3:00
		EVACUATIO	ON DATA		
Description of Me	asuring Point (MP)	Top	o of Casing		
Heig	ht of MP Above Below Land Surf	ace	MP Elevation		
Tota	I Sounded Depth of Well Below I	MP 16.89	Water-Level Elevation		
Held	Depth to Water Below I	MP 5.53	Diameter of Casing	2"	
Wet	ater Column in W	Fell 11.36	Gallons Pumped Bailed Prior to Sampling	5.5 ga	llons
	Gallons per F	0.16	Signalina Roma Intelle	٧	
	Gallons in W	/ell <u>1.81</u>	Sampling Pump Intake: (teet below land surface	•	
Evacuation Metho	ed Teffon bailer and p	olypropylene rope			
Color Light Bro Other (specific ion	n; OVA; HNU; etc.)	Appearance dity = 200	Turbid	Temperature	
Specific Conducts		380		7.02	
		7. 7	_ ·	7.02	
Sampling Method	and Material Tello	n bailer and polypropyl	ene rope		
		Container Descr	ription		
Constituents Sa	impled From	Lab X o	r G&M	Prese	native
TAL - Total Inorg	ganics (no cyanide)	500 ml plas	stic	<u> </u>	INO ₃
TAL - Dissolved	Inorganics (no cyanide)	500 mt plasti	c	Unp	reserved
Remarks			U.		
Sampling Person	nel Cordon W	thati			
eambinik t.c.2011	nel J. Gardner L. Wes	toay			
	GAL./FT, 1-1/4" = 0.06	WELL CASI 2° = 0.16	NG VOLUMES	4* = 0.65	
	1-1/2" = 0.09	2-1/2" = 0,26	3-1/2" = 0.60	6* = 1.47	

APPENDIX E HYDRAULIC CONDUCTIVITY TESTING DATA

1	7	GER	AGH	ГΥ	
A	18	MIL	LER,	INC.	
ASS	an	and We	Mr Con	mhaser	

WATER LEVEL/PUMPING TEST RECORD

PAGE.

OF...

SVen (CA CLUM XX	China and the second	建 种工程的	
PROJECT 3419 CL	& China Shy	TOTAMETT WIN	SITESV	POCULE IN YES
SCREEN 12-22'	MEASURING POINT	T.O. C. (PVG) HEIGHT AE	OVE THE PROPERTY OF THE PROPER
SETTING :	DESCRIPTION	# (#)*.	GROUND S	SURFACE TO TOTAL
STATIC 17.01	MEASURED WITH_	m-Scope	DATE/TIME	1-17-95
WATER LEVEL		•	5(8)	and the second
DRAWDOWN []	START OF TEST	Di 27	PUMPING	<u> </u>
RECOVERY	END OF TEST	10:49	WELL	A STATE OF THE STA
DISTANCE FROM WELL	DICCUADOE	b.	ORIFICE	4, 2,4,4
MEASURED TO PUMPING WELL (r)	RATE	ž.		
* #F 154	The state of		2.3	

	3000			The state of the state of	W #	8		母為 海	THE TAIL	11000	
DATE & TIME	WELL OR t (mins)	HELD (ft)	WET (ft) Time	DEPTH TO WATER (ft)	. s _ (ft)	DEW. ¹¹ CORR. (ft)	ART.2	Time	gpm) De pth	WANG!	REMARKS
1-	MUM.		initia	#4 *			17	1.0	Morter	-5-	A Ligary
Ä	10 m		a e 🎎					+ , - +	1		ASSESSED FOR THE PARTY OF THE P
		ž.	.10	79/01		• DE-	100	8.30	19.20	.19	Tank Tank Tank
			1.20	- 20	81 ₂₃		· sa	9.06	19.19	.18	Mary Company
			.30	1995	.74			9.30	14.18	.17	
			.40	14,62	.61			10.00		. 17	
			.50	19.55	,54			11.06	19.17	.16	
			1.00	A.51	.50				19.15	. 14	
			1.15	19,47	.46			13.00		. 13	
			1.30	19,45	.44			14.00	19.3	. /2	
			1. 45	19.42	.4/			15.∞		.18	
·			2.00	19.40	.31		16	17.00	9.	.10	
			2.15	19,39	. 38			18.00	19.09	.08	
			2.30	19.37	.34			19.00	19.00	.08	1
			2.45	P.35	.34	4		20.00	19.08	.07	
			3.00	19.35	134			22.00	19.01	.06	
			3.15	19,34	.33	22		24.00			* 98 2
			3.30	19,33	.32	<u> </u>		26.00			
			4.00	19,31	.30			28.00			
	<u> </u>		415	19.30	,29		<u> </u>	35.00			
	L.,.,,	<u> </u>	4.30	19.29	28						
	4.45		5.00	19.29	.28 .27						
	ļ		5.50	19.27	.26						
		·	6.00	19.20	.25	1			<u> </u>		
	<u> </u>		6.30	19.24			1		<u> </u>		
	<u> </u>		7.00	19.23							
	<u> </u>	ļ	7.30	19.22	.21						
	<u> </u>		8.00	19,21	1.20	2					

00000				
	W C	ER	AUH	IY
401	PA	MI	LED!	TY INC.
-	U	IATIF		11100

WATER LEVEL/PUMPING TEST RECORD PAGE

	大学 经重要	二 雪柳 彩 " " 。	一十七十	A STATE OF THE PARTY OF	6. 工业和联系公司第75条中国一	<u> </u>
PROJECT Syrews	Chine Dug	Test-WELL 1	W-Z SITI	Syrecus	a Chia	
SCREEN 4.5-1.5'	MEASURING POINT	TOC		EIGHT ABOVE		
SETTING	DESCRIPTION ()	7		SROUND SURFACE	E	
STATIC 400	MEASURED WITH_	m-5081	5 <u>e</u> c	DATE/TIME	-17-95	
WATER LEVEL		•		or Harris		
DRAWDOWN	START OF TEST	11:58	P	PUMPING		
RECOVERY []	END OF TEST	12:22	No.	WELL		
DISTANCE FROM WELL	DISCHARGE	 ∈ .		ORIFICE	14 14 14 14 14 14 14 14 14 14 14 14 14 1	- 92
MEASURED TO PUMPING	RATE	ž.			m	

VELL (II			3 to \$2	一种		200		4	CEXTED S	加度		سه په
DATE &	WELL OR t (mins)	HELD (ft)	WET (fg)	DEPTH TO WATER		DEW. ¹⁾ CORR. (ft)	ART. ²⁾ 8' (ft)	Time		MATER METER MATER	REMA	KS.
1-	MW-Z		Time				·		140		74.7	OSET WAS
`		•	ihihal	i v de grande				7	Cape Grad Grade Grade Grade Grade Grade Grade Grade Grade Grade Grade Grad Grade Grad Grade Grade Grade Grade Grade Grade Grade Grade Grade Grade Grad Grade Grade Grade Grade Grade Grade Grade Grade Grade Grade Grad Grade Grade Grade Grade Grade Grade Grade Grade Grade Grade Grad Grad Grad Grade Grad Grade Grad Grad Grad Grad Grad Grad Grad Grad		T 199 24	· 网络第57
			1.0	200	10.00			/	rus d number	15 47 5 National Property of the Property of t		2°464
			.10	mjrs.	98 (1 2 1) 1 7 1	·		800	4.6	68		- (m. 5
-			.25	5.45	1.45	-			4.61	.61		
			.30	1 . 1	1.44			9.00	4.50	.58	0.00	
			.40	1	1.42			9.30	4.55	.55		
			,50	5,28	1.38			10.00	4,52	.52		
			1.00	534	1.30	1	<u> </u>	11.00				
			115	5,33	1.32			12.00	4143	.43		- 17
			1.30	5,50	1.30		1	13.00	4.39	138		
			1.45	5,20		•		14.00				
			2.00	5.21	1.2,	/		15.00				
			2.15	5,20	1.20	1		17,00			<u> </u>	
			2.30	5,18	1.18	<u> </u>	<u> </u>	17.00			<u> </u>	
		<u> </u>	2.45	5,14	1,14	'		18.00				
		<u> </u>	3.00	5,10	1.10	2				1		<u> </u>
			3.15	15,08	1.08	3	1	20.00				
			3.30	5.05		1			4.15		1	
		ļ	4.00			b		24.00	4.11	111		
ļ		ļ	4.15	4.97				2600	4	<u> </u>		
<u> </u>	4	15	4.30	4,95	,98	5	4_	28.0	4	<u> </u>		
			5.00		.90	1		300	٢			
 			5.30	4,80		_			-	 	<u> </u>	
		 	6.00	4.91		1			-	-		
		-	6.30					 	-	-		
			7.00		.7				-			
			7.30	14,69	1.6	9						

	4.5
480	GERACHTY MILLER, INC.
AVO	LOLLED INC
E 0	WILLIAM INC.

WATER LEVEL/PUMPING TEST RECORD

\$1.3	A Comment
PAGE	OF
FAGE	Ur

	は一人には、一人には	です。	一种的一种	的是一个人,
PROJECT	e China Sluc	WELL MW-3	SITE JUL	eure, "
SCREEN 4-9	MEASURING POINT	TO CHE (PVC)	_ HEIGHT ABOY	A STATE OF THE ST
SETTING	DESCRIPTION	1 Land out a sp	GROUND SUP	RFACE
STATIC_3.50	MEASURED WITH_	· M .	DATE/TIME _	1-17-95
WATER LEVEL		12:40		
DRAWDOWN	START OF TEST	12.40	_ PUMPING	
RECOVERY	END OF TEST	12:58	WELL	2. M. H. Marine,
DISTANCE FROM WELL MEASURED TO PUMPING	DICCUADCE		ORIFICE	
WELL (r)	RATE	· · · · · · · · · · · · · · · · · · ·	12 ·	

DATE & TIME	WELL OR t (mins)	HELD (ft)	WET- Ho Time	DEPTH TO WATER (ft)	(ft)	DEW. ¹⁾ CORR. (ft)	ART. ²⁰	Tine	(apm)	MANO- METER	REMARKS
 -	MW3		**			1.	भारतिकालः भारतिकालः		Mary		100 Mars 1 120 1
			initial		34	3 DE	1,503	<u>a</u> ,		- 20	
		**				*		2 10	A NE	1.00	*
			.10					7.06	4.00	.50	152 J. 25.
			,20	4.81	1.31			7.30	3,98	. 48	
			.30	4.88	1.25	1	ļ		3.95	. 45	
			.40	4.70	1.20	ļ	ļ	8.30	3,93	. 43	
			.50	4.68	1.18	<u> </u>	<u> </u>	900	3.91	,41	
			1.00	4.65	1.15	1	<u> </u>	9.30	3.90	.40	
	N.		1:15	4.61	1.1/		<u> </u>	10,00	3.88	.38	
			1.30	4.59	109		.	11.00	3.85	.35	
			1.45	4.55	105	1		12.00	3.81	.31	
			2.00	4.47	.17			13.00	3.80	.30	
·			215	4.41	.9/			14.00	378	.28	
			2.30	4.38	.8%			15.00	3.76	.26	
			245	4.34	84		1	16.00	3.74	. 24	
			3.00	4,33	.83			17.00	3.73	. 23	## .
			3.15	4.30	.80			18.00	3.72		
			3.30	4.26	.76			19			
			3.45	4.24	1.74	1		20			
			4.00	4.21	1.7	1		22			
			4.15	4.20	.70			24			
			4.30	4.18	.69			26			
			4.45	4.16	.60	T		28			
			5.00	4.14	.64			30			
			5.30	4.11	1.61						
			6.00	4.09							
			630	1394						1	

GERACHTY	
GERAGHTY OF MILLER, INC.	
Per Oreund Woder Consultant	

WATER LEVEL/PUMPING TEST RECORD

3:4	- 1923	72.	2 :	3.	•			4
DA	CE		100	•	^	~		
PA	UE				U	r		I
					_	-	_	_

PROJECT Byra CUSE	China Slig KSKIELL MW-4	STE Smaline MY
SCREEN 4-9' 160' SETTING	MEASURING POINT TOC (PVC) DESCRIPTION	HEIGHT ABOVE GROUND SURFACE
STATIC 4.82 WATER LEVEL	MEASURED WITH M-SCOPE	
DRAWDOWN RECOVERY	START OF TEST	PUMPING
DISTANCE FROM WELL MEASURED TO PUMPING	END OF TEST /: 43-	ORIFICE
WELL (r)	RATE	THE GALL

			Section 1										
DATE & TIME	WELL OR t (mins)	HELD (ft)	WET in Itu	DEPTH TO WATER (ft)	e (ft)	DEW. ¹¹ CORR. (ft)	ART. ²¹ 8' (ft)	Time	Deeth Deeth	MANCE METER Sing		REMARKS ³	
1-	MWY		# 1	1 37	, Ti. 2*		<u>.</u>		weth	in the second	5-35		
			initial			4	4.1	(10)	:•®	The said manager	8 70		
		7.		大学を	- (8)	2.5		7:00	`	*, *,			
(e) (i)	R		. 10	5				7.30	8: 55	(6 ±6)	\$1.00 m		
			120	5.48	.66			800					
			.30	5.14	.32			8.30					
			.40	5.05	.23			9.00					
			.50	5.00	.18			9.30					
			1.00	4.98	.16			10.00	1				
			1.15	14.91	.09			//					
			1.30	4,96	.04			72					
			1.45	4,90	.04			13					
	ļ		2.00	4.85	103			14					
·			2.15	4.25	.03			15					
			7.30	4.24	.02			16					
	<u> </u>		2.45	4,84	.02			17					
	ļ		3.00	4.83	.01			18					
			3.15	4,83	.01			19					
			3.30	4.82	.00			20					
	ļ		3,45	4.32	1.00	/		22					
			4.00		<u> </u>			24					
			4.15					20					
	ļ	<u> </u>	4.30		<u> </u>	ļ		28					
			4.45	ļ	ļ	1		30					
	ļ		5.00	ļ	ļ	<u> </u>							
			5.30	<u> </u>	<u> </u>		1						
	<u> </u>	 	6.00		<u> </u>	<u> </u>	1			(4)			
L	<u></u>		6.30	<u> </u>						<u></u>			

49	GERACHTY O MILLER, INC.	WATER LEVEL	/PUMPING	TEST RE	CORD F	AGE	OF.)
	PROJECT SIAM	a ChinaStu	Joken A	W.YI S	Su.	alus	// L
		MEASURING POINT DESCRIPTION			HEIGHT ABOV	E	1000
	STATIC 13.52 WATER LEVEL	MEASURED WITH	m-sco	pe.	DATE/TIME	1-17-9	5
		START OF TEST			PUMPING		
	SIGNATURE COOL STREET	END OF TEST	:10	₹0 E	-		4
ĺ	DISTANCE FROM WELL - MEASURED TO PUMPING WELL (r)	DISCHARGE			ORIFICE		Lastica (#

DATE & TIME	WELL OR t (mins)	HELD (ft)	Time	DEPTH TO WATER	(ft)	DEW. ¹¹ CORR. (ft)	ART, 20	Time	Sont Dipth	MANO: METER	*	REMARKS
1	MW41		ाँ 🏥 🔞	F.Z				5.00 5.00	with	S		
£,	100		initial	*** *** -				22	<u></u>	1.7		
	<i>&</i>						·			i di		\$ 1.0 mm
#) ³⁰⁰	â)		.10	470 <u>4</u>				7.00	14.85	** 4		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
			.20					7.30	14.95	ч		
-			130	14.88	1:30	•		800	14,85	',		
			140	14.88	1.36		<u> </u>	830	14.85	и		
			.50	14.48	11			900	14.85	1/		
			1.00	14.87	11			930	14.85	''		
			1.15	14,93	11	ļ		1000	14.9=	1,33		
			1.30	14.07	1.35		ļ	11				
			1.45	14	11	<u> </u>	<u> </u>	12	ļ			
		ļ	2.00	14,97	11	<u> </u>		13	<u> </u>		<u> </u>	
			2.15	14.80	1.34	'	<u> </u>	14	<u> </u>		_	
			2.30	14.86	1 ''	ļ	<u> </u>	15	ļ		_	
			2.45	H.80		<u> </u>		16	<u> </u>		\perp	** <u>*</u>
			3.00	H.86	V			17			_	
			3.15	14. 80				18			1_	
			3.30	14.80	"			19	ļ		_	
			3.45	14.26			_	20	<u> </u>		$oldsymbol{\perp}$	
		1	700	1481				22			1	
			415	14.86	11			24	<u> </u>		_	
			4.30	14.80	11			26	<u> </u>		1_	
		Ů.	4.45	14.81		<u> </u>		28	1		1	
			5.00	14,86				30	1		1	
			5.30	14.80	. 11				1		1_	
			6.00	14.85	1.3	3					1	
			6,30	14.95	11			_	1			

•	1250	3 .	V. 7 3
4	GERAC	HT	,
A	GERAC & MILLE	R.II	Car
ARCH.	C IVEL CONT		הייבו

DISTANCE FROM WELL

MEASURED TO PUMPING

DISCHARGE, RATE

WATER LEVEL/PUMPING TEST RECO

Ground Water Connellents		在特別
PROJECT SWEAK	Chus Slug (St WELL MW-5	SITE Diction NY
SCREEN 4191	MEASURING POINT TOC (PVC)	HEIGHT ABOVE
STATIC 3.18	DESCRIPTION MEASURED WITH M-SCOPE	GROUND SURFACE DATE/TIME/-/7-95-
WATER LEVEL	•	DATE TIME
DRAWDOWN	START OF TEST //: 20	PUMPING
RECOVERY []	END OF TEST 11: 45	WELL
DICTARICE FOOR A VAICE		67 Will 18 18

ORIFICE

VELL (r		HELD (ft)	WET (P)	25251.50	(10)		ART. ²¹ e* (ft)	70.	A sta	MANO. METER	REMARKS [®]
-	MW-S	. 34.	Contract of	3 27 2	38	. .			1 Plus	3	郑威斯 马。福度200
		. /	is hal		4				Wille	CT AND	韩国是 图书:
. r	*.			grey with							A. Carrier
			10	2113	1.34			100	4.06	.28	
			.201	<u></u>				7.30	4.03	725	59
•			130	5.03	1.25	1			4.01		
,			.40	4.96	1.18	1		8.30	3.99	.21	
			.50	4,40	+	+		9.00	390	.18	
			1.00	11. 36	1.08	<u> </u>	<u> </u>		5,9:1		
			1.15	4.80	1.00	+	<u> </u>	10.00	2,93		
	ļ		1.30	4.33	-	ļ	 	11	1	.12	
			1.45	4.66	1		-	12	355	1 1 1	
			2.06	4.61	1.83		<u> </u>		3,80		
			2.15	4.58	_	+	<u> </u>	14	3, 83	.05	
			2.30	4.54	1.76		 	15	3, 93	105	
			2.45	4.48				16		.04	
	ļ		3.00	4.44	1.66			7	3.91		A Sept.
	ļ		3.15	4.41	1.63		<u> </u>	18	3.5	102	
	ļ	<u> </u>	3.30	4,38	160		ļ	19	ļ		
	ļ		3 75	4,35				8			
·	ļ	ļ	4.00	4.31	.53	3		22	ļ	ļ	
		-	4.15	4.28				24 26			
	-	<u> </u>	4.30				 	06			
		-	4.45				-	28	 	 	
	 		500				-	30	-	 	
	-	 	5.30	4,10	1.39		4	 	-		
	ļ	 		4.12	1.3			-	-	-	
	1		6.30	4,09	1,31					1	

4	7	GER	AGI	HT	1
S	8	MIL	LE	R, II	AC.
AD'	Orpe	mf We	w C	pand	

WATER LEVEL/PUMPING TEST RECORD

	A Section	AP D A	ANIA D	23	
•	PA A	^ - 1	÷ Y	12-	~=
•				-	100-
100	יחו				v,
*		mid-a			-44

وموسوا والأناء	The second of the second	1 - m - m 123	S. C. S.	· · · · · · · · · · · · · · · · · · ·	御知道書書 これませんごう
PROJECT Syracus	e China J	way T WELL !	1W-6	SITE SMACHA	NY
SCREEN 5-15	MEASURING POINT	TOC	(PUC)	HEIGHT ABOVE	1 m
SETTING	DESCRIPTION		•	GROUND SURFACE	All the Ca
STATIC 2.63	MEASURED WITH_	M-Sco	pe	_ DATE/TIME	17-95
WATER LEVEL				÷.	: Y
DRAWDOWN []	START OF TEST	10:05		PUMPING	* *
RECOVERY D' 🛱	END OF TEST	10:15	. 32 🔾	METT STATES	4.
DISTANCE FROM WELL	DISCHARGE	383 8 K 38 	(¥(•(b)	_ ORIFICE	- AN
MEASURED TO PUMPING WELL (r)	RATE			r andrie	

DATE & TIME	WELL OR 1 (mins)	HELD ,	WET	DEPTH TO WATER (ft)	s (ft)	DEW. ¹⁾ CORR. (ft)	ART. ²³ . 8' (ft)	Time	De pth	WELEU	REMARKS*
1-	MWY		Marija	٠,٠٠٠	• 1	¥II		- 4.13 -5	Waty	5	AND THE REAL PROPERTY.
ţ÷.			initial			, 5 2	17.7			1047	AND THE RESERVE OF THE
			ģ.	(i) (i)				22	1 182		
			. 10	× 8				7.00	226	113	
			. 10	3213	1.28			7.30	3.75	./2	
			.30	375	1.12			8.00	2.74	.11	
			.40	365	102		<u> </u>	8 30	2.72	.09	
			.50	358	.95			9.00	2,72	.09	
			1.00	351	. 88			9.30		.08	
			1.15	343	, 80			10.00	2.70	.07	10:15 am-end
			1,30	3,35	.7	4		11	<u> </u>		
			1.45	3.28	. 6	5		12	ļ		
			2.00	3.21	. 25			13	ļ		
			2.15	3.15	. 52		ļ	14	<u> </u>		
		<u> </u>	2.30	3.10	1.47	-	<u> </u>	15	<u> </u>		# ·
ļ	1		2.45	3.00			<u> </u>	16	<u> </u>		
ļ	<u> </u>		3.00	3.02	.39	1	2	7	1		. #
	1	ļ	3.15	2.99	136	2		18			
		ļ	3.30	2.96	1.33	3		19	ļ	ļ	
		<u> </u>	3.45		, 3	0		20		ļ	
			4.00	0.91	, 29		딒	22	 	ļ	
	_	<u> </u>	4.15	2.89	. 2			24		ļ	
		_	4.30	2.87	124			24			
<u> </u>	-	_	4.45	2.80				28		 	
	 	ļ	5.00		.21			30		-	
			5.30	1	, 18		_				
			6.00	9.70							
			6.30	12.7:	7.1						

	GERACHTY Of MILLER, INC. Oround-Weter Consultants	WATER LEVEL	/PUMPING	TEST RECORD	Promison of	D
1	syawa	Church with		1911 11 11 11 11 11 11 11 11 11 11 11 11		•
•	PROJECT	0.00 Swg Test	WELL M	W- SITE SG	racine; PJ #	_
	SCREEN 51 151	MEASURING POINT	TOC (P	VC) HEIGHT A	BOVE	
		DESCRIPTION		GROUND	SURFACE	•
	STATIC 5.02	MEASURED WITH	M-Scope	DATE/TIM	E 1-17-95	_
	WATER LEVEL		•		N	
	DRAWDOWN	START OF TEST	1:14	PUMPING	***	_
2	RECOVERY	END OF TEST	1:24	WELL		
	DISTANCE FROM WELL	DISCHARGE		ORIFICE _		
	MEASURED TO PUMPING	RATE		0111100		_

		+1			1.9		1		·	21 34.5	
DATE & TIME	WELL OR t (mins)	HELD (ft)	WET IN Time	DEPTH TO WATER (ft)	: (ft)	DEW. ¹⁾ CORR. (ft)	ART, ²¹ 8', (ft)	Time	de la	MANO	REMARKS
				• • •				·	Weter	3	2017年11日
	MW-		initial						1	. A \$4.	· · · · · · · · · · · · · · · · · · ·
	-							:		20.5 - 10.5	
			.10	n ng i	- FA		٠.	7.00	5.19	.17	<u>-</u>
			.20	6.31	1,29	}		7.30	5.17	.15	
			,30	6.20	1.18			8.00	5:15	./3	
			.40	6.11	1.09			830		1	
			.50	6.03	1.01			920		./0	
			1.00	5,99	.97			9.30	5,1/		
			1.15	5.91	.89			10,00			
			1.30	5.83	.81			11.00		1	124 end
			1.45	5.79	1.77			12			
			2.00	5.71	.69			13			6
			2.15	5.66	1.64	A		14			
			2.30	5.61	.59			15			
			2.45	5.57	.55	1		16			
			3.00	5.53	.5/			17			
			3.15	5.50	.48	U.		18			
			3.30	5.46	.44	4		19			
			3.45	6.42	.40			20			
			4.00	9.40				22			
			4.15	5,37	135	7		231			
			4.30	5, 35				26			:
			4.45	1				28			
			5.00		.29			30			
			5.30		.25						provide the formation of the first state of the fir
			6.00	- 1							
			6.30	1	.19						


C- ---- 07 1751


Modeling Group AQTESOLV GERAGHTY & MILLER, SYRACUSE CHINA LANDFILL SLUG TEST MW-1 1. primingini primingi 1.E-002 humulmumhumuhumuhumuh 0. 4.4 8.8 13.2 17.6 22 6.2664E-005 ft/min 0.1

Drawdown (ft)


INC.


Time (min)






Drawdown (ft)






SYRACUSE CHINA LANDFILL SLUG TEST MW-5 10. Errmmynnminnminnminnminnmin 3.3802E-004 ft/min × L




Drawdown (ft)

Drawdown (ft)



Drawdown (ft)



APPENDIX F

DATA VALIDATION

MEMORANDUM

TO:

Marc Sanford

FROM:

Lisa Westbay

DATE:

September 11, 1995

SUBJECT:

Inorganic Data Validation of Samples Collected at the Syracuse China Site,

Syracuse, New York (Project No. AY0146.017).

Groundwater, surface water, and sediment samples were collected at the Syracuse China site located in Syracuse, New York. The samples were sent to Industrial and Environmental Analysts, Inc. (IEA) in Monroe, Connecticut for the analysis of target analyte list (TAL) metals and cyanide. Analyses were performed following the United States Environmental Protection Agency (USEPA) Contract Laboratory Program (CLP) Statement of Work (SOW) for Inorganics as specified in the New York State Department of Environmental Conservation (NYSDEC) Analytical Services Protocol (ASP) dated September 1989, revised December 1991.

Validation of the laboratory data was performed following the quality assurance/quality control (QA/QC) criteria set forth in the "USEPA Laboratory Data Validation Functional Guidelines for Evaluating Inorganic Analyses" dated July 1988 and the NYSDEC ASP. Eight groundwater samples, one field duplicate, one field blank, eight surface water, and nine sediment samples were sent to IEA for analysis. The quality of the data was acceptable with the appropriate qualifications described in this memorandum.

INORGANIC DATA VALIDATION SUMMARY

Two data packages (sample delivery groups [SDGs]) were provided by the laboratory for metal and cyanide sample results. The validation results for each SDG are discussed separately below.

SDG Z1154 RESULTS - TOTAL METALS

Sample results for nine groundwater samples (including one field duplicate), six surface water (two samples were analyzed for lead only), and five sediment samples (one was analyzed for lead only) were reported in this SDG.

Holding Times

All samples were analyzed within holding time requirements.

Calibration

The initial and continuing calibration requirements were met.

Blanks

The following analytes were detected in the Field Blank (reported in SDG A1154):

Analysis Date	<u>Analyte</u>	Concentration (ug/L)
August 21, 1995 August 21, 1995 August 21, 1995 August 21, 1995 August 21, 1995 August 21, 1995 August 21, 1995	Aluminum Calcium Iron Lead Magnesium Manganese Nickel	28.0 B 202 B 70.1 B 3.0 B 50.4 B 2.0 B 7.8 B
August 21, 1995	Zinc	27.6

New, disposable bailers were used to collect groundwater samples at each monitoring well except at MW-4I and MW-7, where reusable Teflon bailers were used. Therefore, only results for locations MW-4I and MW-7 are subject to qualification due to field blank results. The following sample results were qualified as non-detect (U) based on field blank results:

Sample ID	<u>Analyte</u>	Concentration (ug/L)
MW-7	Nickel	21.2 U
MW-7	Zinc	75.7 U

The following analytes were detected in the initial calibration blanks (ICBs):

Analysis Date	<u>Analyte</u>	Concentration (ug/L)
August 21, 1995	Calcium	8.0 B
August 30, 1995	Magnesium	7.9 B

The following analytes were detected in the continuing calibration blanks (CCBs):

August 21, 1995 1	Analysis Date	CCB#	Analyte	Concentration (ug/L)
August 21, 1995 1 Silver 2.0 B August 21, 1995 2 Copper 6.7 B August 21, 1995 2 Iron 11.6 B August 21, 1995 3 Aluminum 24.5 B August 21, 1995 3 Calcium 25.0 B August 21, 1995 3 Calcium 25.0 B August 21, 1995 3 Copper 6.7 B August 21, 1995 3 Copper 6.7 B August 21, 1995 3 Iron 19.8 B August 21, 1995 4 Calcium 53.2 B August 21, 1995 4 Calcium 53.2 B August 21, 1995 5 Copper 6.1 B August 21, 1995 5 Copper 6.1 B August 21, 1995 6 Copper 6.1 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Vanadium 1.2 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 7 Aluminum 25.2 B August 28, 1995 7 Magnesium 15.7 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Aluminum 23.4 B August 28, 1995 10 Aluminum 23.4 B August 30, 1995 10 Magnesium 20.5 B August 30, 1995 11 Aluminum 20.5 B August 30, 1995 11 Aluminum 20.5 B August 30, 1995 11 Aluminum 34.8 B	August 21, 1995	1	Iron	10 0 R
August 21, 1995 1 Silver 2.0 B August 21, 1995 2 Copper 6.7 B August 21, 1995 3 Aluminum 24.5 B August 21, 1995 3 Calcium 25.0 B August 21, 1995 3 Copper 6.7 B August 21, 1995 3 Copper 6.7 B August 21, 1995 3 Copper 6.7 B August 21, 1995 3 Iron 19.8 B August 21, 1995 4 Calcium 53.2 B August 21, 1995 4 Calcium 53.2 B August 21, 1995 5 Copper 6.1 B August 21, 1995 5 Copper 6.1 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Vanadium 1.2 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 6 Vanadium 1.2 B August 21, 1995 6 Magnesium 19.8 B August 28, 1995 7 Aluminum 25.2 B August 28, 1995 7 Calcium 19.7 B August 28, 1995 8 Aluminum 15.7 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 8 Magnesium 15.7 B August 28, 1995 8 Magnesium 15.7 B August 28, 1995 9 Aluminum 91.8 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Magnesium 30.7 B August 28, 1995 10 Aluminum 23.4 B August 30, 1995 10 Magnesium 20.5 B August 30, 1995 11 Aluminum 34.8 B		1	Magnesium	
August 21, 1995 2 Iron 11.6 B August 21, 1995 3 Aluminum 24.5 B August 21, 1995 3 Calcium 25.0 B August 21, 1995 3 Copper 6.7 B August 21, 1995 3 Copper 6.7 B August 21, 1995 3 Iron 19.8 B August 21, 1995 3 Iron 19.8 B August 21, 1995 4 Calcium 53.2 B August 21, 1995 4 Iron 13.9 B August 21, 1995 5 Copper 6.1 B August 21, 1995 5 Copper 6.1 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Iron 19.3 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 6 Vanadium 1.2 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 7 Aluminum 25.2 B August 28, 1995 7 Calcium 19.7 B August 28, 1995 7 Magnesium 15.7 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Magnesium 30.7 B August 28, 1995 9 Magnesium 30.7 B August 28, 1995 10 Aluminum 23.4 B August 30, 1995 10 Magnesium 20.5 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B		1	_	
August 21, 1995 2 Iron 11.6 B August 21, 1995 3 Aluminum 24.5 B August 21, 1995 3 Calcium 25.0 B August 21, 1995 3 Copper 6.7 B August 21, 1995 3 Iron 19.8 B August 21, 1995 4 Calcium 53.2 B August 21, 1995 4 Iron 13.9 B August 21, 1995 5 Copper 6.1 B August 21, 1995 5 Vanadium 1.2 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Iron 19.3 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 6 Vanadium 1.2 B August 21, 1995 6 Magnesium 19.8 B August 22, 1995 7 Aluminum 25.2 B August 28, 1995 7 Aluminum 25.2 B August 28, 1995 8 Aluminum 15.6 B August 28,	August 21, 1995	2	Copper	
August 21, 1995 3 Aluminum 24.5 B August 21, 1995 3 Calcium 25.0 B August 21, 1995 3 Copper 6.7 B August 21, 1995 3 Iron 19.8 B August 21, 1995 3 Vanadium 1.4 B August 21, 1995 4 Calcium 53.2 B August 21, 1995 4 Iron 13.9 B August 21, 1995 5 Copper 6.1 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Iron 19.3 B August 21, 1995 6 Iron 19.3 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 6 Vanadium 1.2 B August 21, 1995 6 Vanadium 1.2 B August 22, 1995 7 Aluminum 25.2 B August 28, 1995 7 Aluminum 25.2 B August 28, 1995 7 Magnesium 15.7 B August 28, 1995 8 Aluminum 91.8 B August 28	August 21, 1995	2		
August 21, 1995 3 Calcium 25.0 B August 21, 1995 3 Copper 6.7 B August 21, 1995 3 Iron 19.8 B August 21, 1995 4 Calcium 53.2 B August 21, 1995 4 Iron 13.9 B August 21, 1995 5 Copper 6.1 B August 21, 1995 5 Copper 6.1 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Iron 19.3 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 6 Vanadium 1.2 B August 21, 1995 6 Vanadium 19.8 B August 21, 1995 6 August 21, 1995 6 August 21, 1995 6 August 21, 1995 6 August 21, 1995 7 Aluminum 25.2 B August 28, 1995 7 Calcium 19.7 B August 28, 1995 7 Magnesium 15.7 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Iron 16.4 B August 28, 1995 8 Magnesium 40.9 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Aluminum 36.0 B August 28, 1995 9 Magnesium 30.7 B August 28, 1995 9 Magnesium 30.7 B August 28, 1995 10 Aluminum 23.4 B August 30, 1995 10 Magnesium 20.5 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B	August 21, 1995	3	Aluminum	
August 21, 1995 3 Iron 19.8 B August 21, 1995 3 Iron 19.8 B August 21, 1995 4 Calcium 53.2 B August 21, 1995 4 Iron 13.9 B August 21, 1995 5 Copper 6.1 B August 21, 1995 5 Copper 6.1 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Iron 19.3 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 6 Vanadium 1.2 B August 21, 1995 6 Vanadium 19.8 B August 21, 1995 6 Vanadium 19.8 B August 21, 1995 7 Aluminum 25.2 B August 28, 1995 7 Calcium 19.7 B August 28, 1995 8 Aluminum 15.7 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Iron 16.4 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Calcium 36.0 B August 28, 1995 9 Calcium 30.7 B August 28, 1995 10 Aluminum 23.4 B August 30, 1995 10 Magnesium 20.5 B August 30, 1995 10 Magnesium 20.5 B August 30, 1995 11 Aluminum 34.8 B	August 21, 1995	3	Calcium	
August 21, 1995 3 Iron 19.8 B August 21, 1995 3 Vanadium 1.4 B August 21, 1995 4 Calcium 53.2 B August 21, 1995 4 Iron 13.9 B August 21, 1995 5 Copper 6.1 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Iron 19.3 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 6 Vanadium 1.2 B August 21, 1995 6 Vanadium 19.8 B August 28, 1995 7 Aluminum 25.2 B August 28, 1995 7 Aluminum 25.2 B August 28, 1995 7 Magnesium 15.7 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Potassium 15.6 B August 28, 1995 9 Aluminum 47.3 B <t< td=""><td>August 21, 1995</td><td>3</td><td>·</td><td></td></t<>	August 21, 1995	3	·	
August 21, 1995 3 Vanadium 1.4 B August 21, 1995 4 Calcium 53.2 B August 21, 1995 4 Iron 13.9 B August 21, 1995 5 Copper 6.1 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Iron 19.3 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 6 Vanadium 1.2 B August 21, 1995 6 Vanadium 1.2 B August 28, 1995 7 Aluminum 25.2 B August 28, 1995 7 Aluminum 19.7 B August 28, 1995 7 Magnesium 19.7 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Aluminum 47.3 B August 30, 1995 10 Aluminum 23.4 B	August 21, 1995	3		
August 21, 1995 4 Calcium 53.2 B August 21, 1995 4 Iron 13.9 B August 21, 1995 5 Copper 6.1 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Iron 19.3 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 6 Vanadium 1.2 B August 28, 1995 7 Aluminum 25.2 B August 28, 1995 7 Calcium 19.7 B August 28, 1995 7 Magnesium 15.7 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Iron 16.4 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 8 Potassium 40.9 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Aluminum 47.3 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Aluminum 20.2 B	August 21, 1995	3		
August 21, 1995 4 Iron 13.9 B August 21, 1995 5 Copper 6.1 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Iron 19.3 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 6 Vanadium 1.2 B August 22, 1995 7 Aluminum 25.2 B August 28, 1995 7 Calcium 19.7 B August 28, 1995 7 Magnesium 15.7 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 8 Potassium 40.9 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Magnesium 30.7 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Magnesium 20.2 B	August 21, 1995	4	· ·	
August 21, 1995 5 Copper 6.1 B August 21, 1995 5 Vanadium 1.2 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Iron 19.3 B August 21, 1995 6 Magnesium 19.8 B August 22, 1995 6 Vanadium 1.2 B August 28, 1995 7 Aluminum 25.2 B August 28, 1995 7 Calcium 19.7 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Iron 16.4 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 8 Potassium 40.9 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Aluminum 36.0 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Aluminum 20.2 B August 30, 1995 10 Magnesium 20.5 B		4	Iron	
August 21, 1995 5 Vanadium 1.2 B August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Iron 19.3 B August 21, 1995 6 Magnesium 19.8 B August 22, 1995 7 Aluminum 25.2 B August 28, 1995 7 Calcium 19.7 B August 28, 1995 7 Magnesium 15.7 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Iron 16.4 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 8 Potassium 40.9 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Magnesium 30.7 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Magnesium 20.2 B August 30, 1995 10 Magnesium 20.5 B August 30, 1995 11 Aluminum 24.1 B	August 21, 1995	5	Copper	
August 21, 1995 6 Copper 3.6 B August 21, 1995 6 Iron 19.3 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 6 Vanadium 1.2 B August 28, 1995 7 Aluminum 25.2 B August 28, 1995 7 Calcium 19.7 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Calcium 36.0 B August 28, 1995 9 Magnesium 30.7 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Magnesium 20.2 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B		5		
August 21, 1995 6 Iron 19.3 B August 21, 1995 6 Magnesium 19.8 B August 21, 1995 6 Vanadium 1.2 B August 28, 1995 7 Aluminum 25.2 B August 28, 1995 7 Calcium 19.7 B August 28, 1995 8 Aluminum 15.7 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Iron 16.4 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 8 Potassium 40.9 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Calcium 36.0 B August 28, 1995 9 Magnesium 30.7 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Magnesium 20.2 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B		6		·
August 21, 1995 6 Magnesium 19.8 B August 21, 1995 6 Vanadium 1.2 B August 28, 1995 7 Aluminum 25.2 B August 28, 1995 7 Calcium 19.7 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Iron 16.4 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 8 Potassium 40.9 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Magnesium 36.0 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Magnesium 20.2 B August 30, 1995 10 Magnesium 20.5 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B	August 21, 1995	6		· · · · -
August 21, 1995 6 Vanadium 1.2 B August 28, 1995 7 Aluminum 25.2 B August 28, 1995 7 Calcium 19.7 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Iron 16.4 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Calcium 36.0 B August 28, 1995 9 Magnesium 30.7 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Magnesium 20.2 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B	August 21, 1995	6	Magnesium	_
August 28, 1995 7 Aluminum 25.2 B August 28, 1995 7 Calcium 19.7 B August 28, 1995 8 Aluminum 15.7 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Iron 16.4 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Calcium 36.0 B August 28, 1995 9 Magnesium 30.7 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Magnesium 20.2 B August 30, 1995 10 Magnesium 20.5 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B		6	•	· —
August 28, 1995 7 Calcium 19.7 B August 28, 1995 8 Aluminum 15.7 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Iron 16.4 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Calcium 36.0 B August 28, 1995 9 Magnesium 30.7 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Magnesium 20.2 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B	<u> </u>	7	· · · · · · · · · · · · · · · · · · ·	_
August 28, 1995 7 Magnesium 15.7 B August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Iron 16.4 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Calcium 36.0 B August 28, 1995 9 Magnesium 30.7 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Magnesium 20.2 B August 30, 1995 10 Magnesium 20.5 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B	August 28, 1995	7	Calcium	
August 28, 1995 8 Aluminum 91.8 B August 28, 1995 8 Iron 16.4 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Calcium 36.0 B August 28, 1995 9 Magnesium 30.7 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Magnesium 20.2 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B	August 28, 1995	7		
August 28, 1995 8 Iron 16.4 B August 28, 1995 8 Magnesium 15.6 B August 28, 1995 9 Aluminum 40.9 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Calcium 36.0 B August 28, 1995 9 Magnesium 30.7 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Magnesium 20.2 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B	August 28, 1995	8		
August 28, 1995 8 Magnesium 15.6 B August 28, 1995 8 Potassium 40.9 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Calcium 36.0 B August 28, 1995 9 Magnesium 30.7 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Magnesium 20.2 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B	August 28, 1995	8	Iron	
August 28, 1995 8 Potassium 40.9 B August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Calcium 36.0 B August 28, 1995 9 Magnesium 30.7 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Calcium 20.2 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B		8	Magnesium	-
August 28, 1995 9 Aluminum 47.3 B August 28, 1995 9 Calcium 36.0 B August 28, 1995 9 Magnesium 30.7 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Calcium 20.2 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B	August 28, 1995	8		-
August 28, 1995 9 Calcium 36.0 B August 28, 1995 9 Magnesium 30.7 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Calcium 20.2 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B	August 28, 1995	9	·	
August 28, 1995 9 Magnesium 30.7 B August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Calcium 20.2 B August 30, 1995 10 Magnesium 20.5 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B	August 28, 1995	9	· — —	
August 30, 1995 10 Aluminum 23.4 B August 30, 1995 10 Calcium 20.2 B August 30, 1995 10 Magnesium 20.5 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B	August 28, 1995	9		
August 30, 1995 10 Calcium 20.2 B August 30, 1995 10 Magnesium 20.5 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B	August 30, 1995	10	_	
August 30, 1995 10 Magnesium 20.5 B August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B		10		
August 30, 1995 11 Aluminum 34.8 B August 30, 1995 11 Calcium 24.1 B	August 30, 1995	10		-
August 30, 1995 11 Calcium 24.1 B		11	_	
August 20, 1005		11	· · · 	
	August 30, 1995	11	· 	

The following analytes were detected in the aqueous preparation blank (PB):

Analysis Date	<u>Analyte</u>	Concentration (ug/L)
August 21, 1995	Calcium	9.870 B
August 21, 1995	Copper	4.610 B
August 21, 1995	Iron	12.040 B

The following sample results were qualified as non-detect (U) based on blank results:

Sample ID	Analyte	Concentration (ug/L)
MW-1 MW-1 MW-2 MW-4 MW-5 MW-5 SW-1 SW-1 SW-2 SW-3 SW-4	Copper Vanadium Copper Copper Copper Vanadium Copper Vanadium Copper Copper Copper Copper	18.0 U 1.6 U 27.6 U 14.9 U 7.1 U 2.3 U 15.7 U 7.1 U 12.8 U 6.5 U 9.0 U

Inductively Coupled Plasma Interference Check Sample

The percent recoveries for inductively coupled plasma (ICP) interference check sample (ICS) analyses were within the control limits of $\pm 20\%$ of the true value, with the following exceptions in the final solution AB:

Analysis Date	<u>Analyte</u>	<u>%R</u>
August 21, 1995	Chromium	79.7
August 21, 1995	Cobalt	78.2
August 21, 1995	Manganese	78.7
August 21, 1995	Nickel	78.0

The following sample results were qualified as estimated (J) due to ICP results:

Sample ID	<u>Analyte</u>	Concentration (ug/L)
MW-3	Calcium	656,000 J
MW-4I	Calcium	792,000 J

Laboratory Control Sample

Laboratory control sample (LCS) results were within the control limits.

Duplicate Sample Analysis

Two samples were designated for duplicate analysis. The relative percent difference (RPD) values for each were within the control limits.

Matrix Spike Sample Analysis

Two samples were designated for matrix spike sample analysis. The percent recoveries (%R) were within the control limits, with the following exceptions:

Sample ID	Analyte	<u>%R</u>
SED-1	Antimony	42.9
SED-1	Mercury	179.0
SED-1	Zinc	74.8
SED-1	Cyanide	20.6

The following data were estimated (J or UJ) due to matrix spike results:

Sample ID	<u>Analyte</u>	Concentration (mg/kg)
SED-1 SED-1 SED-2 SED-3 SED-3 SED-4 SED-4	Antimony Zinc Antimony Zinc Antimony Zinc Antimony Zinc Antimony Zinc	2.4 UJ 599 J 4.2 BJ 796 J 4.3 UJ 722 J 6.3 UJ 775 J

Mercury was not detected in the associated samples; therefore, qualification of the mercury data were not necessary. Cyanide results in associated samples were rejected due to low (<30%) matrix spike recovery.

A post digestion spike was performed for antimony, zinc, and cyanide. The spike recoveries were within the control limits.

Furnace Atomic Absorption Quality Control

The method of furnace atomic absorption was not used for analysis of samples in this package.

Inductively Coupled Plasma Serial Dilution

Samples SED-1 and SW-1 were designated for ICP serial dilution analysis. The ICP serial dilution results were within the control limits, with the following exceptions:

Sample ID	<u>Analyte</u>	<u>%D</u>
SW-1	Magnesium	12.9
SW-1	Sodium	10.6

Due to high percent differences (>10%), magnesium and sodium results in associated samples (aqueous samples), were qualified as estimated (J or UJ).

Sample Result Verification

Discrepancies were not found between the reported results and the QC data package.

Field Duplicate

A field duplicate was collected at location MW-6 and labelled Rep-1. The following analytes were detected in the sample and duplicate collected from sampling location MW-6, along with the corresponding RPD value:

Analyte	Sample MW-6 Concentration (ug/L)	Replicate Concentration (ug/L)	%RPD
Aluminum	41600	46600	11
Arsenic	27.6	35.6	25
Barium	545	541	1
Beryllium	5.4	7.2	29
Calcium	477000	518000	8
Chromium	76.4	87.6	14
Cobalt	60.2	63.0	4
Copper	276	260	6
Iron	85100	95500	12
Lead	56.5	56.9	1
Magnesium	158000	179000	12
Manganese	2790	3080	10
Mercury	0.20 B	0.20 U	0
Nickel	106	119	12
Potassium	10100	10100	0
Selenium	6.0	6.9	14
Silver	41.8	4.0 B	165
Sodium	19300	21700	12
Vanadium	56.9	58.1	2
Zinc	342	342	0

Based on the field duplicate results, it is this data reviewer's professional opinion that because the silver RPD value is high, all positive silver results for the aqueous samples should be qualified as estimated (J), including the results reported in SDG A1154. It is also this data reviewer's opinion that further qualification of the data was not necessary based on the field duplicate results.

Overall Assessment of Data for the Case

The quality of the inorganic data presented in this QC data package is acceptable with the appropriate qualifications described in this memorandum.

SDG Z1154 RESULTS - DISSOLVED METALS

Sample results for nine groundwater samples (including one field duplicate) were reported in this SDG.

Holding Times

All samples were analyzed within holding time requirements.

Calibration

The initial and continuing calibration requirements were met.

Blanks

The field blank was not analyzed for dissolved metals. Therefore, the data were evaluated against initial, continuing, and preparation blanks only. The following analytes were detected in the ICBs:

Analysis Date	<u>Analyte</u>	Concentration (ug/L)
August 23, 1995	Aluminum	23.0 B
August 23, 1995	Magnesium	7.0 B

The following analytes were detected in the CCBs:

Analysis Date	CCB#	Analyte	Concentration (ug/L)
August 28, 1995	1	Aluminum	36.0 B
August 28, 1995	1	Calcium	18.2 B
August 28, 1995	1	Copper	-2.1 B
August 28, 1995	1	Magnesium	17.9 B
August 28, 1995	2	Aluminum	25.8 B
August 28, 1995	2	Beryllium	1.6 B
August 28, 1995	2	Copper	-2.5 B

Analysis Date	CCB#	<u>Analyte</u>	Concentration (ug/L)
August 28, 1995	2	Magnesium	9.1 B
August 28, 1995	2	Potassium	33.6 B
August 28, 1995	2	Vanadium	12.0 B
August 28, 1995	3	Aluminum	40.0 B
August 28, 1995	3	Beryllium	2.0 B
August 28, 1995	3	Copper	-3.5 B
August 28, 1995	3	Magnesium	10.2 B
August 28, 1995	3	Vanadium	5.9 B
August 28, 1995	4	Aluminum	59.3 B
August 28, 1995	4	Beryllium	1.8 B
August 28, 1995	4	Calcium	23.8 B
August 28, 1995	4	Copper	-3.8 B
August 28, 1995	4	Magnesium	22.9 B

The following analytes were detected in the preparation blank (PBs):

Analysis Date	<u>Analyte</u>	Concentration (ug/L)
August 23, 1995	Aluminum	22.714 B

The following sample results were qualified as non-detect (U) based on blank results:

Sample ID	<u>Analyte</u>	Concentration (ug/L)
MW-2 MW-6 MW-7 MW-4I MW-4I MW-4I	Copper Vanadium Vanadium Beryllium Copper Vanadium	3.8 U 3.0 U 8.3 U 1.3 U 2.7 U
Rep-1 Rep-1	Beryllium Vanadium	15.3 U 1.2 U 3.7 U

Inductively Coupled Plasma Interference Check Sample

The percent recoveries for ICP ICS analyses were within the control limits.

Laboratory Control Sample

LCS results were within the control limits.

Duplicate Sample Analysis

One water sample was designated for duplicate analysis. The RPD values were within the control limits.

Matrix Spike Sample Analysis

One water sample was designated for matrix spike sample analysis, in which the percent recoveries were within the control limits.

Furnace Atomic Absorption Quality Control

The method of furnace atomic absorption was not used for analysis of samples in this package.

Inductively Coupled Plasma Serial Dilution

Sample MW-4 was designated for ICP serial dilution analysis. The ICP serial dilution results were within the control limits, with the following exception:

Sample ID	Analyte	<u>%D</u>
MW-4L	Calcium	10.4

Calcium results in associated data were qualified as estimated (J) due to ICP serial dilution results.

Sample Result Verification

Discrepancies were not found between the reported results and the QC data package.

Field Duplicate

A field duplicate was collected at location MW-6 and labelled Rep-1. The following analytes were detected in the sample and duplicate collected from sampling location MW-6, along with the corresponding RPD value:

<u>Analyte</u>	Sample MW-6 Concentration (ug/L)	Replicate Concentration (ug/L)	%RPD
Aluminum	3040	4320	35
Antimony	4.0 B	3.9 B	33
Barium	93.4 B	111 B	17
Beryllium	1.0 U	1.2 B	100
Calcium	92200	90000	2
Chromium	4.7 B	6.2 B	28
Iron	2090	2950	34
Lead	3.6	3.2	12
Magnesium	20500	23400	13
Manganese	121	152	23
Nickel	5.0 B	7.6 B	41

<u>Analyte</u>	Sample MW-6 Concentration (ug/L)	Replicate Concentration (ug/L)	%RPD
Potassium	2660	3480	27
Sodium	17400	15200	13
Vanadium	3.0 B	3.7 B	21
Zinc	56.6	15.0 B	116

Based on the field duplicate results, it is this data reviewer's professional opinion that because the zinc RPD value is high, all positive zinc results in the associated samples should be qualified as estimated (J). It is also this data reviewer's opinion that further qualification of the data was not necessary based on the field duplicate results.

Overall Assessment of Data for the Case

The quality of the inorganic data presented in this QC data package is acceptable with the appropriate qualifications described in this memorandum.

SDG A1154 RESULTS

Sample results for two surface-water samples, four sediment samples (two were analyzed for lead only), and one field blank are reported in SDG A1154. The validation results for SDG A1154 are discussed below.

Holding Times

All samples were analyzed within holding time requirements.

Calibration

The initial and continuing calibration requirements were met.

Blanks

The following analytes were detected in the Field Blank:

Analysis Date	Analyte	Concentration (ug/L)
August 21, 1995 August 21, 1995	Aluminum Calcium Iron Lead Magnesium Manganese Nickel Zinc	28.0 B 202 B 70.1 B 3.0 B 50.4 B 2.0 B 7.8 B 27.6

The following analytes were detected in the ICBs:

Analysis Date	Analyte	Concentration (ug/L)
August 21, 1995	Calcium	8.0 B
August 30, 1995	Magnesium	7.9 B

The following analytes were detected in the CCBs:

Analysis Date	CCB#	Analyte	Concentration (ug/L)
August 21, 1995	1	Iron	19.9 B
August 21, 1995	1	Magnesium	19.7 B
August 21, 1995	1	Silver	2.0 B
August 21, 1995	2	Copper	6.7 B
August 21, 1995	2	Iron	11.6 B
August 21, 1995	3	Aluminum	24.5 B
August 21, 1995	3	Calcium	25.0 B
August 21, 1995	3	Copper	6.7 B
August 21, 1995	3	Iron	19.8 B
August 21, 1995	3	Vanadium	1.4 B
August 21, 1995	4	Calcium	53.2 B
August 21, 1995	4	Iron	13.9 B
August 21, 1995	5	Copper	6.1 B
August 21, 1995	5	Vanadium	1.2 B
August 21, 1995	6	Copper	3.6 B
August 21, 1995	6	Iron	19.3 B
August 21, 1995	6	Magnesium	19.8 B
August 21, 1995	6	Vanadium	1.2 B
August 28, 1995	7	Aluminum	25.2 B
August 28, 1995	7	Calcium	19.7 B
August 28, 1995	7	Magnesium	15.7 B
August 28, 1995	8	Aluminum	91.8 B
August 28, 1995	8	Iron	16.4 B
August 28, 1995	8	Magnesium	15.6 B
August 28, 1995	8	Potassium	40.9 B
August 28, 1995	9	Aluminum	47.3 B
August 28, 1995	9	Calcium	36.0 B
August 28, 1995	9	Magnesium	30.7 B
August 30, 1995	10	Aluminum	23.4 B
August 30, 1995	10	Calcium	20.2 B
August 30, 1995	10	Magnesium	20.5 B
August 30, 1995	11	Aluminum	34.8 B
August 30, 1995	11	Calcium	24.1 B
August 30, 1995	11	Magnesium	23.0 B

The following analytes were detected in the PBs:

Analysis Date	<u>Analyte</u>	Concentration (ug L)
August 21, 1995	Calcium	9.870 B
August 21, 1995	Copper	4.610 B
August 21, 1995	Iron	12.040 B

The following sample results were qualified as non-detect (U) based on blank results:

Sample ID	Analyte	Concentration (ug/L)
SW-5 SW-5	Copper Zinc	8.1 U 46.7 U
SW-6 SW-6	Copper Vanadium	8.6 U 4.0 U

Inductively Coupled Plasma Interference Check Sample

The percent recoveries for all ICP ICS analyses were within the control limits of $\pm 20\%$ of the true value, with the following exceptions:

Analysis Date	<u>Analyte</u>	<u>%R</u>
August 21, 1995	Chromium	79.7
August 21, 1995	Cobalt	78.2
August 21, 1995	Manganese	78.7
August 21, 1995	Nickel	78.0

Since the associated samples contained aluminum, calcium, iron, and magnesium in concentrations at least one order of magnitude less than their respective levels in the interference check sample, qualification of the data was not necessary.

Laboratory Control Sample

LCS results were within the control limits.

Duplicate Sample Analysis

Samples SED-1 and SW-1 were designated for duplicate analysis. The RPD values for each were within the control limits.

Matrix Spike Sample Analysis

Samples SED-1 and SW-1 were designated for matrix spike sample analysis. The percent recoveries (%R) were within the control limits, with the following exceptions:

Sample ID	<u>Analyte</u>	<u>%R</u>
SED-1	Antimony	42.9
SED-1	Mercury	179.0
SED-1	Zinc	74.8
SED-1	Cyanide	20.6

Antimony was not detected in the associated samples, and therefore the associated results were qualified as estimated (UJ). Due to high mercury and low zinc spike recoveries, positive mercury and zinc results were qualified as estimated (J). Cyanide was not detected in the associated samples, and therefore, the results were qualified as unusable (R).

A post digestion spike was performed for antimony, zinc, and cyanide. The spike recoveries were within the control limits.

Furnace Atomic Absorption Quality Control

The method of furnace atomic absorption was not used for analysis of samples in this package.

Inductively Coupled Plasma Serial Dilution

Samples SED-5 and SW-5 were designated for the ICP serial dilution analysis. The ICP serial dilution results were within the control limits.

Sample Result Verification

Discrepancies were not found between the reported results and the QC data package.

Field Duplicate

The field duplicate was not reported in this data package.

Overall Assessment of Data for the Case

The quality of the inorganic data presented in this QC data package is acceptable with the appropriate qualifications described in this memorandum.

MEMORANDUM

TO:

William Gray

FROM:

Lauren Sjogren

DATE:

March 31, 1995

SUBJECT:

Inorganic Data Validation of Samples Collected for the Syracuse China Site

located in Syracuse, New York (Project No. AY0146.004).

Soil samples were collected for the Syracuse China site located in Syracuse, New York. The samples were sent to Industrial and Environmental Analysts, Inc. (IEA) in Monroe, Connecticut for the analysis of target analyte list (TAL) metals and cyanide following the United States Environmental Protection Agency (USEPA) Contract Laboratory Program (CLP) Statement of Work (SOW) for Inorganics as specified in the New York State Department of Environmental Conservation (NYSDEC) Analytical Services Protocol (ASP) dated September 1989, revised December 1991.

Validation of the laboratory data was performed following the quality assurance/quality control (QA/QC) criteria set forth in the "USEPA Laboratory Data Validation Functional Guidelines for Evaluating Inorganics Analyses" dated July, 1988 and the NYSDEC ASP. Twenty-six soil samples, one field duplicate, six field blanks and five trip blanks were sent to IEA for analysis. Sample identification, collection dates, and laboratory received dates are listed in Tables 1 and 2. The quality of the data was acceptable with the appropriate qualifications described in this memorandum.

INORGANIC DATA VALIDATION SUMMARY

Two data packages (sample delivery groups [SDGs]) were provided by the laboratory for metal sample results. The validation results for each SDG are discussed separately below.

SDG Z1368 RESULTS

Ten soil samples are contained in SDG Z1368. These samples were collected on November 28, November 30, December 1, December 2, and December 6, 1994 and received by the laboratory within 48 hours of collection. The validation results for SDG Z1368 are discussed below.

Holding Times

All samples were analyzed within holding time requirements.

Calibration

The correlation coefficients for the lead initial calibrations conducted on December 14, December 15, and December 16, 1994 using graphite furnace atomic absorption spectroscopy (GFAA) were found to be < 0.995. Therefore, because lead was detected the samples analyzed using GFAA, the positive lead results for samples MW-6, MW-7, MW-3I, MW-4I, PSB-5, PSB-4, PSB-1, and PSB-2, were qualified as estimated (J). All other initial and all continuing calibration requirements were met.

Blanks

The following analytes were detected in the initial calibration blanks (ICBs) analyzed:

Analysis DateAnalyte	Concentration (ug/L)	
December 14, 1994	Aluminum	20.2 B
December 14, 1994	Copper	-2.2 B
December 14, 1994	Zinc	-3.1 B
December 14, 1994	Selenium	1.0 B

The "B" qualifier indicates that the concentration detected is between the contract required detected limit (CRDL) and the instrument detection limit (IDL). Because the negative concentration of copper and zinc was not recorded below the negative CRDL for these analytes, in this data reviewer's professional judgement that qualification of the associated copper and zinc sample results was not necessary. Selenium was not detected in any of the samples associated with the positive selenium CCB result. Aluminum was detected in all the samples at concentrations that are above five times the ICB concentrations, therefore, qualification of the aluminum sample results based on the ICB results was not necessary.

The following analytes were detected in the continuing calibration blanks (CCBs) analyzed:

	_	(-,,,
CCB#	Analyte	Concentration (ug/L)
1	Aluminum	21.1 B
1		59.8 B
1		37.1 B
1		-3.7 B
2		-2.8 B
2	Zinc	-4.3 B
3	Zinc	-4.3 B
4	Aluminum	21.8 B
4		-2.2 B
4		59.8 B
4		58.9 B
4	~	-4.3 B
2		-1.1 B
4	Selenium	1.2 B
	1 1 1 2 2 2 3 4 4 4 4 4 4	1 Aluminum 1 Iron 1 Magnesium 1 Zinc 2 Copper 2 Zinc 3 Zinc 4 Aluminum 4 Copper 4 Iron 4 Magnesium 4 Zinc 6 Arsenic

Because the negative concentrations for the analytes listed above were not recorded below the corresponding negative CRDL for these analytes, in this data reviewer's professional judgement that qualification of the sample results based on these CCB results was not necessary. Selenium was not detected in any of the samples associated with the positive selenium ICB result. Aluminum, iron, and magnesium were detected in all the samples at concentrations that are above five times the CCB concentrations for these three analytes, therefore, qualification of the aluminum, iron, and/or magnesium sample results based on the CCB results was not necessary.

The following analytes were detected in preparation blank (PB) analyzed:

Analyte	Concentration (ug/L)
Aluminum	5.7 B
Calcium	24.3 B
Chromium	0.52 B
Copper	2.4 B
Iron	8.9 B
Magnesium	9.0 B

The following copper sample results were qualified as not detected based on the associated PB result:

Analyte	Concentration (ug/L)
MW-3I	8.4 U
MW-4I	7.7 U
PSS-11	6.3 U
PSB-5	10.6 U
PSB-4	10.2 U
PSB-3	7.9 U

The other analytes detected in the PB were also detected in the samples at concentrations greater than five times the PB concentrations. Therefore, further qualification of the sample results based on the PB results was not necessary. No analytes were detected in any of the other blanks. Field blanks were not required for this sampling round.

Inductively Coupled Plasma Interference Check Sample

The percent recoveries for all inductively coupled plasma interference check sample (ICS) analyses were within the control limits of $\pm 20\%$ of the true value.

Laboratory Control Sample

All laboratory control sample (LCS) results were within the control limits.

Duplicate Sample Analysis

Two samples were designated for the duplicate analysis. The chromium relative percent difference (RPD) value was above the control limit for the sample and duplicate collected at MW-6. The calcium, magnesium, and manganese RPD values were above the control limits for the sample and duplicate collected at PSB-5. Therefore, all chromium, calcium, magnesium, and manganese sample results were qualified as estimated (J) if detected and estimated (UJ) if not detected. A sample and duplicate were analyzed for lead using inductively coupled plasma emission spectroscopy (ICP) with the results found to be within the control limits. This duplicate is contained in SDG A1368. All other duplicate sample results were also within the control limits.

Matrix Spike Sample Analysis

Two samples were designated for the matrix spike sample analysis. Low antimony and cyanide matrix spike recoveries of 67.6%, and 72.1%, respectively, were reported for MW-6. Low antimony and high manganese matrix spike recoveries of 67.4%, and 157.1%, respectively, were reported for PSB-5. Therefore, all postive antimony, cyanide, and manganese sample results were qualified as estimated (J) and all non-detect antimony, and cyanide sample results were qualified as estimated (UJ). A matrix spike sample was analyzed for lead using ICP with the results found to be

within the control limits. This matrix spike sample is contained in SDG A1368. All other matrix spike recoveries were within the control limits.

Furnace Atomic Absorption Quality Control

The majority of samples were analyzed for arsenic, lead, selenium, and thallium using GFAA. The arsenic post-digestion spike recovery for sample PSB-3 was found to be below the control limits with a recovery of 51.5%. Therefore, the arsenic detected in sample PSB-3 was qualified as estimated (J). Several sample results were determined by the method of standard additions (MSA). Lead was measured in sample MW-3I by MSA twice with both correlation coefficients found to be < 0.995. Therefore, the lead detected in sample MW-3I was qualified as estimated (J). All other GFAA quality control criteria requirements were met.

Inductively Coupled Plasma Serial Dilution

Sample MW-6 was used for the ICP serial dilution analysis. All ICP serial dilution results were within the control limits.

Sample Result Verification

No discrepancies were found between the reported results and the QC data package.

Field Duplicate

Soil field duplicates were not required.

Overall Assessment of Data for the Case

The quality of the inorganic data presented in this QC data package is acceptable with the appropriate qualifications described in this memorandum.

SDG A1368 RESULTS

Seven water samples, seven soil samples, and one water field duplicate are contained in SDG A1368. These samples were collected on December 7, 1994 and received by the laboratory within 48 hours of collection. The validation results for SDG A1368 are discussed below.

Holding Times

All samples were analyzed within holding time requirements.

Calibration

The correlation coefficient for the lead initial calibration conducted on December 16, 1994 using GFAA was found to be < 0.995. Therefore, the positive lead results for associated samples PSW-7, and PSW-12, were qualified as estimated (J). The sodium percent recovery was above control limits (116.7%) for the fourth continuing calibration verfication standard (CCV) analyzed. Because no samples were analyzed after this CCV, qualification of the data was not necessary. All other initial and all continuing calibration requirements were met.

Blanks

The following analytes were detected in the ICBs analyzed:

Analysis Date	Analyte	Concentration (ug/L)
December 14, 1994	Arsenic	-1.8 B
December 21, 1994	Copper	-5.1 B
December 21, 1994	Vanadium	-8.2 B
December 21, 1994	Zinc	-4.9 B
December 19, 1994	Arsenic	-1.0 B
December 19, 1994	Thallium	1.6 B

Because the negative concentration of arsenic, copper, vanadium and zinc was not recorded below the negative CRDL for these analytes, in this data reviewer's professional judgement that qualification of the associated arsenic, copper, vanadium, and zinc sample results was not necessary. Thallium was not detected in any of the samples associated with the positive thallium ICB result.

The following analytes were detected in the CCBs analyzed:

Analysis Date	CCB#	<u>Analyte</u>	Concentration (ug/L)
December 14, 1994 December 21, 1994	1 1 1 1 1 2 2 2 2 2 2 2 2 3 3 3 3 4 4	Arsenic Copper Iron Magnesium Zinc Arsenic Chromium Copper Potassium Selenium Zinc Arsenic Copper Nickel Zinc Arsenic Copper	-1.1 B -4.2 B 35.9 B 25.4 B -5.8 B -1.3 B -5.0 B -3.6 B -750.4 B -1.1 B -6.0 B -1.5 B -6.0 B -8.4 B -6.3 B -1.5 B -5.4 B
		Сорра	-5.4 B

December 21, 1994	4	To Loron 1 1	
December 21, 1994	4	Lead (ICP analysis)	17.4 B
December 21, 1994	4	Nickel	-9.1 B
December 21, 1994	4	Sodium	208.3 B
December 21, 1994	7	Zinc	-6.0 B
December 21, 1994	5	Copper	-4.8 B
December 21, 1994	5	Iron	66.7 B
December 21, 1994	5	Magnesium Silver	53.3 B
December 21, 1994	5	Zinc	3.1 B
December 19, 1994	1	Thallium	-6.6 B
December 20, 1994	2	Thallium	1.2 B 1.4 B
			1.4 B

Because the negative concentrations for the analytes listed above were not recorded below the corresponding negative CRDL for these analytes, in this data reviewer's professional judgement that qualification of the sample results based on these CCB results was not necessary. The following analytes were qualified as not detected based on the corresponding CCB results:

Sample ID	<u>Analyte</u>	Concentration (ug/L)
PSW-5	Iron	93.1 U
PSW-7	Iron	99.9 U
PSW-8	Iron	97.5 U
PSW-9	Iron	117.0 U

The following analytes were detected in PBs analyzed:

<u>Analyte</u>	Concentration (ug/L)
Aluminum Iron Magnesium	24.7 B 20.6 B 25.5 B

Analyte	Concentration (ug/L)
Calcium Iron Magnesium Silver Sodium Zinc	18.9 B 6.2 B 7.5 B 0.9 B 11.7 B 1.6 B

Silver	0.9 B
Sodium	11.7 B
Zinc	1.6 B

The following sample results were qualified as not detected based on the corresponding PB results:

Sample ID	Analyte	Concentration (ug/L)	Units
PSW-6	Aluminum	103.0 U	ug/L
PSS-7	Silver	1.5 U	mg/kg
PSS-8	Silver	4.6 U	mg/kg
PSS-9	Silver	3.2 U	mg/kg

The other analytes detected in the PB were not detected in the associated samples or were also detected in the associated samples at concentrations greater than five times the PB concentrations. Therefore, further qualification of the sample results based on the PB results was not necessary. No analytes were detected in any of the other blanks. Field blanks were not required for this sampling round.

Inductively Coupled Plasma Interference Check Sample

The percent recoveries for all inductively coupled plasma interference check sample (ICS) analyses were within the control limits of $\pm 20\%$ of the true value.

Laboratory Control Sample

All laboratory control sample (LCS) results were within the control limits.

Duplicate Sample Analysis

Two soil samples and one water sample were designated for the duplicate analyses. The water duplicate results, and the soil duplicate result for lead analyzed by ICP are contained in this SDG. The other soil duplicate results are contained in SDG Z1368. The chromium relative percent difference (RPD) value was above the control limit for the soil sample and duplicate collected at MW-6. The calcium, magnesium, and manganese RPD values were above the control limits for the soil sample and duplicate collected at PSB-5. Therefore, all chromium, calcium, magnesium, and manganese soil sample results were qualified as estimated (J) if detected and estimated (UJ) if not detected. All water duplicate sample results, and all other soil duplicate sample results were also within the control limits.

Matrix Spike Sample Analysis

Two soil samples and one water sample were designated for the matrix spike sample analysis. The water matrix spike results, and the soil matrix spike result for lead analyzed by ICP are contained in this SDG. The other soil matrix spike results are contained in SDG Z1368. Low antimony and cyanide soil matrix spike recoveries of 67.6%, and 72.1%, respectively, were reported for MW-6. Low antimony and high manganese soil matrix spike recoveries of 67.4%, and 157.1%, respectively, were reported for PSB-5. Therefore, all postive antimony, cyanide, and manganese soil sample results were qualified as estimated (J) and all non-detect antimony, and cyanide soil sample results were qualified as estimated (UJ). All water matrix spike results, and all other soil matrix spike recoveries were within the control limits.

Furnace Atomic Absorption Quality Control

The majority of samples were analyzed for arsenic, lead, selenium, and thallium using GFAA. All GFAA quality control criteria requirements were met.

Inductively Coupled Plasma Serial Dilution

Soil sample PSS-5 and water sample PSW-9 were used for the ICP serial dilution analyses. For soil sample PSS-5, the intial and serial dilution copper results did not agree within 10%, therefore, copper detected in the soil samples were qualified as estimated (J) and all copper non-detects for the soil samples were qualified as estimated (UJ). All other ICP serial dilution results were within the control limits.

Sample Result Verification

No discrepancies were found between the reported results and the QC data package.

Field Duplicate

A field duplicate from sampling location PSW-8 was collected and labeled Dup. Soil field duplicates were not required. The following analytes were detected in the sample and duplicate collected from sampling location PSW-8 along with the corresponding RPD value:

Analyte	Sample PSW-8 Concentration (ug/L)	Duplicate Concentration (ug/L)	RPD
Aluminum Barium Calcium Copper Iron Lead Magnesium Manganese Nickel Potassium Sodium	468	290	47
	58.2 B	45.8 B	24
	43200	62200	36
	10.2 B	4.8 B	72
	97.5 B	143	38
	19.8	30.8	43
	8010	11200	33
	15.7	18.1	14
	23.6 B	8.0 U	200
	1840 B	2600 B	34
Zinc	43800	61400	33
	48.2	122	87

Based on the field duplicate results, it is this data reviewer's professional opinion that because the zinc RPD value is high, all positive zinc results for the water samples analyzed should be qualified as estimated (J). It is also this data reviewer's opinion that further qualification of the data was not necessary based on the field duplicate results.

Overall Assessment of Data for the Case

The quality of the inorganic data presented in this QC data package is acceptable with the appropriate qualifications described in this memorandum.

g:\chemical\data-val\albany\schina\1994\z1368ino.mem

Table 1. Sample Identification, Collection Dates, and Laboratory Received Dates for Samples Analyzed Under IEA Project Number 3094-Z1368.

ID	Laboratory ID	Date Collected	Date Received
FB 112894	1368001	11/28/94	11/30/94
MW-6	1368002	11/28/94	11/30/94
MW-3I	1368003	11/30/94	12/01/94
MW-4I	1368004	11/30/94	12/01/94
FB 113904	1368005	11/30/94	12/01/94
TB 113094	1368006		12/01/94
PSS-11	1368007	12/01/94	12/02/94
PBM-1	1368008	12/01/94	12/02/94
PBM-2	1368009	12/01/94	12/02/94
MW-7	1368010	12/01/94	12/02/94
FB 120194	1368011	12/01/94	12/02/94
TB 120194	1368012	der to	12/02/94
PSB-51368013	12/02/94	12/05/94	
PSB-41368014	12/02/94	12/05/94	
FB 120294	1368015	12/02/94	12/05/94
TB 120294	1368016		12/05/94
PSB-11368017	12/06/94	12/07/94	
PSB-21368018	12/06/94	12/07/94	
PSB-31368019	12/06/94	12/07/94	
TB 120694	1368020		12/07/94

Table 2. Sample Identification, Collection Dates, and Laboratory Received Dates for Samples Analyzed Under IEA Project Number 3094-A1368.

Geraghty and Miller, Inc. ID	Laboratory ID	Date Collected	Date Received
FB 120694	1368021	12/06/94	12/07/94
PSW-5	1368022	12/07/94	12/08/94
PSS-51368023	12/07/94	12/08/94	
PSW-7	1368024	12/07/94	12/08/94
PSS-71368025	12/07/94	12/08/94	
PSW-6	1368026	12/07/94	12/08/94
PSS-61368027	12/07/94	12/08/94	100,7,
PSS-81368028	12/07/94	12/08/94	
PSW-8	1368029	12/07/94	12/08/94
PSS-91368030	12/07/94	12/08/94	12.00.71
PSW-9	1368031	12/07/94	12/08/94
PSS-10	1368032	12/07/94	12/08/94
PSW-10	1368033	12/07/94	12/08/94
PSS-12	1368034	12/07/94	12/08/94
PSW-12	1368035	12/07/94	12/08/94
FB 120794	1368036	12/07/94	12/08/94
TB 120794	1368037		12/08/94
DUP	1368038	12/07/94	12/08/94

MEMORANDUM

TO:

William Gray

FROM:

Lauren Sjogren

DATE:

March 31, 1995

SUBJECT: Inorganic Data Validation of Groundwater Samples Collected for the Syracuse China

Site located in Syracuse, New York (Project No. AY0146.004).

Groundwater samples were collected for the Syracuse China site located in Syracuse, New York. The samples were sent to Industrial and Environmental Analysts, Inc. (IEA) in Monroe, Connecticut for the analysis of target analyte list (TAL) metals and cyanide following the United States Environmental Protection Agency (USEPA) Contract Laboratory Program (CLP) Statement of Work (SOW) for Inorganics as specified in the New York State Department of Environmental Conservation (NYSDEC) Analytical Services Protocol (ASP) dated September 1989, revised December 1991.

Validation of the laboratory data was performed following the quality assurance/quality control (QA/QC) criteria set forth in the "USEPA Laboratory Data Validation Functional Guidelines for Evaluating Inorganics Analyses" dated July 1988, and the NYSDEC ASP. Eight water samples, one field duplicate, one trip blank and one field blank were sent to IEA for analysis. Sample identification, collection dates, and laboratory received dates are listed in Table 1. The quality of the data was acceptable with the appropriate qualifications described in this memorandum.

INORGANIC DATA VALIDATION SUMMARY

One data package (sample delivery group [SDG]) was provided by the laboratory for metal sample results. The validation results for this SDG is discussed below.

SDG Z0018 RESULTS

Samples were collected from eight monitoring wells and sent to the laboratory for the analysis of total and dissolved metals (filtering). Samples are contained in SDG Z0018. These samples were collected on January 5, 1995 and received by the laboratory within 48 hours of collection. The validation results for SDG Z0018 are discussed below.

Holding Times

All samples were analyzed within holding time requirements.

Calibration

The correlation coefficient for the thallium initial calibration conducted on January 26, 1995 using graphite furnace atomic absorption spectroscopy (GFAA) was found to be <0.995. Therefore, the positive thallium results for associated samples MW-6 (total) and MW-3 (total) were qualified as estimated (J), and the non-detect thallium results for associated samples MW-1 (total), MW-5 (total), MW-2 (total), DUP 1 (total), MW-7 (total), MW-4 (total), MW-4I (total), and FB010595 (total) were qualified as estimated (UJ). All other initial and all continuing calibration requirements were met.

Blanks

The following analytes were detected in the initial calibration blanks (ICBs) analyzed:

Analysis Date	Analyte	Concentration (ug/L)
January 26, 1995	Arsenic	-1.0 B
January 26, 1995	Copper	-4.6 B
January 26, 1995	Arsenic	-1.3 B
January 27, 1995	Selenium	1.0 B

The "B" qualifier indicates that the concentration detected is between the contract required detected limit (CRDL) and the instrument detection limit (IDL). Because the negative concentration of arsenic was not recorded below two times the negative IDL; in this data reviewer's professional judgement, qualification of the associated arsenic sample results was not necessary. In this data reviewer's professional judgement, because regular concentrations of copper were recorded below two times regular copper IDL, all positive sample results less than the CRDL were qualified as estimated (J).

The following selenium sample results were qualified as not detected (U) based on the associated ICB result.

Sample ID	Concentration (ug/L)
MW-2 (total)	1.8 U
MW-3 (total)	1.1 U
DUP 1 (total)	1.0 U
MW-4 (total)	1.5 U
MW-4I (total)	2.7 U

The following analytes were detected in the continuing calibration blanks (CCBs) analyzed:

Analysis Date	CCB#	Analyte	Concentration (ug/L)
January 26, 1995	1	Copper	-4.9 B
January 26, 1995	1	Iron	73.2 B
January 26, 1995	1	Magnesium	29.1 B
January 26, 1995	2	Copper	-4.6 B
January 26, 1995	2	Zinc	-3.2 B
January 26, 1995	3	Arsenic	-1.0 B
January 26, 1995	3	Copper	-4.3 B
January 26, 1995	3	Iron	76.5 B
January 26, 1995	3	Magnesium	47.1 B
January 26, 1995	4	Arsenic	-1.0 B
January 26, 1995	4	Calcium	16.8 B
January 26, 1995	4	Copper	-4.3 B
January 26, 1995	4	Iron	28.9 B
January 26, 1995	5	Aluminum	18.7 B
January 26, 1995	5	Calcium	25.6 B
January 26, 1995	5	Copper	-5.2 B
January 26, 1995	5	Iron	88.7 B
January 26, 1995	5	Magnesium	59.4 B
January 26, 1995	1	Arsenic	-1.5 B
January 26, 1995	2	Arsenic	-1.0 B
January 26, 1995	3	Arsenic	-1.3 B
January 26, 1995	4	Arsenic	-1.3 B
January 27, 1995	3	Thallium	1.1 B

The following sample result was qualified as not detected (U) based on the CCB results.

Sample ID	Analyte	Concentration (ug/L)
MW-2 (dissolved)	Iron	18.2 U

Because the negative concentrations for arsenic and zinc listed above were not recorded below two times the corresponding negative IDL for these analytes, in this data reviewer's professional judgement that qualification of the sample results based on these CCB results was not necessary. Thallium was not detected in any of the samples associated with the positive thallium CCB result. Aluminum, calcium, and magnesium were detected in all the associated samples at

concentrations that are above five times the CCB concentrations for these three analytes, therefore, qualification of the aluminum, calcium, and/or magnesium sample results based on the associated CCB results was not necessary. Copper sample results have already been qualified based on the ICB results.

The following analytes were detected in preparation blank (PB) analyzed:

Analyte	Concentration (ug/L)
Iron	37.23 B
Magnesium	24.6 B
Lead (GFAA)	2.8 B

The following sample results were qualified as not detected based on the associated PB results:

Sample ID	<u>Analyte</u>	Concentration (ug/L)
MW-2 (total) MW-5 (total) MW-4 (dissolved) MW-6 (dissolved) MW-5 (dissolved) MW-3 (dissolved) DUP 1 (dissolved) MW-7 (dissolved)	Lead Lead Iron Lead Lead Lead Lead Lead Lead Lead	11.0 U 6.7 U 32.4 U 7.9 U 3.0 U 2.2 U 3.0 U 3.7 U
MW-4 (dissolved)	Lead	2.7 U

The magnesium detected in the PB was detected in the samples at concentrations greater than five times the PB concentration. Therefore, further qualification of associated the magnesium sample results, based on the PB results, was not necessary. No analytes were detected in any of the other blanks.

One field blank was collected with the results listed below:

Field Blank FB010595 (total)

Analyte	Concentration (ug/L)
Aluminum	49.2 B
Calcium	709 B
Iron	114
Magnesium	140 B
Manganese	14 B
Sodium	153 B
Zinc	17.4 B

Field Blank FB010595 (dissolved)

<u>Analyte</u>	Concentration (ug/L)
Aluminum	57.5 B
Calcium	856 B
Iron	128
Magnesium	163 B
Manganese	7.0 B
Sodium	51.9 B
Zinc	9.8 B

The following sample results were qualified as not detected (U) based on the associated field blank results:

Sample ID	Analyte	Concentration (ug/L)
MW-1 (total)	Zinc	69.6 U
MW-5 (total)	Zinc	51.2 U
MW-2 (total)	Zinc	66.6 U
MW-7 (total)	Zinc	52.4 U
MW-1 (dissolved)	Manganese	3.4 U
MW-1 (dissolved)	Zinc	47.6 U
MW-5 (dissolved)	Manganese	21.3 U
MW-2 (dissolved)	Aluminum	31.6 U
MW-2 (dissolved)	Zinc	29.7 U
MW-3 (dissolved)	Aluminum	17.4 U
MW-3 (dissolved)	Zinc	38.9 U
DUP 1 (dissolved)	Aluminum	16.9 U
DUP 1 (dissolved)	Zinc	40.9 U

MW-7 (dissolved)
MW-4 (dissolved)

Zinc Aluminum

36.6 U 34.5 U

Inductively Coupled Plasma Interference Check Sample

The percent recoveries for all inductively coupled plasma interference check sample (ICS) analyses were within the control limits of $\pm 20\%$ of the true value.

Laboratory Control Sample

All laboratory control sample (LCS) results were within the control limits.

Duplicate Sample Analysis

Sample MW-1 (total) and MW-1 (dissolved) were designated for the duplicate analysis. All duplicate sample results were within the control limits.

Matrix Spike Sample Analysis

Sample MW-1 (total) and MW-1 (dissolved) were designated for the matrix spike sample analysis. All matrix spike recoveries were within the control limits.

Furnace Atomic Absorption Quality Control

The majority of samples were analyzed for arsenic, lead, selenium, and thallium using GFAA. The following post-digestion spike recoveries were found to be below the control limits:

Sample ID	<u>Analyte</u>	Spike Recovery	Qualifier
MW-2 (total)	Arsenic	79.0%	J
MW-41 (dissolved)	Selenium	80.0%	J
MW-2 (total)	Selenium	76.0%	UJ
MW-3 (total)	Selenium	68.0%	UJ
DUP 1 (total)	Selenium	68.0%	UJ
MW-4 (total)	Selenium	66.0%	UJ
Sample ID	Analyte	Spike Recovery	Qualifier
MW-4I (total)	Selenium	68.0%	UJ
MW-6 (total)	Thallium	79.5%	J
MW-2 (total)	Thallium	53.5%	UJ
MW-3 (total)	Thallium	69.0%	J
DUP 1 (total)	Thallium	78.0%	UJ
MW-4 (total)	Thallium	79.0%	UJ
MW-4I (total)	Thallium	79.0%	UJ
MW-5 (dissolved)	Thallium	77.5%	UJ
MW-2 (dissolved)	Thallium	74.0%	UJ
MW-3 (dissolved)	Thallium	82.5%	UJ
DUP 1 (dissolved)	Thallium	81.0%	UJ
MW-7 (dissolved)	Thallium	80.5%	UJ
MW-4 (dissolved)	Thallium	82.0%	UJ
MW-4I (dissolved)	Thallium	64.5%	UJ
MW-3 (dissolved)	Lead	115.5%	None
MW-4 (dissolved)	Lead	115.5%	None
FB010595 (dissolved)	Lead	117.0%	None

Several sample results were determined by the method of standard additions (MSA). Lead was measured in samples MW-4 (total) and MW-4I (total) by MSA twice with all the correlation coefficients found to be < 0.995. Therefore, the lead detected in samples MW-4 (total) and MW-4I (total) were qualified as estimated (J). All other GFAA quality control criteria requirements were met.

Inductively Coupled Plasma Serial Dilution

Sample MW-1 (total) and MW-1 (dissolved) was used for the inductively coupled plasma (ICP) serial dilution analysis. The aluminum and iron percent differences between the initial and serial dilution results for MW-1 (total) were greater than the criteria. Therefore, aluminum and iron results for all the total samples were qualified as estimated (J and UJ). All other ICP serial dilution results were within the control limits.

Sample Result Verification

No discrepancies were found between the reported results and the QC data package.

Field Duplicate

DUP 1 is a field duplicate of MW-3.

The results of DUP 1, MW-3, and the corresonding relative percent difference (RPD) values are listed below:

Analyte	MW-3 (total) Concentration (ug/L)	DUP 1 (total) Concentration (ug/L)	RPD
Aluminum	41,500	51,400	21
Antimony	38.0 U	48.2 B	200
Arsenic	49.3	61.9	23
Barium330	389	16	23
Calcium	65,800	630,000	4.3
Chromium	49.5	58.5	17
Cobalt38.6	42.9	11	
Copper85.5	96.8	12	
Iron	70,200	81,400	15
Lead	176	254	36
Magnesium	206,000	199,000	3.5
Manganese	3,460	3,390	2.0

Nickel75.5 Potassium Sellinum Sodium Thallium Vanadium Zinc	82.7 7,980 1.1 32,600 1.1 B 74.2 198	9.1 8,900 1.0 32,800 1.0 U 75.2 218	11 9.5 0.6 200 1.3 9.6
Analyte	MW-3 (dissolved) Concentration (ug/L)	DUP 1 (dissolved) Concentration (ug/L)	RPD
Aluminum	17.44 B	16.9 B	2.9
Arsenic	1.6 B	1.9 B	17
Barium29.6 B Calcium Copper2.9 B	31.0 B 172,000 2.0 U	1.3 178,000 200	3.4
Iron Lead	1,120	1,160	3.5
Magnesium	2.2	3.0	31
Manganese	44,300 549	45.700	3.1
Sodium	29,300	567	3.2
Zinc	38.9	30,400 40.9	3.7 5.0

The field duplicate results are considered acceptable.

Overall Assessment of Data for the Case

A comparison of the total and dissolved results for the samples was performed. All sample results with a percent difference (%D) over 10% were qualified as estimated (J) and results with a %D greater than 50% were qualified as unusable (R). The results are listed below.

Sample ID	Analyte	Dissolved Concentration (ug/L)	Total Concentration (ug/L)	%D	Qualifier
MW-4I MW-4I MW-4I MW-4I MW-4I MW-4I	Barium Chromium Copper Iron Lead Manganese	576 114 197 106,000 145	470 95.7 155 85,200 71.0	23 19 27 24 104	J J J R
	manganese	4,380	3,920	12	Ţ

MW-4I MW-4I MW-4I MW-5 FB010595	Nickel Vanadium Zinc Zinc Iron	132 94.2 377 80.2 128	108 74.2 294 51.2 114	22 27 28 57 12	J J J R
---	--	-----------------------------------	-----------------------------------	----------------------------	------------------

The quality of the inorganic data presented in this QC data package is acceptable with the appropriate qualifications described in the memorandum.

g:\chemical\data-val\albany\schina\1994\z0018ino.mem

Table 1. Sample Identification, Collection Dates, and Laboratory Received Dates for Samples Analyzed Under IEA Project Number 3095-Z0018.

eraghty and Miller, Inc. ID	Laboratory ID	Date Collected	Date Received
MW-6	0018001	01/05/95	01/07/07
MW-1	0018002	01/05/95	01/06/95 01/06/95
MW-5	0018003	01/05/95	01/06/95
MW-2	0018004	01/05/95	01/06/95
MW-3	0018005	01/05/95	01/06/95
DUP 1	0018006	01/05/95	01/06/95
MW-7	0018007	01/05/95	01/06/95
MW-4	0018008	01/05/95	01/06/95
MW-4I	0018009	01/05/95	01/06/95
FB 010595	0018010	01/05/95	01/06/95
TB 010595	0018011	01/05/95	01/06/95

MEMORANDUM

TO:

Bill Gray

FROM:

Lisa Westbay and Lauren Sjogren

DATE:

April 3, 1995

SUBJECT:

Data Validation of Samples Collected at the Syracuse China Site

(Project No. AY0146.004)

Samples were collected at the Syracuse China site in Syracuse, New York and were sent to IEA Laboratories, Inc. in Monroe, Connecticut for analysis. Ten surface water samples were collected on December 7, 1994 and were analyzed for volatile organic compounds (VOCs); 14 sediment samples were collected on December 1, 1994 and December 7, 1994 and were analyzed for VOCs; 18 soil boring samples were collected between November 28, 1994 and December 6, 1994 and were analyzed for VOCs; one soil sample was collected on December 6, 1994 and was analyzed for semivolatile organic compounds (SVOCs); two soil boring samples were collected on December 1, 1994 and were analyzed for polychlorinated biphenyls (PCBs); and 11 groundwater samples were collected on January 5, 1995 and were analyzed for VOCs, metals, and cyanide. The samples were analyzed by IEA Laboratory using the New York State Department of Environmental Conservation (NYSDEC) Contract Laboratory Program (CLP) Statement of Work (SOW), January 1991. Validation of the VOC and SVOC data was performed following the "USEPA Contract Laboratory Program, National Functional Guidelines for Organic Data Review", dated June 1991 (Draft), and the "United States Environmental Protection Agency (USEPA) Region II Standard Operating Procedure (SOP)", dated January 1992, for validation of the PCB data.

Three data packages (sample delivery groups [SDGs]) were provided by the laboratory, and the validation results of each are discussed separately below. The quality of the data was acceptable with the appropriate qualifications described in this memorandum.

ORGANIC DATA VALIDATION SUMMARY

SDG Z1368 RESULTS

Holding Times

Volatiles: All samples were analyzed within seven days from time of sample collection.

Semivolatiles: All samples were extracted within the holding time of seven days from sample collection to extraction and 40 days from sample extraction to analysis.

PCBs: All samples were extracted within holding time of seven days of the date of collection and extracted within 40 days of the date of extraction.

GC/MS Tunes

Volatiles: Each set of tuning data meets the required ion abundance criteria. All samples were analyzed within the 12-hour tune time limit.

Semivolatiles: Each set of tuning data meets the required ion abundance criteria specified. All samples were analyzed within the 12-hour tune time limit.

Pesticides Instrument Performance

PCBs: To evaluate the performance of the gas chromatograph (GC) instruments used to analyzed the samples, the following were reviewed:

- retention time windows
- initial calibration
- linearity criteria
- resolution between adjacent peaks

- 4,4'-DDT/Endrin degradation
- RPD values for all performance evaluation mixture (PEM) analytes

All of the criteria listed above were found to be acceptable, with one exception. The %RSD for 4,4'-DDT, analyzed using column DB-1701, was 30%; and therefore, exceeded the linearity criteria. However, because pesticides were not analyzed for in these samples, qualification of the data was not necessary.

Calibration

Initial Calibration

Volatiles: Three initial calibrations were conducted. The initial calibration conducted on instrument HP5995G on November 14, 1994, had all relative response factors (RRF) ≥ 0.05 , and all percent relative standard deviations (%RSD) $\leq 30\%$. The initial calibration conducted on instrument HP5995B on November 5, 1994, had all relative response factors (RRF) ≥ 0.05 , and all percent relative standard deviations (%RSD) $\leq 30\%$, except for acetone which was 32.4%. The initial calibration conducted on instrument HP5972D on November 9, 1994, had all RRFs ≥ 0.05 , and all %RSDs $\leq 30\%$, except for acetone which was 62.5%. The following sample results were qualified as estimated (J) due to the associated initial calibration results:

Sample ID	Compound	Concentration (ug/kg)
MW-6 MW-4I PSS-11 PBM-1 MW-7 PSB-5 PSB-4	Acetone Acetone Acetone Acetone Acetone Acetone Acetone Acetone	39 J 38 J 36 J 33 J 150 J 22 J 20 J

Acetone was detected in samples PSB-1, PSB-2, and PSB-3 but were not qualified as estimated (J) because they will be further qualified as non-detected (U) based on the blank results discussed in Section IV. on page 15.

Semivolatiles: The initial calibration was conducted December 1, 1994 with all RRFs ≥ 0.05 and all %RSDs $\leq 30\%$, with one exception. The %RSD for hexachlorocyclopentadiene was 50.5. Hexachlorocyclopentadiene was not detected in the associated sample, and therefore, no action was taken.

PCBs: All initial calibration requirements were met.

Continuing Calibration

Volatiles: Seven continuing calibration runs were conducted with all RRFs \geq 0.05 and %D \leq 25%, with the exceptions noted below.

Instrument: HP5995G	Calibration Date: 12/3/94	Time: 10:28
Compound	<u>%D</u>	
Chloromethane	-34.5	
Vinyl chloride	-28.5	
Acetone	34.0	
2-Butanone	43.0	
4-Methyl-2-pentanon		
2-Hexanone	41.6	

Instrument:	HP5995B	Calibration Date: 12/5/94	Time: 10:05
-------------	---------	---------------------------	-------------

Compound	<u>%D</u>
Acetone	47.3
2-Butanone	39.3
4-Methyl-2-pentanone	34.8
2-Hexanone	36.4

Instrument: HP5995B Calibration Date: 12/6/94 Time: 9:46

Compound	<u>%D</u>
2-Butanone Carbon tetrachloride	40.2 -31.7
4-Methyl-2-pentanone	32.8
2-Hexanone	36.5

Instrument: HP5995B	Calibration Date: 12/9/94	Time: 8:54
Compound	<u>%D</u>	
Chloromethane	-37.3	
Acetone	28.4	
2-Butanone	39.6	
4-Methyl-2-pentano	ne 32.6	
2-Hexanone	30.3	
1,1,2,2-Tetrachloro	ethane 28.8	
Instrument: HP5972D	Calibration Date: 12/6/94	Time: 8:58
Compound	<u>%D</u>	
Acetone	26.0	
Instrument: HP5972D	Calibration Date: 12/7/94	Time: 9:08
Compound	<u>%D</u>	
Chloromethane	26.6	
Acetone	52.6	
4-Methyl-2-pentanor	ne 55.3	
Instrument: HP5972D	Calibration Date: 12/9/94	Time: 8:04
Compound	<u>%D</u>	
Acetone	25.5	

Based on continuing calibration results, the following compounds were qualified as estimated (J) if detected and estimated (UJ) if nondetected:

Sample ID	Compound	Concentration
FB112894	Chloromethane Vinyl chloride	10 UJ
	Acetone	10 UJ 10 UJ
	2-Butanone	10 UJ
	4-Methyl-2-pentanone	10 UJ
	2-Hexanone	10 UJ

Sample ID	Compound	Concentration
FB113094	Chloromethane Vinyl chloride	10 UJ 10 UJ
	Acetone	10 UJ
	2-Butanone	10 UJ
/8	4-Methyl-2-pentanone	
	2-Hexanone	10 UJ
MW-6	2-Butanone	11 UJ
	4-Methyl-2-pentanone	11 UJ
	2-Hexanone	11 UJ
MW-3I	Acetone	11 UJ
	2-Butanone	11 UJ
	4-Methyl-2-pentanone	11 UJ
	2-Hexanone	11 UJ
MW-4I	2-Butanone	11 UJ
	4-Methyl-2-pentanone	11 UJ
	2-Hexanone	11 UJ
PSS-11	2-Butanone	14 UJ
	4-Methyl-2-pentanone	14 UJ
	2-Hexanone	14 UJ
PBM-1	2-Butanone	16 UJ
	4-Methyl-2-pentanone	16 UJ
	2-Hexanone	16 UJ
PBM-2	Acetone	13 UJ
	2-Butanone	13 UJ
	4-Methyl-2-pentanone	13 UJ
	2-Hexanone	13 UJ
MW-7	4-Methyl-2-pentanone	12 UJ
	2-Hexanone	12 UJ
PSB-5	2-Butanone	13 UJ
	4-Methyl-2-pentanone	13 UJ
	2-Hexanone	13 UJ
PSB-4	2-Butanone	12 UJ
	4-Methyl-2-pentanone	12 UJ
	2-Hexanone	12 UJ

Sample ID	Compound	Concentration
PSB-1	Chloromethane	12 UJ
	Acetone	36 UJ
	4-Methyl-2-pentanone	12 UJ
	2-Hexanone	12 UJ
	1,1,2,2-Tetrachloroetha	
PSB-2	Chloromethane	11 UJ
	Acetone	24 UJ
	2-Butanone	11 UJ
	4-Methyl-2-pentanone	11 UJ
	2-Hexanone	11 UJ
	1,1,2,2-Tetrachloroetha	ne 11 UJ
PSB-3	Chloromethane	14 UJ
	Acetone	31 UJ
	2-Butanone	14 UJ
	4-Methyl-2-pentanone	14 UJ
	2-Hexanone	14 UJ
	1,1,2,2-Tetrachloroetha	ne 14 UJ
TB113094	Acetone	10 UJ
FB120194	Acetone	10 UJ
TB120194	Acetone	10 UJ
FB120294	Acetone	10 UJ
TB120294	Chloromethane	10 UJ
	Acetone	10 UJ
	4-Methyl-2-pentanone	10 UJ
TB120694	Acetone	10 UJ

Due to the previous qualification of acetone results based on initial calibration results (samples MW-6, MW-4I, PSS-11, PBM-1, MW-7, PSB-5, PSB-4) and the previous qualification of 2-butanone results in samples MW-7 and PSB-1 as estimated (J), no further qualification to these data were made.

Semivolatiles: One continuing calibration run was conducted on December 15, 1994, with all RRFs ≥ 0.05 and all %RSDs $\leq 25\%$ with the following exceptions:

Compound	<u>%D</u>
Hexachlorocyclopentadiene	30.1
3-Nitroaniline	26.7
4-Nitroaniline	32.2
Carbazole	43.4

None of the above compounds were detected in the associated sample; therefore, these compound results were qualified as estimated (UJ) for sample PSB-3.

Blanks

Volatiles: Seven method blanks were analyzed; no compounds were detected in them except for the following:

Method Blank: VBLKGG Date Analyzed: 12/3/94

Compound	Concentration in Micrograms per Liter (ug/L)
Methylene chlorid	e 0.8 J
Acetone	4 J
Chloroform	1 J

Method Blank: VBLKDX Date Analyzed: 12/6/94

Compound	Concentration (ug/L)	
Acetone	20	

Method Blank: VBLKB4 Date Analyzed: 12/6/94

Compound	Concentration in Micrograms per Kilogram (ug/kg)
Acetone	5.1

Method Blank: VBLKB7 Date Analyzed: 12/9/94

Compound Concentration (ug/kg)

Acetone 25

The following sample results were qualified as non-detected (U) due to the associated method blank results:

Sample ID	Compound	Concentration (ug/kg)
PSB-1	Acetone	36 U
PSB-2	Acetone	24 U
PSB-3	Acetone	31 U

Four field blanks and four trip blanks were analyzed; no compounds were detected in these blanks. However, FB120694, which was reported in SDG A1368, was associated with three samples contained in this SDG. Toluene was detected in FB120694 at an estimated concentration of 2 ug/L, and therefore, the following sample results were qualified as non-detected (U) as a result:

Sample ID	Compound	Concentration (ug/kg)
PSB-1	Toluene	12 U
PSB-2	Toluene	11 U
PSB-3	Toluene	14 U

Semivolatiles: One method blank was analyzed with the following target compounds detected:

Compound Concentration (ug/kg)

Di-n-butylphthalate 21 J

bis(2-Ethylhexyl)phthalate 11 J

The following sample results were qualified as non detected due to the method blank results:

Sample ID	Compound	Concentration (ug/kg)
PSB-3	Di-n-butylphthalate	470 U
PSB-3	bis(2-Ethylhexyl)phthalate	470 U

No field blanks were associated with this sample.

The following tentatively identified compounds (TICs) were detected in the method blank:

Method Blank	Compound	Retention Time (Minutes)	Concentration (ug/kg)
SBLKFI	4-Methyl-3-penten-2-one	5.38	540 JN
SBLKFI	Unknown	5.97	400 J
SBLKFI	Unknown	6.38	1,400 J
SBLKFI	Aldol condensation prod		57,000 JA
SBLKFI	Unknown	8.44	590 J
SBLKFI	Unknown alkane	9.27	110 J
SBLKFI	Unknown alkane	10.55	400 J
SBLKFI	Unknown alkane	10.69	180 J
SBLKFI	Unknown alkane	10.78	470 J
SBLKFI	Unknown alkane	11.16	500 J
SBLKFI	Unknown alkane	11.20	150 J
SBLKFI	Unknown alkane	11.31	360 J
SBLKFI	Unknown	11.41	99 J
SBLKFI	Unknown alkane	11.55	370 J
SBLKFI	Unknown alkane	11.76	77 J
SBLKFI	Unknown alkane	11.95	100 J
SBLKFI	Unknown alkane	17.97	100 J
SBLKFI	Unknown alkane	20.65	91 J
SBLKFI	Unknown alkane	23.04	72 J
SBLKFI	Unknown	24.70	72 J 98 J
SBLKFI	Unknown alkane	27.59	120 J

The following TICs were found in sample PSB-3 and not reported (R) because they were also detected in the associated method blank:

Sample ID	Compound Ro	etention Time (Minutes)
PSB-3	4-Methyl-3-penten-2-one	5.40
PSB-3	Unknown	5.98
PSB-3	Unknown	6.33
PSB-3	Aldol condensation prod.	
PSB-3	Unknown	8.43
PSB-3	Unknown alkane	9.28
PSB-3	Unknown alkane	10.55
PSB-3	Unknown alkane	10.69
PSB-3	Unknown alkane	10.78
PSB-3	Unknown alkane	11.16
PSB-3	Unknown alkane	11.21
PSB-3	Unknown alkane	11.32
PSB-3	Unknown alkane	11.56

PSB-3	Unknown alkane	11.95
PSB-3	Unknown alkane	17.97
PSB-3	Unknown alkane	20.65
PSB-3	Unknown	24.71

PCBs: No compounds were detected in the blanks.

Surrogate Recovery

Volatiles: All surrogate spike recoveries were within the set criteria.

Semivolatiles: All surrogate spike recoveries were within the set criteria.

PCBs: Surrogate spike recoveries were within the set criteria, with the exception of TCX (56%) in sample PBM-1MSB; action was not required.

Matrix Spike/Matrix Spike Duplicate

Volatiles: Two soil MS/MSDs and two MSBs were analyzed. Samples MW-6 and PSB-5 were designated for spiking and analysis as the MS/MSDs. No spike recoveries or RPD values were outside QC limits with one exception. The 1,1-dichloroethene RPD value for the PSB-5 MS/MSD was 23%. Since the criteria for this compound is 22% and the compound was not detected in any samples, it is this data reviewer's professional opinion that qualification of the data is not necessary.

Semivolatiles: A soil MS/MSD and MSB were analyzed. Sample PSB-3 was designated for spiking and analysis as the MS/MSD. One spike recovery (pentachlorophenol) was above the QC limits for the MS/MSD sample, and two spike recoveries (pentachlorophenol and 4-nitrophenol) were above the QC limits for the MSB sample. However, since these compounds were not detected in the associated sample, it is this data reviewer's opinion that qualification of the data is not necessary.

PCBs: A soil MS/MSD and MSB were analyzed. Sample PBM-1 was spiked with aroclor-1260 and analyzed as the MS/MSD. No spike recoveries or RPD values were outside QC limits for the MS/MSD and MSB samples.

Field Duplicates

Volatiles: Soil field duplicates were not required.

Semivolatiles: Soil field duplicates were not required.

PCBs: Soil field duplicates were not required.

Internal Standards Performance

Volatiles: All IS area counts and retention times met QC requirements with one exception. The retention time for chlorobenzene-d5 in sample FB120294 was 16.61. This retention time exceeded the ± 0.50 minute QC criteria of the ISTD retention time of 17.53. Since no compounds were detected in sample FB120294 that were associated with this standard, it is this data reviewers opinion that the data were not compromised and no qualification of the data was necessary.

Semivolatiles: All IS area counts and retention times met QC requirements.

Target Compound Identification

Volatiles: All relative retention times met QC requirements, and all compounds were reported correctly.

Semivolatiles: All relative retention times met QC requirements, and all compounds were reported correctly.

PCBs: All retention times met QC requirements and all compounds were reported correctly.

Compound Quantitation and Reported Detection Limit

Volatiles: All compound detection limits were met or adjusted for dilution factors.

Semivolatiles: All compound detection limits were met or adjust for dilution factors.

PCBs: All compound detection limits were met or adjusted for dilution factors.

Tentatively Identified Compounds

Volatiles: All TICs were reported correctly.

Semivolatiles: All TICs were reported correctly.

System Performance

Volatiles: The performance of the instruments during the volatile organic analyses is considered acceptable.

Semivolatiles: The performance of the instruments during the volatile organic analyses is considered acceptable.

Overall Assessment of Data

The quality of the data represented by this QC package is acceptable with the appropriate qualifiers specified in this memorandum.

SDG A1368 RESULTS

Holding Times

Volatiles: All samples were analyzed within seven days from time of sample collection.

GC/MS Tunes

Volatiles: Each set of tuning data meets the required ion abundance criteria. All samples were analyzed within the 12-hour tune time limit.

Calibration

Initial Calibration

Volatiles: Two initial calibrations were conducted. The initial calibration conducted using instrument HP5995B on November 5, 1994, had all relative response factors (RRF) ≥ 0.05 , and all percent relative standard deviations (%RSD) $\leq 30\%$, except for acetone which was 34.1%. The initial calibration conducted using instrument HP5972D on November 9, 1994, had all RRFs ≥ 0.05 , and all %RSDs $\leq 30\%$, except for acetone which was 62.5%. Acetone was not detected in any of the surface water samples; acetone was detected in sediment samples PSS-5, PSS-6, PSS-7, PSS-8, and PSS-9 but the results were not qualified as estimated (J) because they were further qualified as not detected (U) based on the blank results as discussed in Section IV.

Continuing Calibration

Volatiles: Four continuing calibration runs were conducted at the required frequency with all RRFs ≥ 0.05 and percent differences (%D) $\leq 25\%$, with the following exceptions:

Instrument ID	Date	Compound	<u>%D</u>
HP5995B	12/9/94	Chloromethane	-37.3
HP5995B HP5995B	12/9/94 12/9/94	Acetone 2-Butanone	29.5 39.6
HP5995B	12/9/94	4-Methyl-2-pentanone	32.6
HP5995B HP5995B	12/9/94 12/9/94	2-Hexanone 1,1,2,2-Tetrachloroethane	30.3 28.8

Results for the samples associated with the continuing calibration performed on December 9, 1994 were qualified as estimated (J) if detected and estimated (UJ) if non-detected.

Blanks

Volatiles: Four method blanks were analyzed; no compounds were detected in these blanks except for the following:

Method Blank: VBLK7 Date Analyzed: 12/9/94

Concentration in Micrograms

<u>Compound</u>

<u>per Kilogram (ug/kg)</u>

Acetone

25

The following sample results were qualified as not-detected (U) due to the associated method blank results:

Sample ID	Compound	Concentration (ug/kg)
PSS-5 PSS-7 PSS-6 PSS-8 PSS-9	Acetone Acetone Acetone Acetone Acetone	30 U 17 U 28 U 110 U 41 U
		-T1 U

No tentatively identified compounds (TICs) were detected in any of the method blanks.

Two field blanks and one trip blank were analyzed; no compounds were detected in FB120794. The following compounds were detected in the remaining blanks:

Sample ID	Compound	Concentration (ug/L)
TB120794	Chloroform	1 J
FB120694	Toluene	2 Ј

The samples associated with FB120694 were reported in the first data package (SDG Z1368), and are therefore not discussed in this section. No qualification of chloroform sample results associated with TB120794 were required because the chloroform concentrations in the samples exceeded the blank concentration multiplied by five. No TICs were detected in the field blanks.

Surrogate Recovery

Volatiles: All surrogate spike recoveries were within the set criteria.

Matrix Spike/Matrix Spike Duplicate

Volatiles: A surface water MS/MSD and one MSB were analyzed. Sample PSW-9 was spiked and analyzed as the MS/MSD. No spike recoveries or relative percent difference (RPD) values were outside QC limits for the PSW-9 MS/MSD and the MSB. A soil MS/MSD was analyzed and reported in SDG Z1368. Qualification of the data was not necessary based on the MS/MSD and MSB results.

Field Duplicates

A field duplicate of surface water sample PSW-9 was collected and labelled DUP. Both PSW-9 and DUP were analyzed with chloroform and bromodichloromethane detected in both at the same estimated concentrations of 9 ug/L and 2 ug/L, respectively. It is this data reviewer's opinion that these field duplicate results are acceptable.

Internal Standards

Volatiles: All internal standard (IS) area counts and retention times met QC requirements.

Target Compound Identification

Volatiles: All relative retention times met QC requirements and all compounds were reported correctly.

Compound Quantitation and Reported Detection Limits

Volatiles: All compound detection limits were met or were adjusted for dilution factors.

Tentatively Identified Compounds

Volatiles: All TICs were reported correctly.

System Performance

The performance of the instruments during the volatile organic analyses is considered acceptable.

Overall Assessment of Data

The quality of the data represented by this QC package is acceptable with the appropriate qualifiers specified in this memorandum.

SDG Z0018 RESULTS

Holding Times

Volatiles: All samples were analyzed within seven days from time of sample collection.

GC/MS Tunes

Volatiles: Each set of tuning data meets the required ion abundance criteria. All samples were analyzed within the 12-hour tune time limit.

Calibration

Initial Calibration

Volatiles: One initial calibration was conducted on November 9, 1994 on instrument HP5972D. This initial calibration had all relative response factors (RRF) ≥ 0.05 and all percent relative standard deviations (%RSD) $\leq 30\%$, except for acetone which was 62.5%. Acetone was not detected in any of the groundwater samples, and therefore, no action was taken.

Continuing Calibration

Volatiles: One continuing calibration run was conducted (January 9, 1995) at the required frequency, and all RRFs were ≥ 0.05 and percent differences (%D) were ≤ 25 %, with one exception. The %D for chloroethane was 33.0%. Chloroethane was not detected in any sample associated with this continuing calibration, and therefore, the non-detect chloroethane sample results were qualified as estimated (UJ).

Blanks

Volatiles: One method blank was analyzed; no compounds were detected in this blank.

One field blank and one trip blank were analyzed; no compounds were detected in these blanks with the exception of chloroform which was detected in FB010595 at an estimated concentration of 1 ug/L. Chloroform was not detected in any of the samples associated with this blank, therefore no qualification of the data was necessary.

Surrogate Recovery

Volatiles: All surrogate spike recoveries were within the set criteria.

Matrix Spike/Matrix Spike Duplicate

Volatiles: A MS/MSD and MSB were analyzed. Sample MW-1 was spiked and analyzed as the MS/MSD. No spike recoveries or RPD values were outside QC limits for the MW-1 MS/MSD and the MSB.

Field Duplicates

A field duplicate of groundwater sample MW-3 was analyzed. Xylene (total) was detected in MW-3 at an estimated concentration of 0.7 ug/L, but was not detected in the duplicate (10U). The data are considered acceptable with no qualification necessary.

Internal Standards

Volatiles: All internal standard (IS) area counts and retention times met QC requirements.

Target Compound Identification

Volatiles: All relative retention times met QC requirements and all compounds were reported correctly.

Compound Quantitation and Reported Detection Limits

Volatiles: All compound detection limits were met or were adjusted for dilution factors.

Tentatively Identified Compounds

Volatiles: All TICs were reported correctly.

System Performance

The performance of the instruments during the volatile organic analyses is considered acceptable.

Overall Assessment of Data

The quality of the data represented by this QC package is acceptable with the appropriate qualifiers specified in this memorandum.

APPENDIX G

LABORATORY REPORTS

TABLE VOA-1.6 3094-1368 GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/Kg dry weight basis.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	MW-6 MSD 1368002MSD VBLKB3 1.12	MW-3I 1368003 VBLKB3 1.09	MW-4I 1368004 VBLKB3 1.08	Quant. Limits with no Dilution
Chloromethane	ט	ט	ט	10
Bromomethane	U and the last	U U	The Transfer	10
Vinyl Chloride	ט	Ū	U	10
Chloroethane	טאיי	U	Taken University	C. 335.00
Methylene Chloride	Ū	U Ges	U VALES IN THANK XX, SC	10
Acetone	61	Ū O	38	10
Carbon Disulfide	ט	ט ט	U TO THE STATE OF	10
1,1-Dichloroethene	53X	U	Market 19 mill	10
1,1-Dichloroethane	U	U	บ	10
1,2-Dichloroethene (total)	U	U	U	10
Chloroform	ט	U		10
1,2-Dichloroethane	U en	Ū	ש	10
2-Butanone	U	ט	ט	10
1,1,1-Trichloroethane	91,5 U	י ס	υ 🦸	10
Carbon Tetrachloride	U	ן ט	ט	10
Bromodichloromethane	σ	ט	U and	10
1,2-Dichloropropane	Ū	ט	ן ט	10
cis-1,3-Dichloropropene	ן ס	ט	U	10
Trichloroethene	64X	2Ј	ט ו	10
Dibromochloromethane	ט	ט	ן ט	10
1,1,2-Trichloroethane	ט	σ	ן ט ן	10
Benzene	59X	U	ן ט	10
trans-1,3-Dichloropropene	ט	ט	ט	10
Bromoform	ט	ט	ט	10
4-Methyl-2-Pentanone	U	ט	ប	10
2-Hexanone	ט	U	O U	10
Tetrachloroethene	ט	Ū	U	10
1,1,2,2-Tetrachloroethane	U	Miles U	U	10
Toluene	62X	21	3J	10
Chlorobenzene	62X	U.	ט יי	10
Ethylbenzene	Ū	U	U	10
Styrene	U	U	U	10
Xylene (total)	<u>ט</u>	<u> </u>	Ū	10
Date Received	11/20/04	10/01/01	10.101.101	
Date Extracted	11/30/94	12/01/94	12/01/94	
Date Analyzed	N/A	N/A	N/A	1
pare marined	12/05/94	12/05/94	12/05/94	

TABLE VOA-1.8 3094-1368 GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/Kg dry weight basis.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	MW-7 1368010 VBLKB3 1.20	P8B-5 1368013 VBLKB3 1.28	PSB-5 MS 1368013MS VBLKB3 1.28	Quant. Limits with no Dilution
Chloromethane Bromomethane Vinyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene Xylene (total)	00000000000000000000000000000000000000	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	U U U U U U U U U U U U U U U U U U U	10 10 10 10 10 10 10 10 10 10 10 10 10 1
Date Received Date Extracted Date Analyzed	12/02/94 N/A 12/05/94	12/05/94 N/A 12/05/94	12/05/94 N/A 12/05/94	

TABLE VOA-1.9 3094-1368 GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/Kg dry weight basis.

Client Sample I.D.	PSB-4		Quan	
Lab Sample I.D. Method Blank I.D.	1368014	l	Limi	
Dilution Factor	VBLKB3	<u> </u>	with Dilu	
	1 1 1		DITE	1610
Chloromethane	ט		1 1	LO
Bromomethane	Ū	4.3.3444		LO
Vinyl Chloride	ט	50000 VIII	1 1	LO
Chloroethane	ט			LO .
Methylene Chloride	ט	37.44	1 -	LO
Acetone	20		1 -	10
Carbon Disulfide	ט			10
1,1-Dichloroethene	The Late		1 7	10
1,1-Dichloroethane 1,2-Dichloroethene (total)	ם			10
Chloroform	0	in the	1 7	10 10
1,2-Dichloroethane	a a	Į.	1 -	10
2-Butanone		İ		10
1,1,1-Trichloroethane	ا ق		i -	10
Carbon Tetrachloride	Ü			10
Bromodichloromethane	ט	i=		10
1,2-Dichloropropane	ן ס			10
cis-1,3-Dichloropropene	ט	of the state of		10
Trichloroethene	ט			10
Dibromochloromethane	ש	7 7		10
1,1,2-Trichloroethane	ם		1	10
Benzene	ם	1470 to	1	10
trans-1,3-Dichloropropene Bromoform	ם ט			10
4-Methyl-2-Pentanone	ן ט	>		10
2-Hexanone	ן ט	-42		10 10
Tetrachloroethene	l ö l	7,00	1	10
1,1,2,2-Tetrachloroethane	Ü			10
Toluene	3J	******		10
Chlorobenzene	י ס			10
Ethylbenzene	ס	1 1000000	30 T II	10
styrene	ט			10
Xylene (total)	<u>ט</u>			10
Date Received	12/05/94			
Date Extracted	N/A		ļ	
Date Analyzed	12/05/94	1	1	

TABLE VOA-1.10 3094-1368 GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/Kg dry weight basis.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	Method Blank VBLKB4 VBLKB4 1.00	PSB-5 MSD 1368013MSD VBLKB4 1.28	Quant. Limits With no Dilution
Chloromethane Bromomethane Vinyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene Xylene (total)	2	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	10 10 10 10 10 10 10 10 10 10 10 10 10 1
Date Received Date Extracted Date Analyzed	N/A 12/06/94	12/05/94 N/A 12/06/94	

TABLE VOA-1.12 3094-1368 GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/Kg dry weight basis.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	PSB-3 1368019 VBLKB7 1.43		a a		Quant. Limits with no Dilution
Chloromethane	ט				10
Bromomethane	ט				10
Vinyl Chloride	U				10
Chloroethane Methylene Chloride	U		556	7 \$06	10
Acetone	2J 31B				10
Carbon Disulfide	1 31B	7.0			10
1,1-Dichloroethene	l ü				10
1,1-Dichloroethane	ט ו		Δ		10
1,2-Dichloroethene (total)	U				10
Chloroform	ט		1		10
1,2-Dichloroethane 2-Butanone	ט				10
1,1,1-Trichloroethane	U				10
Carbon Tetrachloride	U				10
Bromodichloromethane	Ü				10
1,2-Dichloropropane	Ŭ		ł		10
cis-1,3-Dichloropropene	υ	<u> </u>	1		10
Trichloroethene	ט		ļ		10
Dibromochloromethane	ט				10
1,1,2-Trichloroethane · Benzene	U				10
trans-1,3-Dichloropropene	ט				10
Bromoform	ם פ				10
4-Methyl-2-Pentanone	บั				10
2-Hexanone	Ŭ				10
Tetrachloroethene	บ				10
1,1,2,2-Tetrachloroethane	σ				10
Toluene	6 J				10
Chlorobenzene	U		- 65		10
Ethylbenzene Styrene	U	25			10
Xylene (total)	ם ע				10
Date Received	12/07/94				
Date Extracted	N/A				
Date Analyzed	12/09/94				

TABLE SV-1.0 3094-1368 GERAGHTY & MILLER EPA TCL SEMI-VOLATILE ORGANICS

All values are ug/Kg dry weight basis.

Sample Identification

Dilution Factor	1.0	1.42	1.42	1.42	
Method Blank I.D.	<u>SBLKFI</u>	SBLKFI	<u>SBLKFI</u>	<u>SBLKFI</u>	0
Compound	Method <u>Blank</u>	PSB-3	PSB-3 MS	PSB-3 MSD	Quantitation Limits with no Dilution
Phenol	U	U	2,000X	2,100X	330
bis(2-Chloroethyl)ether	U	U	U	U	330
2-Chlorophenol	U	U	2,100X	2,200X	330
1,3-Dichlorobenzene	U	U	Ū	Û	330
1,4-Dichlorobenzene	U	U	1,200X	1,300X	330
1,2-Dichlorobenzene	U	U	Ū	Ü	330
2-Methylphenol	U	U	U	U	330
2,2'-oxybis(1-Chloropropane)	U	U	U	U	330
4-Methylphenol	U	U	U	U	330
N-Nitroso-di-n-propylamine	U	U	1,500X	1,600X	330
Hexachloroethane	U	U	Ú	Ú	330
Nitrobenzene	U	U	U	U	330
Isophorone	U	U	U	U	330
2-Nitrophenol	U	U	U	U	330
2,4-Dimethylphenol	U	U	U	U	330
bis(2-Chloroethoxy)methane	U	U	U	U	330
2,4-Dichlorophenol	Ü	U	Ú	U	330
1,2,4-Trichlorobenzene	U	U	1,400X	1,500X	330
Naphthalene	Ü	U	Ü	Ú	330
4-Chloroaniline	Ū	Ü	Ū	Ü	330
Hexachlorobutadiene	Ü	Ū	Ū	Ü	330
4-Chloro-3-methylphenol	Ū	Ū	2.200X	2,500X	330
2-Methylnaphthalene	Ŭ	Ū	Ü	U	330
Hexachlorocyclopentadiene	Ū	Ũ	Ũ	Ŭ	330
2,4,6-Trichlorophenol	Ū	Ŭ	Ŭ	Ŭ	330
2,4,5-Trichlorophenol	Ŭ	Ŭ	Ŭ	Ŭ	800
2-Chloronaphthalene	Ŭ	Ū	Ŭ	Ŭ	330
2-Nitroaniline	Ŭ	Ū	Ū	Ŭ	800
Dimethylphthalate	Ŭ	Ŭ	Ŭ	Ŭ	330
Acenaphthylene	Ŭ	Ŭ	Ŭ	Ŭ	330
2,6-Dinitrotoluene	Ŭ	Ŭ	Ŭ	Ŭ	330
3-Nitroaniline	Ŭ	Ŭ	Ŭ	Ŭ	800
Acenaphthene	Ŭ	Ŭ	•	(1,600X	330
•			-	-	

See Appendix for qualifier definitions.

Note: Sample detection limit = quantitation limit x dilution factor.

TABLE SV-1.0 3094-1368 GERAGHTY & MILLER EPA TCL SEMI-VOLATILE ORGANICS

All values are ug/Kg dry weight basis.

Sample Identification

Dilution Factor	1.0 1.42 1.42 1.42	
Method Blank I.D.	SBLKFI SBLKFI SBLKFI	
Compound	Method PSB-3 PSB-3 Blank PSB-3 MS MSD	Quantitation Limits with no
2,4-Dinitrophenol 4-Nitrophenol Dibenzofuran 2,4-Dinitrotoluene Diethylphthalate 4-Chlorophenyl-phenylether Fluorene 4-Nitroaniline 4,6-Dinitro-2-methylphenol N-Nitrosodiphenylamine (1) 4-Bromophenyl-phenylether lexachlorobenzene Pentachlorophenol Phenanthrene Anthracene Carbazole Di-n-butylphthalate Fluoranthene Pyrene Butylbenzylphthalate 3,3'-Dichlorobenzidine Benzo(a)anthracene Chrysene bis(2-Ethylhexyl)phthalate Di-n-octylphthalate Benzo(b)fluoranthene Benzo(k)fluoranthene Benzo(a)pyrene	U U U U U U U U U U U U U U U U U U U	800 800 330 330 330 330 800 800 330 330
Indeno(1,2,3-cd)pyrene Dibenzo(a,h)anthracene Benzo(g,h,i)perylene	U U 34J U U U U U U V 32J U	330 330 330

TABLE SV-2.0 3094-1368 GERAGHTY & MILLER SEMI-VOLATILE TENTATIVELY IDENTIFIED COMPOUNDS

Sample Identification: Method Blank SBLKFI

CAS#	Compound	RT	Estimated Concentration, ug/Kg
141797	Unknown 3-penten-2-one,4-methyl-	5.38	540JN
	Unknown	5.97	400J
	Unknown	6.38	1,400J
	Aldol condensation product	7.07	57,000JA
	Unknown	8.44	590J
	Unknown alkane	9.27	110J
	Unknown alkane	10.55	400J
	Unknown alkane	10.69	180J
	Unknown alkane	10.78	470J
	Unknown alkane	11.16	500J
	Unknown alkane	11.20	150J
	Unknown alkane	11.31	360J
	Unknown	11.41	99J
	Unknown alkane	11.55	370J
	Unknown alkane	11.76	773
	Unknown alkane	11.95	100J
	Unknown alkane	17.97	100J
	Unknown alkane	20.65	91J
	Unknown alkane	23.04	72J
	Unknown	24.70	98J
	Unknown alkane	27.59	120J

Sample Identification: PSB-3

CAS#	Compound	RT	Estimated Concentration, ug/Kg
141797	3-Penten-2-one,4-methyl- Unknown Unknown Aldol condensation product Unknown	5.40 5.98 6.33 7.04 8.43	640JNB 870JB 1,400JB 74,000JAB 740JB
	Unknown alkane	9.28 10.55 10.69 10.78 11.16 11.21	280JB 960JB 420JB 1,100JB 1,200JB 370JB

TABLE SV-2.1 3094-1368 GERAGHTY & MILLER SEMI-VOLATILE TENTATIVELY IDENTIFIED COMPOUNDS

Sample Identification: PSB-3 (continued)

CAS#	Compound	RT	Estimated Concentration, ug/Kg
	Unknown alkane	11.32	880JB
	Unknown alkane	11.56	860JB
	Unknown alkane	11.95	230JB
	Unknown alkane	17.97	260JB
	Unknown alkane	20.65	230JB
57103	Hexadecanoic acid	23.47	570JN
	Unknown	24.71	230JB
	Unknown	25.27	700J
57114	Octadecanoic acid	25.47	480JN
103231	Hexanedioic acid,bis(2-eth	27.64	6,000JN

TABLE GC-1.0 3094-1368 GERAGHTY & MILLER POLYCHLORINATED BIPHENYLS (PCB's)

All values are ug/Kg dry weight basis.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	Method Blank 120694-B05 PBLK29 1.00	PBM-1 MS 1368008MS PBLK29 1.33	PBM-1 MSD 1368008MSD PBLK29 1.33	Quant. Limits with no Dilution
Aroclor-1016 Aroclor-1221 Aroclor-1232 Aroclor-1242 Aroclor-1248 Aroclor-1254 Aroclor-1260	บ บ บ บ บ	UX UX UX UX UX UX UX 91X	UX UX UX UX UX UX 89X	33 67 33 33 33 33 33
Date Received Date Extracted Date Analyzed	12/06/94 12/13/94	12/02/94 12/06/94 12/13/94	12/02/94 12/06/94 12/13/94	

TABLE GC-1.1 3094-1368 GERAGHTY & MILLER POLYCHLORINATED BIPHENYLS (PCB's)

All values are ug/Kg dry weight basis.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	PBM-2 1368009 PBLK29 1.35	Quant. Limits with no Dilution
Aroclor-1016 Aroclor-1221 Aroclor-1232 Aroclor-1242 Aroclor-1248 Aroclor-1254 Aroclor-1260	ט ט ט ט ט	33 67 33 33 33 33 33
Date Received Date Extracted Date Analyzed	12/02/94 12/06/94 12/13/94	

TABLE GC-1.2 3094-1368 GERAGHTY & MILLER POLYCHLORINATED BIPHENYLS (PCB's)

All values are ug/Kg dry weight basis.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	Method Blank 120894-B05 PBLK37 1.00	PBM-1 1368008 PBLK37 1.33	Quant. Limits with no Dilution
Aroclor-1016 Aroclor-1221 Aroclor-1232 Aroclor-1242 Aroclor-1248 Aroclor-1254 Aroclor-1260	ט ט ט ט	ם מ מ מ מ	33 67 33 33 33 33
Date Received Date Extracted Date Analyzed	12/08/94 12/13/94	12/02/94 12/08/94 12/13/94	

TABLE AS-1.0 3094-1368 GERAGHTY & MILLER EPA TAL METALS

All values are mg/Kg dry weight basis.

Client Sample I.D. Lab Sample I.D.	MW-6 1368002	MW-6 D 1368002D	MW-6 S 1368002S	MW-3I 1368003
				1300003
Aluminum Antimony Arsenic Barium Beryllium Cadmium Calcium Chromium Cobalt Copper Cyanide Iron Lead Magnesium Manganese Mercury Nickel Potassium Selenium Silver Sodium Thallium Vanadium	4600 8.4UN 3.6 37.7B 0.26B 0.44U 50800* 11.1 5.9B 15.4 0.53UN 11700 3.2 13600* 458.*N 0.10U 11.6 589.B 0.22U 0.67U 76.8B 0.38B 7.1B	4770 10.3B 3.2 35.9B 0.22U 0.44U 54800 6.2 6.2B 14.5 0.54U 10800 3.2 14400 397. 0.10U 12.4 779.B 0.22U 0.67U 70.8B 0.22U 7.1B	4580 75.2N 11.8 406. 9.0 10.1 NR 44.6 97.8 58.3 3.8N 10100 6.9 NR 466. 0.55 100. NR 1.7 9.2 NR 10.3	6630 8.2UN 2.0B 33.3B 0.27B 0.43U 41700* 10.1 4.6B 8.4 0.54UN 12100 2.3+S 17200* 332.*N 0.11U 13.8 986.B 0.22U 0.64U 80.1B 0.22U
Zinc	24.0	22.0	99.3 113.	9.5B 22.7

TABLE AS-1.1 3094-1368 GERAGHTY & MILLER EPA TAL METALS

All values are mg/Kg dry weight basis.

				
	Ì			
Client Sample I.D.	MW-4I	PSS-11	MW - 7	PSB-5
Lab Sample I.D.	1368004	1368007	1368010	1368013
Aluminum	3940	9470	2270	5360
Antimony	8.2UN	10.5UN	8.9UN	9.5UN
Arsenic	2.7	0.280	1.6BS	2.4B
Barium	29.3B	120.	6.4B	22.8B
Beryllium	0.21U	0.28ប	0.23T	0.250
Cadmium	0.43T	0.55ซ	0.47U	0.500
Calcium	52300*	9000*	48300*	27300*
Chromium	5.2	3.2	4.7	6.6
Cobalt	3.9B	2.4B	3.7B	4.4B
Copper	7.7	6.3B	16.9	10.6
Cyanide	0.51UN	0.67UN	0.57UN	0.60UN
Iron	8740	583.	6350	9150
Lead	3.5S	3060	4.4	29.9
Magnesium	14000*	399.B*	16700*	9250*
Manganese	307.*N	14.1*N	244.*N	257.*N
Mercury	0.100	0.130	0.0940	0.110
Nickel	7.0B	3.2B	8.2B	10.B
Potassium	813.B	1980	311.B	630.B
Selenium	0.210	0.280	0.23U	0.25T
Silver	0.64U	0.83U	0.700	0.75ช
Sodium	73.0B	4710	75.3B	161.B
Thallium	0.210	0.280	0.23U	0.250
Vanadium	6.9B	2.5B	5.0B	14.3
Zinc	28.4	319.	14.7	22.6

TABLE AS-1.2 3094-1368 GERAGHTY & MILLER EPA TAL METALS

All values are mg/Kg dry weight basis.

Client Sample I.D. Lab Sample I.D.	PSB-5 D 1368013D	PSB-5 S 1368013S	PSB-4 1368014	PSB-1 1368017
Aluminum Antimony Arsenic Barium Beryllium Cadmium Calcium Chromium Cobalt Copper Cyanide Iron Lead Magnesium Manganese Mercury Nickel Potassium Selenium Silver Sodium Thallium Vanadium	4870 9.5U 2.5 22.3B 0.33B 0.50U 46100* 7.3 6.0B 11.2 0.62U 11000 17.8B 14900* 458.* 0.10U 12.6 522.B 0.26U 0.75U 186.B 0.25U 8.1B	4390 84.0N 12.5 450. 11.3 11.8 NR 50.2 109. 62.2 6.1 9170 39.8 NR 452.N 0.61 111. NR 2.4 10.9 NR 12.2 118.	3920 9.5UN 4.4 38.2B 0.25U 0.50U 37800* 6.2 3.3B 10.2 0.60UN 8340 3.8 15100* 296.*N 0.12U 5.6B 402.B 0.25U 0.75U 102.B 0.25U	7320 9.1UN 5.9 57.2 0.29B 0.48U 42200* 10.5 7.2B 16.4 0.58UN 16800 6.8S 14800* 422.*N 0.11U 16.2 846.B 1.2U 0.72U 117.B 0.24U 15.2
Zinc	28.2	127.	20.0	30.3

TABLE AS-1.3 3094-1368 GERAGHTY & MILLER EPA TAL METALS

All values are mg/Kg dry weight basis.

Client Sample I.D.	PSB-2	DOD 3		
Cilent Sample 1.D.	PSB-2	PSB-3		XO
Lab Sample I.D.	1368018	1368019		
Aluminum	5600	6690		
Antimony	8.6UN	9.4UN	ļ	
Arsenic	3.3	1.0BW		
Barium	32.8B	19.7B		1
Beryllium	0.26B	0.25U		
Cadmium	0.45U	0.500	f	
Calcium	52000*	55600*		į
Chromium	6.2	3.3		
Cobalt	5.4B	2.9B		ļ
Copper	16.4	7.9		
Cyanide	0.55UN	0.62UN		
Iron	10500	3410		
Lead	11.65	426.	1	
Magnesium	21500*	4910*	Ì	
Manganese	362.*N	106.*N		}
Mercury	0.0940	0.12U		
Nickel	10.6	- 4.7B	1	
Potassium	681.B	868.B		İ
Selenium	0.23U	0.25U		
Silver	0.68U	0.740		
Sodium	114.B	1140B		
Thallium	0.23U	0.25U		
Vanadium	11.2B	7.0B		
Zinc	25.6	36.7		ľ

ORGANICS APPENDIX

- U Indicates that the compound was analyzed for but not detected.
- J Indicates that the compound was analyzed for and determined to be present in the sample. The mass spectrum of the compound meets the identification criteria of the method. The concentration listed is an estimated value, which is less than the specified minimum detection limit but is greater than zero.
- B This flag is used when the analyte is found in the blanks as well as the sample. It indicates possible sample contamination and warns the data user to use caution when applying the results of this analyte.
- N Indicates that the compound was analyzed for but not requested as an analyte. Value will not be listed on tabular result sheet.
- S Estimated due to surrogate outliers.
- X Matrix spike compound.
- (1) Cannot be separated.
- (2) Decomposes to azobenzene. Measured and calibrated as azobenzene.
- A This flag indicates that a TIC is a suspected aldol condensation product.
- E Indicates that it exceeds calibration curve range.
- D This flag identifies all compounds identified in an analysis at a secondary dilution factor.
- C Confirmed by GC/MS.
- T Compound present in TCLP blank.
- P This flag is used for a pesticide/aroclor target analyte when there is a greater than 25 percent difference for detected concentrations between the two GC columns (see Form X).

INORGANICS APPENDIX

C - Concentration qualifiers

- U Indicates analyte result less than instrument detection limit (IDL)
- B Indicates analyte result between IDL and contract required detection limit (CRDL)

Q - QC qualifiers

- E Reported value is estimated because of the presence of interference
- M Duplicate injection precision not met
- ${\bf N}$ Spiked sample recovery not within control limits
- S The reported value was determined by the method of standard additions (MSA)
- W Post-digest spike recovery furnace analysis was out of 85-115 percent control limit, while sample absorbance was less than 50 percent of spike absorbance
- * Duplicate analysis not within control limit
- + Correlation coefficient for MSA is less than 0.995

M - Method codes

- P ICP
- A Flame AA
- F Furnace AA
- CV Cold vapor AA (manual)
- C Cyanide
- NR Not Required
- NC Not Calculated as per protocols

STATE CERTIFICATIONS

In some instances it may be necessary for environmental data to be reported to a regulatory authority with reference to a certified laboratory. For your convenience, the laboratory identification numbers for the IEA-Connecticut laboratory are provided in the following table. Many states certify laboratories for specific parameters or tests within a category (i.e. method 325.2 for wastewater). The information in the following table indicates the lab is certified in a general category of testing such as drinking water or wastewater analysis. The laboratory should be contacted directly if parameter-specific certification information is required.

IEA-Connecticut Certification Summary (as of June 1993)

State	Responsible Agency	Certification	Lab Number
Connecticut	Department of Health Services	Drinking Water, Wastewater	PH-0497
Kansas	Department of Health and Environmental Services	Drinking Water, Wastewater/Solid, Hazardous Waste	E-210/E-1185
Massachusetts	Department of Environmental Protection	Potable/Non-Potable Water	CT023
New Hampshire	Department of Environmental Services	Drinking Water, Wastewater	252891
New Jersey	Department of Environmental Protection	Drinking Water, Wastewater	46410
New York	Department of Health	CLP, Drinking Water, Wastewater, Solid/ Hazardous Waste	10602
North Carolina	Division of Environmental Management	Wastewater	388
Rhode Island	Department of Health	ChemistryNon- Potable Water and Wastewater	- A43
California	Department of Health Services	Hazardous Waste	1778

TABLE VOA-1.2 3094-1368 GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/L.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	TB 120194 1368012 VBLKDX 1.00	FB 120294 1368015 VBLKDX 1.00	Quant. Limits With no Dilution
Chloromethane Bromomethane Vinyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene Xylene (total)	מממממממממממממממממממממממממממממממממממממממ	מממממממממממממממממממממממממממממממממממממממ	10 10 10 10 10 10 10 10 10 10 10 10 10 1
Date Received Date Extracted Date Analyzed	12/02/94 N/A 12/06/94	12/05/94 N/A 12/06/94	

TABLE VOA-1.1 3094-1368 GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/L.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	Method Blank VBLKDX VBLKDX 1.00	TB 113094 1368006 VBLKDX 1.00	FB 120194 1368011 VBLKDX 1.00	Quant. Limits With no Dilution
Chloromethane Bromomethane Vinyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene Xylene (total)	ט ט ט ט ט ט ט ט ט ט ט ט ט ט ט ט ט ט ט		666666666666666666666666666666666666666	10 10 10 10 10 10 10 10 10 10 10 10 10 1
Date Received Date Extracted Date Analyzed	N/A 12/06/94	12/01/94 N/A 12/06/94	12/02/94 N/A 12/06/94	

TABLE VOA-1.11 3094-1368 GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/Kg dry weight basis.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	Method Blank VBLKB7 VBLKB7 1.00	PSB-1 1368017 VBLKB7 1.19	PSB-2 1368018 VBLKB7 1.14	Quant. Limits With no Dilution
Chloromethane Bromomethane Vinyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene Xylene (total)	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 2 3 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	00000000000000000000000000000000000000	10 10 10 10 10 10 10 10 10 10 10 10 10 1
Date Received Date Extracted Date Analyzed	N/A 12/09/94	12/07/94 N/A 12/09/94	12/07/94 N/A 12/09/94	

TABLE VOA-1.3 3094-1368 GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/L.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	Method Blank VBLKDY VBLKDY 1.00	TB 120294 1368016 VBLKDY 1.00	Quant. Limits with no Dilution
Chloromethane Bromomethane Vinyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene Xylene (total)	םמססטטטטטטטטטטטטטטטטטטטטטטטטטטטטטטטטטטט	ממממממממממממממממממממממממממ	10 10 10 10 10 10 10 10 10 10 10 10 10 1
Date Received Date Extracted Date Analyzed	N/A 12/07/94	12/05/94 N/A 12/07/94	

TABLE VOA-1.0 3094-1368 GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/L.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	Method Blank VBLKGG VBLKGG 1.00	FB 112894 1368001 VBLKGG 1.00	FB 113094 1368005 VBLKGG 1.00	Quant. Limits with no Dilution
Chloromethane Bromomethane Vinyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,1-Dichloroethene 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane 8enzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene Xylene (total)	0.8J 4J 00.8J 1J 0000000000000000000000000000000000	ם טטטטטטטטטטטטטטטטטטטטטטטטטטטטטטטטטטטט		10 10 10 10 10 10 10 10 10 10 10 10 10 1
Date Received Date Extracted Date Analyzed	N/A 12/03/94	11/30/94 N/A 12/03/94	12/01/94 N/A 12/03/94	

TABLE VOA-1.4 3094-1368 GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/L.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	Method Blank VBLKD2 VBLKD2 1.00	TB 120694 1368020 VBLKD2 1.00		Quant. Limits With no Dilution
Chloromethane Bromomethane Vinyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide	ט ט ט ט ט ט	ช บ บ บ บ		10 10 10 10 10 10
1,1-Dichloroethene 1,1-Dichloroethane 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane	U U U U U U	ט ט ט ט ט	5) 1 <u></u>	10 10 10 10 10 10
Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane	บ บ บ บ บ บ	ט ט ט ט ט	a =	10 10 10 10 10 10
Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane	ט ט ט ט ט	ט ט ט ט	-	10 10 10 10 10
Toluene Chlorobenzene Ethylbenzene Styrene Xylene (total)	0 0 0 0 0 0	บ บ บ บ		10 10 10 10 10
Date Received Date Extracted Date Analyzed	N/A 12/09/94	12/07/94 N/A 12/09/94		

TABLE VOA-1.5 3094-1368 GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/Kg dry weight basis.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	Method Blank VBLKB3 VBLKB3 1.00	MW-6 1368002 VBLKB3 1.12	MW-6 MS 1368002MS VBLKB3 1.12	Quant. Limits With no Dilution
Chloromethane	ט	บ	ט	10
Bromomethane	บั	Ŭ	Ŭ	10
Vinyl Chloride	Ŭ	ซื	Ŭ	10
Chloroethane	υ	Ü	บั	10
Methylene Chloride	Ū	Ü	U	10
Acetone	υ	39	81	* 10
Carbon Disulfide	Ū	บ		10
1,1-Dichloroethene	ŭ Ü	Ü	56X	= 10
1,1-Dichloroethane	Ü	υ	U	10
1,2-Dichloroethene (total)	U	Ū	U	10
Chloroform	Ū	ט	Ū	10
1,2-Dichloroethane	Ū	ש	U 1. 3 15	10
2-Butanone	ט	υ	3J	10
1,1,1-Trichloroethane	U	ט	U	10
Carbon Tetrachloride	U	ט	ן ט	10
Bromodichloromethane	U	ש	U	10
1,2-Dichloropropane	U	U	U	10
cis-1,3-Dichloropropene	ט	ש	ט	10
Trichloroethene	ט	Ū	62X	10
Dibromochloromethane	ט	ן ד	ט	10
1,1,2-Trichloroethane	ט	Ū	ט	10
Benzene	U	Ū	57X	10
trans-1,3-Dichloropropene	ū	U	Ū	10
Bromoform	ט	U	U	10
4-Methyl-2-Pentanone 2-Hexanone	U	ט	U	10
Tetrachloroethene	U ,	ט -	Ü	10
1,1,2,2-Tetrachloroethane	U	ט	ט	10
Toluene	U U	Ū	U	10
Chlorobenzene	u u	2J	61X	10
Ethylbenzene		U	60X	10
Styrene	_ U	U	U	10
Xylene (total)	U U	U	Ü	10 10
Date Received		11/30/94	11/30/94	
Date Extracted	N/A	N/A	N/A	
Date Analyzed	12/05/94	12/05/94	12/05/94	ì

TABLE VOA-1.0 3094-1368A GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/L.

Lab Sample I.D. Method Blank I.D. Dilution France VBLKD2 VBLKD2 VBLKD2			
Lab Sample I.D. Method Blank I.D. Dilution Factor Chloromethane Bromomethane Bromomethane Vinyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethane 1,2-Dichloroethane 1,2-Dichloroethane 1,1,1-Trichloroethane 2-Butanone 1,1,1-Trichloroethane 1,1,1-Trichloroethane 1,2-Dichloromethane 1,2-Dichloromethane 1,1,2-Trichloroethane 1,2-Dichloromethane 1,1,2-Trichloroethane UU Trichloroethene UI Dibromochloromethane 1,1,2-Trichloroethane UI Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene Tetrachloroethene UI 1,1,2,2-Tetrachloroethane UI 1,1,2,2-Tetrachloroethane UI Toluene Chlorobenzene Ethylbenzene Styrene UI VBEKD2 VBEKD	120694 PS	W-7	
Method Blank I.D. Dilution Factor Chloromethane Bromomethane Winyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,2-Dichloroethene 1,2-Dichloroethene 1,1,1-Trichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropene Trichloroethene Unu 1,2-Trichloroethane Unu 1,2-Trichloroethane Unu 1,1,2-Trichloroethane Unu 1,1,2,2-Tetrachloroethane Unu 1,2-Dichloroethane		Qua	nt.
Dilution Factor Chloromethane Bromomethane Vinyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,2-Dichloroethene 1,2-Dichloroethane 1,2-Dichloroethane 1,1,1-Trichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane Cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene Etrachloroethene 1,1,2,2-Tetrachloroethane Tetrachloroethene 1,1,2,2-Tetrachloroethane Tetrachloroethene Chlorobenzene Ethylbenzene Styrene VU VU VU VU VU VU VU VU VU VU		8024 Lim	its
Chloromethane Bromomethane Vinyl Chloride Chloroethane Wethylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,2-Dichloroethane 1,2-Dichloroethane 1,2-Dichloroethane 1,1,1-Trichloroethane 2-Butanone 1,1,1-Trichloroethane UCarbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane Cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane UU 1,1,2-Trichloroethane UU 1,1,2-Trichloropropene UU Trichloroethene UU 1,1,2-Trichloroethane UU 1,1,2-Tetrachloroethane UU 1,1,2,2-Tetrachloroethane UU 1,2-Tetrachloroethane UU 1,2-Tetrachloroethane UU 1,2-Tetrachloroethane UU 1,2,2-Tetrachloroethane UU 1,2-Tetrachloroethane UU 1,2-Tetrachloroethane UU 1,2,2-Tetrachloroethane UU 1,2,2-T	BLKD2 VBL		h no
Bromomethane Vinyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,2-Dichloroethane 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Ucarbon Tetrachloride Bromodichloromethane 1,2-Dichloropropene Trichloroethene Ucis-1,3-Dichloropropene Trichloroethane Ucis-1,3-Dichloropropene Ucis-1,3-Dichloropropene Ucis-1,3-Dichloropropene Ucis-1,3-Dichloropropene Ucis-1,2-Trichloroethane Ucis-1,2-Trichloroethane Ucis-1,2-Trichloroethane Ucis-1,3-Dichloropropene Ucis-1,2-Trichloroethane Ucis-1,3-Dichloropropene U	1.00 1.	00 Dil	utio
Bromomethane Vinyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,2-Dichloroethane 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropene Trichloroethene U 1,2-Trichloropropene Trichloroethane U 1,1-Trichloropropene U Cis-1,3-Dichloropropene U Trichloroethane U Dibromochloromethane U 1,1,2-Trichloropropene U Trichloroethene U Dibromoform U 4-Methyl-2-Pentanone U 2-Hexanone Tetrachloroethene U 1,1,2,2-Tetrachloroethane U Toluene Chlorobenzene Ethylbenzene Styrene U V V V V V V V V V V V V			
Vinyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene UDibromochloromethane 1,1,2-Trichloroethane UDibromochloromethane UDibromochloromethane UDibromochloromethane UDibromochloromethane UDibromochloromethane UDIBROMOGOME UDIBROMOGO			10
Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,2-Dichloroethane 1,2-Dichloroethane 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane UU Trichloroethene Dibromochloromethane UU Trichloroethene UU Trichloroethene UU Trichloroethene UU Trichloroethene UU Trichloroethane UU UU UU UU UU UU UU UU UU UU UU UU UU			10
Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,2-Dichloroethane 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U U U U U U		200	10
Acetone Carbon Disulfide 1,1-Dichloroethene 1,1-Dichloroethane 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane Cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane U 1,1,2-Trichloroethane U 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U U U U U U	14 4551	100 000	10
Carbon Disulfide 1,1-Dichloroethene 1,1-Dichloroethane 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane Cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U	1	and the second of the second	10
1,1-Dichloroethene 1,1-Dichloroethane 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane Cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene UU Benzene trans-1,3-Dichloropropene UU Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene UU UU UU UU UU UU UU UU UU UU UU UU UU			10
1,1-Dichloroethane 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane Cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U U U U U U	1		10
1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U			10
Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U		100	10
1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene			10
2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U		'	10
1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene			10
Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene			10
Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U U U U U U	'		10
1,2-Dichloropropane Cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U		. 1 '	10
Cis-1,3-Dichloropropene Trichloroethene U Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U U U U U U	ı ,	'	10
Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U	1	- I	10
Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U		· .	10
1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U U U U U U	l '	'	10 10
trans-1,3-Dichloropropene Bromoform U 4-Methyl-2-Pentanone U 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U U U U U U			10
Bromoform 4-Methyl-2-Pentanone U 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U U U U U U	· · · · · · · · · · · · · · · · · · ·		10
4-Methyl-2-Pentanone 2-Hexanone U U 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U U U U U U	· · · · · · · · · · · · · · · · · · ·		10
2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane U Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U U U U U U	1	1	10
Tetrachloroethene 1,1,2,2-Tetrachloroethane U Toluene Chlorobenzene Ethylbenzene Styrene U V V V V V V V V V V V V V V V V V V	•		10
1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U U U U U U		<u>.</u> 1 '	10
Toluene Chlorobenzene Ethylbenzene Styrene U U U U U U U U U U U U U U U U U U			10
Chlorobenzene Ethylbenzene Styrene U			10
Ethylbenzene U U U U U U U U U U U U U U U U U U	1	'	10
Styrene		W NAMES OF	10
Verland /Latal	U	The state of the s	10
Aylene (total)	U		10
		1717	10
Date Received	107/04		
Date Extracted N/A	/07/94 12/08		
Dodge Smaller S	N/A N/ /09/94 12/09	/A	

TABLE VOA-1.2 3094-1368A GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/L.

Client Sample I.D.	Method	PSW-9	PSW-9	
Citent bampie 1.D.	Blank	MS	MSD	
Lab Sample I.D.	VBLKD5	1368031MS	1368031M8D	Quant. Limits
Method Blank I.D.	VBLKD5	VBLKD5	VBLKD5	with no
Dilution Factor	1.00	1.00	1.00	Dilution
Chloromethane				
Bromomethane	U	U	ū	10
Vinyl Chloride	U	a	ט	10
Chloroethane	a a	U	U	10
Methylene Chloride	۵	ט ט	U	10
Acetone	0	l g	ש	10
Carbon Disulfide	ט	ט	<u> </u>	10
1,1-Dichloroethene	Ü	-	Ū	10
1,1-Dichloroethane	ם ם	54X	51X	10
1,2-Dichloroethene (total)	Ü	U U	U	10
Chloroform	n n	9J	U	10
1,2-Dichloroethane	0	95 U	9J	10
2-Butanone	Ü	l ü	Ŭ s	10
1,1,1-Trichloroethane	Ü	Ü	Ü	10
Carbon Tetrachloride	Ü	ט ו	U U	10
Bromodichloromethane	Ü	2J	U	10
1,2-Dichloropropane	Ü	บ	2J	10
cis-1,3-Dichloropropene	Ü	l ü	U U	10
Trichloroethene	Ü	48X		10
Dibromochloromethane	บ	U	44X	10
1,1,2-Trichloroethane	บั	ď	U U	10
Benzene	Ü	50X	46X	10
trans-1,3-Dichloropropene	Ü	บ็	U	10
Bromoform	Ū	ΰ	Ü	10
4-Methyl-2-Pentanone	Ŭ	ΰ	a a	10
2-Hexanone	Ü	ΰ	Ü	10 10
Tetrachloroethene	ט	Ü	ū	10
1,1,2,2-Tetrachloroethane) Ū	l ŭ	u u	10
Toluene	ט	52 X	47X	10
Chlorobenzene	Ū	52X	48X	10
Ethylbenzene	ט ט	U	บ	10
Styrene	Ū	Ü		10
Xylene (total)	U U	<u> </u>	บ	10
Date Received		12/02/04		
Date Extracted	37/3	12/08/94	12/08/94	
Date Analyzed	N/A 12/12/94	N/A	N/A	
	12/12/34	12/12/94	12/12/94	

TABLE VOA-1.1 3094-1368A GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/L.

Client Sample I.D.	Dow 6			
	PSW-6			Ount
Lab Sample I.D.	1368026			Quant. Limits
Method Blank I.D.	VBLKD2			with no
Dilution Factor	1.00			Dilution
Chloromethane	U			
Bromomethane	ŭ	. 19		10
Vinyl Chloride	Ü			10
Chloroethane	U			10
Methylene Chloride	U	5)		10
Acetone Carbon Disulfide	U			10
1,1-Dichloroethene	U			10
1,1-Dichloroethane	U			10
1,2-Dichloroethene (total)	U U	_		10
Chloroform	Ü			10
1,2-Dichloroethane	ŭ			10
2-Butanone	บี	İ		10
1,1,1-Trichloroethane	Ü	1		10
Carbon Tetrachloride	Ū			10
Bromodichloromethane	ט	1]	10
1,2-Dichloropropane	บ			10
cis-1,3-Dichloropropene Trichloroethene	U		i	10
Dibromochloromethane	U		1	10
1,1,2-Trichloroethane	U			10
Benzene	U			10
trans-1,3-Dichloropropene	Ü	<u> </u>	1	10
Bromoform	Ü	5		10
4-Methyl-2-Pentanone	Ü			10
2-Hexanone	Ŭ]	V-	10
Tetrachloroethene	U o			10
1,1,2,2-Tetrachloroethane	U	2.2		10
Toluene	OU			10
Chlorobenzene	U			10
Ethylbenzene	Ŭ			10
Styrene Xylene (total)	Ü		* 2 4 3	10
witche (cocat)	U			10
Date Received	12/08/94			
Date Extracted	N/A			
Date Analyzed	12/09/94	l		1

TABLE VOA-1.3 3094-1368A GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/L.

	1			
Client Sample I.D.	Method Blank	PSW-5	Psw-8	
Ish Sample I D	**********			Quant.
Lab Sample I.D. Method Blank I.D.	VBLKD3	1368022	1368029	Limits
Dilution Factor	VBLKD3	VBLKD3	VBLKD3	with no
	1.00	1.00	1.00	Dilution
Chloromethane	บ	ט	U	10
Bromomethane	ט	Ü	Ŭ	10
Vinyl Chloride	ט	ט	บ	10
Chloroethane	ט	טיי	Ü	10
Methylene Chloride	ט	ט	U	10
Acetone	ט	T .	บ	10
Carbon Disulfide	ט	ט	ซ	10
1,1-Dichloroethene	ט	י איני איני	บ	10
1,1-Dichloroethane	ū	บ	U U	10
1,2-Dichloroethene (total) Chloroform	Ü	ט	U	10
	ū	8J	8J	10
1,2-Dichloroethane 2-Butanone	Ū	U	U	10
1,1,1-Trichloroethane	Ü	Ü	Ŭ	10
Carbon Tetrachloride	ט	ט	ប	10
Bromodichloromethane	ט	บ	ַ	10
1,2-Dichloropropane	ט	מ	2J	10
cis-1,3-Dichloropropene	ซ	Ū	U	10
Trichloroethene	ϋ	U U	U	10
Dibromochloromethane	ט	ט ט	Ŭ	10
1,1,2-Trichloroethane	บ	ซ	Ŭ	10
Benzene	บ	Ü	u u	10
trans-1,3-Dichloropropene	<u>"</u>	บ็	Ü	10
Bromoform	Ŭ	บั	ซ	10
4-Methyl-2-Pentanone	Ŭ	Ü	Ü	10
2-Hexanone	Ŭ	" "	บั	10
Tetrachloroethene	Ü	Ü	ซ	10
1,1,2,2-Tetrachloroethane	Ū	บี	บ	10 10
Toluene	Ū	ט	ซ	10
Chlorobenzene	73.45 U	and U	บั	10
Ethylbenzene	U	Ū	บ	10
Styrene	Ū	्राण वार्	บั	10
Xylene (total)	ט	ט	<u>"</u>	10
Date Received				
Date Extracted	37/3	12/08/94	12/08/94	
Date Analyzed	N/A	N/A	N/A	
	12/09/94	12/10/94	12/10/94	Ī

See Appendix for qualifier definitions
Note: Compound detection limit = quantitation limit x dilution factor

ί.

TABLE VOA-1.4 3094-1368A GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/L.

				<u> </u>
Client Sample I.D.	PSW-9	P8W-10	PSW-12	
Lab Sample I.D.	1368031	1260000	104000	Quant.
Method Blank I.D.	VBLKD3	1368033 VBLKD3	1368035 VBLKD3	Limits
Dilution Factor	1.00	1.00	1.00	with no Dilution
			1.00	Dilucion
Chloromethane	U	Ū	Ū	10
Bromomethane Vinyl Chloride	U	ט	מ	10
Chloroethane	<u>ט</u>	U	ט	10
Methylene Chloride	Ŭ	U	σ	10
Acetone	ָט	Ū	ט	10
Carbon Disulfide	U U	ט	Ū	10
1,1-Dichloroethene	ซ	บ บ	ŭ	10
1,1-Dichloroethane	บ็	ט ט	ט	10
1,2-Dichloroethene (total)	บั	ם ט	ט ט	10
Chloroform	9J	10	8J	10 10
1,2-Dichloroethane	บ	ซ	ŭ	10
2-Butanone	Ū	บั	Ü	10
1,1,1-Trichloroethane	บ	บ	บั	10
Carbon Tetrachloride	Ū	บ	บั	10
Bromodichloromethane	2J	2Ј	2J	10
1,2-Dichloropropane	ן ע	Ū	Ū	10
cis-1,3-Dichloropropene	U	บ	ซ	10
Trichloroethene	U	Ū	U	10
Dibromochloromethane 1,1,2-Trichloroethane	ט ן	U	U	10
Benzene	U	<u>ע</u>	U	10
trans-1,3-Dichloropropene	U U	Ū	Ŭ	10
Bromoform	l ü	U	Ū	10
4-Methyl-2-Pentanone	l ü	U	Ū	10
2-Hexanone	ן ט	ט ט	Ü	10
Tetrachloroethene	Ü	Ü	U U	10
1,1,2,2-Tetrachloroethane	_ Ŭ	Ü	ם	10
Toluene	Ü	Ö	ם ט	10 10
Chlorobenzene	9 0	Ü	Ü	10
Ethylbenzene	Ū	ן ט	Ü	10
Styrene	T U	Ū	บั	10
Xylene (total)	U	Ū	ט	10
Date Received	12/09/04	10/00/04	4 4 4 4 5 4 5 5	
Date Extracted	12/08/94	12/08/94	12/08/94	
Date Analyzed	N/A 12/10/94	N/A 12/10/94	N/A	
]///	12/10/94	12/10/94	

TABLE VOA-1.5 3094-1368A GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/L.

Client Sample I.D.	FB 120794	TB 120794	DUP	
		120/34	DOP	Quant.
Lab Sample I.D. Method Blank I.D.	1368036	1368037	1368038	Limits
Dilution Factor	VBLKD3	ABTKD3	VBLKD3	with no
Dilucion Factor	1.00	1.00	1.00	Dilutio
Chloromethane	ט	ט	***	
Bromomethane	Ŭ	D D	T T	10
Vinyl Chloride	Ŭ	Q.	0	10
Chloroethane	Ŭ	บั	υ	10
Methylene Chloride	บ	Ŭ	บ	10
Acetone	Ū	บั	מ	10
Carbon Disulfide	Ū	บั	ט	10 10
1,1-Dichloroethene	ט	บั	Ü	10
1,1-Dichloroethane	ט	บ	Ü	10
1,2-Dichloroethene (total)	U	Ū	Ü	10
Chloroform	บ	1 J	9J	10
1,2-Dichloroethane	บ	Ū	ซ	10
2-Butanone	U	Ū	Ŭ	10
1,1,1-Trichloroethane	ט	Ū	Ū	10
Carbon Tetrachloride	U	บ	Ū	10
Bromodichloromethane	U	Ū	2Ј	10
1,2-Dichloropropane	U	ប	ט	10
cis-1,3-Dichloropropene Trichloroethene	U	บ	Ū	10
Dibromochloromethane	U	υ	ซ	10
	U	υ	ט	10
1,1,2-Trichloroethane Benzene	U	Ū	Ū	10
trans-1,3-Dichloropropene	U	U	บี	10
Bromoform	Ü	Ū	ט	10
4-Methyl-2-Pentanone	U	U	Ŭ	10
2-Hexanone	Ü	ŭ	ប	10
Tetrachloroethene	U U	<u>ה</u>	ט	10
1,1,2,2-Tetrachloroethane	ซ	U	ט	10
Toluene	ם ט	U 💣 🌯	<u>ש</u>	10
Chlorobenzene	Ü	U U	מ	10
Ethylbenzene	ď	Ü	a A sage	-10
Styrene	Ū	ם ט	Ū	10
Xylene (total)	<u>U</u>	ŋ.	יים אינים יים	10 10
Date Received	10/00/0			10
Date Extracted	12/08/94	12/08/94	12/08/94	
Date Analyzed	N/A	N/A	N/A	
	12/09/94	12/09/94	12/10/94	

TABLE VOA-1.6 3094-1368A GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/Kg dry weight basis.

	7	15		
Client Sample I.D.	Method Blank	P88-5	P65-7	
Lab Sample I.D. Method Blank I.D.	VBLKB7	1368023	1368025	Quant. Limits
Dilution Factor	VBLKB7	VBLKB7 1.30	VBLKB7	with no Dilution
Chloromethane	0.5J	U	U	
Bromomethane	U	υŭ	บั	10 10
Vinyl Chloride Chloroethane	Ū	Ū	Ü	10
	U	U	Ū	
Methylene Chloride Acetone	Ū	2Ј	U	10 10
Carbon Disulfide	25	30B	17B	10
1,1-Dichloroethene	ט	4 J	U	10
1,1-Dichloroethane	U	ן ט	Ü	10
1,2-Dichloroethene (total)	Ü	U	U	10
Chloroform (total)	la ca U	U	U	10
1,2-Dichloroethane	ŭ	U	Ū	10
2-Butanone	us, u	U	Ū	10
1,1,1-Trichloroethane	Ū	ט	Ū	10
Carbon Tetrachloride	U	U	Ū	10
Bromodichloromethane	U	U	ט	10
1,2-Dichloropropane	U	U	. ס	10
cis-1,3-Dichloropropene	l ü	U	ט	10
Trichloroethene	a a	U	ט	10
Dibromochloromethane	l ü	U	ט	10
1,1,2-Trichloroethane	u u	U	ט	10
Benzene	Ü	U	ט	10
trans-1,3-Dichloropropene	a d	ŭ	U	10
Bromoform	ŭ	Ü	<u>ט</u>	10
4-Methyl-2-Pentanone	Ü	U	U	10
2-Hexanone	Ü	U	Ü	10
Tetrachloroethene	Ü	U	ָ טַ	10
1,1,2,2-Tetrachloroethane	Ü	0	Ū	10
roluene	U	ט	U	10
Chlorobenzene	Ü	ט	*0.4 # 0 1000.4	10
Ethylbenzene	Ü	п	ט	10
Styrene	Ŭ	Ü	U U	10
Kylene (total)	U	Ŭ Ü	U U	10 = 10
Date Received		12/08/94	12/08/94	
Date Extracted	N/A	N/A		
Date Analyzed	12/09/94	12/09/94	N/A 12/09/94	

TABLE VOA-1.7 3094-1368A GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/Kg dry weight basis.

		1		
Client Sample I.D.	P88-6	Dag. e	200	
	FB50	P88-8	P88-9	0
Lab Sample I.D.	1368027	1368028	1368030	Quant. Limits
Method Blank I.D.	VBLKB7	VBLKB7	VBLKB7	with no
Dilution Factor	1.39	6.25	2.13	Dilution
Chloromethane	ט	U		/
Bromomethane	Ü	U	Ū	10
Vinyl Chloride	Ü	D D	U U	10
Chloroethane	U	NAME OF THE PARTY	ŭ	10
Methylene Chloride	2J	U	3 J	10 10
Acetone	28B	110B	41B	10
Carbon Disulfide	U	14J	บั	10
1,1-Dichloroethene	ט	U	Ŭ : B	10
1,1-Dichloroethane	Ū	σ	U	10
1,2-Dichloroethene (total) Chloroform	U	ט	U and in	10
1,2-Dichloroethane	Ū	ט	U	10
2-Butanone	ā	U	U	10
1,1,1-Trichloroethane	ט ט	22J	7J	10
Carbon Tetrachloride	ט	ם .	<u> </u>	10
Bromodichloromethane	ם	ט	ŭ	10
1,2-Dichloropropane	ם	a a	ŭ	10
cis-1,3-Dichloropropene	ŭ	D O	U U	10
Trichloroethene	บี	Ü	ט	10
Dibromochloromethane	บ	Ü	Ü	10
1,1,2-Trichloroethane	บ	Ü	บ็	10 10
Benzene	U	Ū	Ŭ	10
trans-1,3-Dichloropropene	U	Ū	บั	10
Bromoform	ซ	U	Ü	10
4-Methyl-2-Pentanone	ט	U	U	10
2-Hexanone Tetrachloroethene	υ	ט	บ	10
	ט	υ	ן ע	10
1,1,2,2-Tetrachloroethane Toluene	ū	U	υ	10
Chlorobenzene	Ū	Ū	Ū	10
Ethylbenzene	ָ ס	a	U	10
Styrene	17 11 2 3	U	Ū	10
Xylene (total)	ט יייי די	U U	U	10
		†	<u> </u>	10
Date Received	12/08/94	12/08/94	12/08/94	1
Date Extracted Date Analyzed	N/A	N/A	N/A	
bace Analyzed	12/09/94	12/09/94	12/09/94	

TABLE VOA-1.8 3094-1368A GERAGHTY & MILLER EPA TCL VOLATILES

All values are ug/Kg dry weight basis.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	P88-10 1368032 VBLKB7 1.32	PSS-12 1368034 VBLKB7 2.70	Quant. Limits with no Dilution
Chloromethane Bromomethane Vinyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane Benzene trans-1,3-Dichloropropene Bromoform 4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane Toluene Chlorobenzene Ethylbenzene Styrene Xylene (total)	מממממממממממממממממממממממממממממממממממממממ	ם מם מם מ מ מ ט מ ט מ מ מ מ ט ט ט ט מ ט ט ט ט	10 10 10 10 10 10 10 10 10 10 10 10 10 1
Date Received Date Extracted Date Analyzed	12/08/94 N/A 12/09/94	12/08/94 N/A 12/09/94	

TABLE VO-2.0 3094-1368A GERAGHTY & MILLER VOLATILE TENTATIVELY IDENTIFIED COMPOUNDS

Sample Identification: Method Blank VBLKD2

CAS#	Estimated Compound RT Concentration, ug/L
	None detected
	Sample Identification: FB 120694
CAS#	Estimated Compound RT Concentration, ug/L
	None detected
	Sample Identification: PSW-7
CAS#	Estimated Compound RT Concentration, ug/L
	None detected
	Sample Identification: PSW-6
CAS#	Estimated Compound RT Concentration, ug/L
	None detected
	Sample Identification: Method Blank VBLKD5
CAS#	Estimated Compound RT Concentration, ug/L
	None detected
	Sample Identification: Method Blank VBLKD3
CAS#	Estimated Compound RT Concentration, ug/L
	None detected

TABLE VO-2.1 3094-1368A GERAGHTY & MILLER VOLATILE TENTATIVELY IDENTIFIED COMPOUNDS

Sample Identification: PSW-5

CAS#	Compound	RT	Estimated Concentration, ug/L
	None detected		
	Sample Identification:	PSW-8	Fall of A
CAS#	Compound	RT	Estimated Concentration, ug/L
	oompound		concentration, ug/L
	None detected		
	Sample Identification:	PSW-9	
CAS#	Compound	RT	Estimated Concentration, ug/L
	Unknown alkane	22.17	150J
124185	Decane	20.62	90JN
6975980	Decane,2-methyl-	21.66	72JN
	Unknown branched alkane	21.03	43J
	Unknown	22.38	37J
	Unknown branched cycloalkane	21.40	24J
	Unknown branched alkane Unknown	21.78	24J
	Unknown alkane	21.99 22.86	22J
	Unknown branched alkane	22.53	20J
	onknown bi unched atkane	22.53	15J
	Sample Identification:	PSW-10	
CAS#	Compound	RT	Estimated Concentration, ug/L
	None detected		

TABLE VO-2.2 3094-1368A GERAGHTY & MILLER VOLATILE TENTATIVELY IDENTIFIED COMPOUNDS

Sample Identification: PSW-12

CAS#	Compound RT None detected	Estimated Concentration, ug/L
	Sample Identification: FB 120794	
CAS#	CompoundRT	Estimated Concentration, ug/L
	None detected	
	Sample Identification: TB 120794	
CAS#	CompoundRT	Estimated Concentration, ug/L
	None detected	
	Sample Identification: DUP	
CAS#	Compound RT	Estimated Concentration, ug/L
	None detected	
	Sample Identification: Method Blank VE	DLKB7
CAS#	Compound RT_	Estimated Concentration, ug/Kg
	None detected	

TABLE VO-2.3 3094-1368A GERAGHTY & MILLER VOLATILE TENTATIVELY IDENTIFIED COMPOUNDS

Sample Identification: PSS-5

CAS#	Compound	RT	Estimated Concentration, ug/Kg
	Unknown siloxane Unknown Unknown Unknown Unknown Unknown Unknown Unknown Unknown Unknown Unknown Unknown	25.93 25.02 25.30 25.57 25.77 26.18 24.44 23.64 23.12 26.35	120J 59J 56J 39J 36J 32J 30J 29J 29J 29J
	Sample Identification:	PSS-7	
CAS#	Compound	RT	Estimated Concentration, ug/Kg
	Unknown	24.88	21J
	Sample Identification:	PSS-6	
CAS#	Compound	RT	Estimated Concentration, ug/Kg
	Unknown Unknown siloxane	24.91 25.85	13J 11J
	Sample Identification:	PSS-8	
CAS#	Compound	RT	Estimated Concentration, ug/Kg
556672	Unknown siloxane Unknown Cyclotetrasiloxane,octamethyl Unknown Unknown branched cycloalkane	25.91 24.98 23.04 25.33 25.61	110J 85J 66JN 63J 58J

TABLE AS-1.0 3094-1368A GERAGHTY & MILLER EPA TAL METALS

All values are ug/L.

I			
PSW-5	PSW-7	PSW-6	PSW-8
100000			
1368022	1368024	1368026	1368029
299	469	102 D	200
.			290.
			38.0U
			1.00
			31.0B
			1.00
			2.0U 43200
			2.0U
			3.0U
			10.2B
			10.00
			97.5B
			19.8
	1		8010
			15.7
			0.200
			23.6B
			1840B
		1	1.0U
		•	3.0U
			43800
			1.00
			6.00
			48.2
	PSW-5 1368022 299. 38.0U 1.0U 31.9B 1.0U 2.0U 42500 2.0U 3.0U 16.1B 10.0U 93.1B 22.7 7810 14.2B 0.20U 8.0U 1500B 1.0U 3.0U 44200 1.0U 7.7B 57.4	1368022 1368024 299. 468. 38.0U 38.0U 1.0U 1.0U 31.9B 58.2B 1.0U 2.0U 2.0U 42500 82000 2.0U 2.0U 3.0U 16.1B 7.4B 10.0U 10.0U 93.1B 99.9B 22.7 39.7S 7810 3360B 14.2B 26.1 0.20U 8.0U 8.0U 1500B 6410 1.0U 3.0U 3.0U 44200 18800 1.0U 7.7B 6.0U	1368022 1368024 1368026

TABLE AS-1.1 3094-1368A GERAGHTY & MILLER EPA TAL METALS

All values are ug/L.

Client Sample I.D. Lab Sample I.D.	PSW-9 1368031	PSW-9 D 1368031D	PSW-9 S 1368031S	PSW-10 1368033
Aluminum Antimony Arsenic Barium Beryllium Cadmium Calcium Chromium Cobalt Copper Cyanide Iron Lead Magnesium Manganese Mercury Nickel Potassium Selenium	198.B	172.B	2030	200.
	38.0U	38.0U	435.	38.0U
	1.0U	1.0U	41.8	1.0U
	24.3B	23.8B	1870	28.6B
	1.0U	1.0U	46.0	1.0U
	2.0U	2.0U	50.2	2.0U
	30300	29200	NR	37800
	2.0U	2.0U	189.	2.0U
	3.0U	3.0U	460.	3.0U
	5.7B	2.1B	248.	2.4B
	10.0U	10.0U	96.2	10.0U
	117.	127.	1040	130.
	22.9	23.0	43.6	22.4
	6060	5880	NR	7560
	6.8B	6.3B	462.	10.7B
	0.20U	0.20U	0.92B	0.20U
	8.0U	8.0U	444.	8.0U
	856.B	987.B	NR	1540B
	1.0U	1.0U	10.0	1.0U
	3.0U	3.0U	47.6	3.0U
Sodium Thallium Vanadium Zinc	26300	25500	NR	43300
	1.0U	1.0U	47.7	1.0U
	6.0U	6.0U	464.	6.0U
	54.1	54.4	504.	59.8

TABLE VO-2.4 3094-1368A GERAGHTY & MILLER YOLATILE TENTATIVELY IDENTIFIED COMPOUNDS

Sample Identification: PSS-8 (continued)

CAS#	Compound	RT	Estimated Concentration, ug/Kg
	Unknown Unknown Unknown Unknown	25.75 26.30 24.40 24.04	49J 41J 37J 35J
	Sample Identification:	PSS-9	
CAS#	Compound	RT	Estimated Concentration, ug/Kg
	Unknown Unknown Unknown Unknown Unknown Unknown Unknown Unknown Unknown Unknown Unknown Unknown Unknown Unknown Unknown Unknown	26.29 25.71 25.91 24.58 23.56 24.00 24.36 25.33 26.13 25.41	180J 170J 110J 100J 97J 97J 92J 89J 71J 61J
	Sample Identification:	PSS-10	Estimated
CAS#	Compound	RT	Concentration, ug/Kg
	Unknown alkane	25.01	13J
	Sample Identification:	PSS-12	
CAS#	Compound	RT	Estimated Concentration, ug/Kg
	None detected		

TABLE AS-1.2 3094-1368A GERAGHTY & MILLER EPA TAL METALS

All values are ug/L.

				
Client Sample I.D.	PSW-12	Diin		
Client Sample 1.D.	P5W-12	DUP		
Lab Sample I.D.	1368035	1368038		
Aluminum	405.	493.		
Antimony	38.00	38.00		
Arsenic	1.1B	1.6B		
Barium	38.6B	45.8B		
Beryllium	1.00	1.00		
Cadmium	2.00	2.00		
Calcium	52200	62200		
Chromium	2.0U	2.00		
Cobalt	3.0U	3.0T		
Copper	3.6B	4.8B	,	
Cyanide	10.0U	10.0U		
Iron	148.	143.		
Lead	47.9S	30.8		
Magnesium	9470	11200		
Manganese	15.6	18.1		
Mercury	0.20ប	0.200		
Nickel	8.0U	8.00		
Potassium	2050B	2600B	ļ	
Selenium	1.00	1.00		
Silver	34.5	3.00		
Sodium	52600	61400	ŀ	
Thallium	1.00	1.00		
Vanadium	6.0T	6.0 U		
Zinc	70.1	122.		

TABLE AS-1.3 3094-1368A GERAGHTY & MILLER EPA TAL METALS

All values are mg/Kg dry weight basis.

	Y	·		
Client Sample I.D.	PSS-5	PSS-7	PSS-6	PSS-8
Lab Sample I.D.	1368023	1368025	1368027	1368028
Aluminum Antimony	7200*	4760*	6860*	10100*
Arsenic	11.6UN 1.6B	11.6UN 0.40B	10.2UN 3.2	43.9UN
Barium	56.7B	109.	50.7B	5.2B 61.2B
Beryllium Cadmium	0.300	0.300	0.51B	1.2U
Calcium	2.1 5610	0.61U 5930	0.54U 4160	2.3U 50500
Chromium	6.0	4.0	13.5	14.2
Cobalt Copper	3.5B 36.4E	4.6B 6.9BE	5.8B	9.2B
Cyanide	0.740	0.72T	3.4BE 0.64U	76.0E 2.8U
Iron Lead	2260	563.	16100	5500
Magnesium	5110 1160B	639. 272.B	51.9 2380	1560 3460B
Manganese	36.3	11.1	315.	73.4
Mercury Nickel	0.24 7.0B	0.14 2.4U	0.12U	0.62
Potassium	919.B	873.B	5.8B 651.B	9.2U 1430B
Selenium Silver	0.64B	0.300	0.27T	1.5B
Sodium	9.1 1800	1.5B 1790	0.81U 86.6B	4.6B 1960B
Thallium	0.300	0.300	0.27U	1.20
Vanadium Zinc	11.1B 260.*	2.6B	20.1	8.9B
	200.	328.*	57.1*	708.*

TABLE AS-1.4 3094-1368A GERAGHTY & MILLER EPA TAL METALS

All values are mg/Kg dry weight basis.

	<u> </u>			
Client Sample I.D.	PSS-9	PSS-10	PSS-12	
			1	
Lab Sample I.D.	1368030	1368032	1368034	
Aluminum	12700*	00704		
Antimony	13.2UN	9270*	15500*	
Arsenic	2.8B	18.6UN	23.2UN	
Barium	113.	3.2B	7.5	
Beryllium	0.45B	64.1B	89.8B	
Cadmium		0.57B	0.61U	
Calcium	1.2B	0.980	1.20	
Chromium	35900	124000	8330	
Cobalt	18.3	11.0	28.6	
Copper	12.1B	5.0B	10.1B	1
Cyanide	31.7E	11.1BE	154.E	
Iron	0.860	1.20	2.3	1
Lead	6520	6330	4900	
	3280	668.	3740	1
Magnesium	10300	. 17200	2470B	1
Manganese	176.	189.	61.2	
Mercury	0.31	0.200	1.1	ļ
Nickel	7.4B	3.9T	39.4	1
Potassium	1830	1650B	1540B	
Selenium	0.35ซ	0.49U	2.0B	
Silver	3.2B	1.5U	31.8	1
Sodium	2540	1940B	2640B	1
Thallium	0.35ប	0.49U	0.61U	
Vanadium	16.5B	23.3B	22.6B	
Zinc	329.*	130.*	746.*	

4

TABLE AS-1.0 3095-1154 GERAGHTY & MILLER EPA TAL METALS (Total)

Agueous August 1995

All values are ug/L.

Client Sample I.D. Lab Sample I.D.	MW-1 1154001	MW-2 1154002	MW-3 1154003	MW-4 1154004
Aluminum	1770	4680	51400	1790
Antimony	33.00	33.00	34.9B	33.00
Arsenic	3.00	6.3B	107.	3.00
Barium	49.9B	55.4B	403.	40.3B
Beryllium	1.00	1.00	5.1	1.00 3.00
Cadmium	3.0℧	3.00	3.00	3.00
Calcium	150000	450000	656000	390000
Chromium	5.2B	7.5B	67.4	3.8B
Cobalt	4.3B	6.4B	47.4B	4.7B
Copper	18.0B	27.6	124.	14.9B
Cyanide	NR	NR	NR.	NR
Iron	3350	10900	126000	3000
Lead .	4.4	8.9	213.	6.6
Magnesium	41500E	70400E	207000E	24300E
Manganese	123.	1510	3470	5720
Mercury	0.200	0.200	0.200	0.200
Nickel	7.00	12.5B	91.1	10.0B
Potassium	1830E	3520E	8560E	4270E
Selenium	5.0B	2.00	5.8	2.00
Silver	2.5B	2.00	2.00	2.00
Sodium	14900E	51600E	43500E	40400R
Thallium	4.00	4.0U	4.00	4.00
Vanadium	1.6B	16.1B	93.0	1.00
Zinc	73.9	85.1	261.	_53.5

TABLE AS-1.1 3095-1154 GERAGHTY & MILLER EPA TAL METALS (Total)

All values are ug/L.

· · · · · · · · · · · · · · · · · · ·					
023	2	=			
Client Samp	ole I.D.	MW-5	MW - 6	MW-7	MW-41
Lab Sample	I.D.	1154005	1154006	1154007	1154008
Aluminum		622.	41600	7500	55400
Antimony	(2000) 1 (2000) 447 (2005) 1 44 (3) 1 1	33.00	33.00	33.00	49.7B
Arsenic	J-18-21-X-21-103-22-X	7.0B	27.6	15.6	41/3
Barium	and the programmer of the control of	45.8B	545.	89.6B	590.
Beryllium		1.00	5.4	1.5B	6.6
Cadmium	1 and 15 and 1 and 1 and 1 and 1	3.0℧	3.00	3.00	3.00
Calcium		88400	477000	299000	792000
Chromium		3.00	76.4	13.3	132.
Cobalt		3.00	60.2	12.3B	61/2
Copper	1.1 Z	7.1B	276.	38.8	236.
Cyanide		NR	NR	NR	NR
Iron		1890	85100	17800	117000
Lead		3.4	56.5	292.	99.1
Magnesium	1000 1000 3000 3000 1000 1000 1000 1000	29400E	158000E	53400E	174000E
Manganese		30.9	2790	1450	4570
Mercury		0.200	0.20B	0.200	0.200
Nickel		7.00	106,	21.2B	155.
Potassium		9010E	10100E	5970E	19400E
Selenium		2.00	6.0	3.3B	5.5
Silver		2.00	41.8	2.00	2.00
Sodium		68000E	19300E	38300E	30700E
Thallium		4.0U	4.0U	4.00	4.0U
Vanadium		2.3B	56.9	18.9B	96.7
Zinc	a#11	62.1	342.	75.7	419.



TABLE AS-1.2 3095-1154 GERAGHTY & MILLER EPA TAL METALS (Total)

Agueous August 1995

All values are ug/L.

Client Sampl	e I.D.	REP-1	SW-1	SW-1 D	SW-1 S
Lab Sample I	.D.	1154009	1154010	1154010D	1154010s
Aluminum		46600	129.B	124.B	1930
Antimony		33.00	33.00	33.OU	446.
Arsenic		35.6	3.00 €	3.00	1940
Barium	1111	541.	36.2B	36:2B	1770
Beryllium		7.2	1.00	1.00	42.5
Cadmium	ž = 2	3.00	3.00	3.00	42.2
Calcium		518000	63100	62500	NR
Chromium		87.6	3.00	3.00	173.
Cobalt		63.0	3.00	3.00	424.
Copper		260.	15.7B	8.6B	221.
yanide		NR	10.00	10.00	99.3
ron		95500	269.	267.	1150
ead		56.9	51.3	51.0	543.
Magnesium		179000E	9320E	9250	NR
langanese		3080	19.9	17.2	441.
lercury	DOMESTIC CONTROL OF THE PARTY O	0.200	0.200	0.200	1.2B
lickel		119.	7.00	7.00	425.
otassium	TIME STORES OF COMME	10100E	2050E	2070	NR
elenium		6.9	2.00	2.5B	1860
ilver		4.0B	2.7B	2.5B	44.2
odium		21700E	22100E	22000	NR
'hallium		4.00	4.0U	4.00	2040
/anadium		58.1	7.1B	7.5B	428.
Zinc	= =	342.	39.6	36.0	445.

Agueous Agust 1995

TABLE AS-1.3 3095-1154 GERAGHTY & MILLER EPA TAL METALS (Total)

All values are ug/L.

Client Sam Lab Sample	The season of th	SW-2 1154012	SW-2A 1154014	SW-3 1154016	SW-4 1154018
Aluminum		173.B	NR	139,B	533.
Antimony Arsenic		33.0U 3.0U	NR NR	33.00 3.00	33.00
Barium		33.2B	NR	38.6B	6.4B 52.0B
Beryllium	To result of	1.00	NR	1.00	1.00
Cadmium		3.00	NR	3.00	3.00
Calcium		36200	NR	37000	39100
Chromium	1.600	3.00	NR	3.00	4.2B
Cobalt	Turbill & Millione Cont.	3.00	NR	3.00	3.00
Copper	THE SECOND SECTION AND ADDRESS OF THE PERSON ADDRESS OF THE PERSON AND ADDRESS OF THE PERSON ADDRESS OF THE PERSON ADDRESS OF THE PERSON ADDRESS OF THE PERSON ADDRESS OF THE PERSON ADDRESS OF THE PERSON ADDRESS OF THE PERSON A	12.8B	NR	6.5B	9.0B
yanide		10.00	NR	10.00	10.00
ron		301.	NR	194.	2360
Lead		79.9	2100	41.3	315.
Magnesium		7190E	NR	7850E	8130E
Manganese		18.3	NR	18.9	259.
Mercury	This is the same of the same o	0.200	NR	0.200	0.200
Nickel		7.00	NR	7.00	7.00
Potassium	2C	1670E	NR	1730E	2140E
Selenium		2.00	NR	2.00	2.00
Silver		2.00	NR	2.00	2.3B
Sodium		19300E	NR	19200B	19600E
Thallium	Color Statement Color Service Address	4.00	NR	4.0页	4.0U
Vanadium		3.1B	NR	2.4B	1.8B
Zinc		23.3	NR	18,6B	52.4

8

TABLE AS-1.4 3095-1154 GERAGHTY & MILLER EPA TAL METALS (Total)

Aqueous August 1995

All values are ug/L.

Client Samp	le I.D.	SW-4A					
ab Sample	I.D.	1154020					
luminum		NR	100 AV				
Intimony Arsenic		NR NR	ğ. 200		37.60.207.3367.5		
Barium Beryllium		NR NR		**************************************		**	
ladmium Lalcium Lhromium		NR NR NR	á. p				
obalt opper		NR NR NR					
yanide ron		NR NR					
ead agnesium		103. NR	V Tale	- 120 X			
anganese ercury		NR NR				3.11	
ickel otassium		NR NR					- 4 }
elenium ilver		NR NR					
odium hallium		NR NR			Ţ.		
anadium Linc		NR NR					

TABLE AS-1.5 3095-1154 GERAGHTY & MILLER EPA TAL METALS

5011 August 1995

All values are mg/Kg dry weight basis.

Client Sample I.D. Lab Sample I.D.	SED-1 1154011	SED-1 D 1154011D	SED-1 S 1154011S	SED-2 1154013
Aluminum Antimony Arsenic Barium Beryllium Cadmium Calcium Chromium Cobalt Copper Cyanide Iron Lead Magnesium	10500	10900	17100	11600
	2.4UN	2.5U	188.N	4.2BN
	44.3	35.3	1600	64.1
	86.4B	86.1B	1690	148.B
	0.81U	1.5B	39.9	1.1U
	2.5B	3.2B	43.5	3.2B
	33000	30200	NR	10900
	32.1	30.4	187.	29.8
	4.6B	5.2B	392.	4.6B
	80.4	81.2	277.	64.8
	2.2UN	2.2U	4.5N	2.8UN
	25700	24300	22500	26500
	3380	3480	3810	4840
	5060	4770	NR	2860
Manganese	158.	147.	3.2N	86.6
Mercury	0.37UN	0.51	3.2N	0.54UN
Nickel	14.2B	15.9B	419.	13.0B
Potassium	853.	952.	NR	685.B
Selenium	4.4	5.1	1490	5.8
Silver	4.1B	4.2B	42.8	5.1B
Sodium	1120	1180	NR	1010B
Thallium	3.2U	3.3U	1640	4.3U
Vanadium	48.1	46.4	436.	44.6B
Zinc -	599.N	580.	926.N	796.N

TABLE AS-1.6 3095-1154 GERAGHTY & MILLER EPA TAL METALS

Soil August 1995

All values are mg/Kg dry weight basis.

Client Sample I.D.		SED-2A 1154015	SED-3 1154017	SED-4 1154019	
Aluminum	14.45	NR	11800	8080	
Antimony	0.00000 (0.000) (1.000)	NR	4.3UN	6.3UN	
Arsenic		NR	48.3	41.1	
Barium		NR	135.B	128.B	G (4-1885)EU
Beryllium		NR	1.40	2.10	
Cadmium		NR	3.6B	3.7B	
Calcium		NR	12900	9950	
Chromium		NR	32.0	20.6B	Server and Apple Stories
Cobalt		NR	5.1B	3.8B	
Copper		NR	88.0	57.6	CANTAGE CANADA TO THE COURT
Cyanide		NR	3.9UN	5.1UN	
Iron		NR	27300	17600	Transaction of
Lead `.		2020	4510	3720	
Magnesium		NR	2110	1690B	wasta ta
Manganese		NR	166.	1540	\$2.60.60
Mercury		NR	0.75UN	1.0UN	COMMON CASCODE
Nickel		NR	15.5B	19.0B	
Potassium		NR	900.B	519.B	690.0000.00857557
Selenium		NR	4.4B	6.8B	
Silver		NR NR	4.9B 1380B	2.1T 949.B	770000000000000000000000000000000000000
Sodium			5.7U		
Thallium		NR	41.3B	8.4U 45.2B	WWW.
Vanadium		NR NR	722.N	775.N	

11

TABLE AS-2.0 3095-1154 GERAGHTY & MILLER EPA TAL METALS (Dissolved)

Aqueous August 1995

All values are ug/L.

Client Sample I.D.	MW-1	MW-2	MM-3	MW-4
Lab Sample I.D.	1154001	1154002	1154003	1154004
Aluminum	2480	5050	2370	656.
Antimony	5.5B	5.1B	4.0B	3.00
Arsenic	3.00	3.00 ,	3.7B	3.00
Barium	46.2B	45.6B	45.4B	24.0B
Beryllium	1.00	1.00	1.00	1.00
Cadmium	1.00	1.00	1.00	1.00
Calcium	136000E	380000E	157000E	3690008
Chromium	4.0B	6.3B	3.7B	1.9B
Cobalt	3,00	3.00	3.00	3.00
Copper	2.00	3.8B	2.00	2.00
Iron	1910	3940	2190	590.
Lead	3.1	3.5	5.7	2.8B
Magnesium .	35600	54000	43500	24000
Manganese	30.1	278.	472.	2020
Mercury	0.200	0.200	0.200	0.200
Nickel	3.7B	10.2B	5.4B	5.5B
Potassium	2100E	5930E	2180E	5110E
Selenium	4.1B	2.00	2.5B	2.00
Silver	1.00	1.00	1.00	1.00
Sodium	14700	48300	33400	38700
Challium	4.00	4.00	4.00	4.00
Vanadium	1.00	11.5B	8.5B	1.00
Zinc	18.8B	16.1B	14.9B	23.8

TABLE AS-2.1 3095-1154 GERAGHTY & MILLER EPA TAL METALS (Dissolved)

Aqueous August 1995

All values are ug/L.

Client Sample I.D.	MW - 5	MW - 6	MW-7	MW-4I
Lab Sample I.D.	1154005	1154006	1154007	1154008
Aluminum	575.	3040	3130	6460
Antimony	5.3B	4.0B	5.2B	5.0B
Arsenic	3.00	3.00	3.00	3.00
Barium	43.1B	93.4B	46.6B	58.4B
Beryllium	1.00	1.00	1.00	1.3B
Cadmium	1.00	1.00	1.00	1.00
Calcium	87800E	92200E	185000E	400000E
Chromium	1.9B	4.7B	4.8B	9.3B
Cobalt	3.00	3.00	3.00	3.00
Copper	2.00	2.00	2.00	2.7B
Iron	627.	2090	2340	5200
Lead	3.9	3.6	34.2	4.7
Magnesium (29900	20500	11800	48700
Manganese	12.6B	121.	864.	1150
Mercury	0.200	0.200	0.200	0.200
Nickel	2.7B	5.0B	6.3B	13.6B
Potassium	11300E	2660E	6570E	19700E
Selenium	2.00	2.00	2.00	2.00
Silver	1.00	1.00	1.00	1.00
Sodium	62500	17400	34100	26800
Thallium	4.00	4.00	4.00	4.00
Vanadium	3.3B	3.0B	8.3B	15.3B
Zinc	26.5	56.6	54.9	36.8

TABLE AS-2.2 3095-1154 GERAGHTY & MILLER EPA TAL METALS (Dissolved)

All values are ug/L.

Client Sample I.D.	REP-1 1154009	
Aluminum Antimony Arsenic Barium Beryllium Cadmium Calcium Chromium Cobalt Copper Iron Lead Magnesium Manganese Mercury Nickel Potassium	4320 3.9B 3.0U 111.B 1.2B 1.0U 90000E 6.2B 3.0U 2.0U 2.950 3.2 23400 152. 0.20U 7.6B 3480E	
Selenium Silver Sodium Thallium Vanadium Zinc	2.00 1.00 15200 4.00 3.78 15.08	

TABLE VO-1.0 3095-0018 GERAGHTY & MILLER EPA TCL VOLATILE ORGANICS

All values are ug/L.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	Method Blank VBLKDC VBLKDC 1.00	MW-6 0018001 VBLKDC 1.00	MW-1 0018002 VBLKDC 1.00	Quant. Limits with no Dilution
Chloromethane	U	U	ס	10
Bromomethane Vinyl Chloride	D D	ğ	ū	10
Chloroethane	Ü	יייי ס	U U	10 10
Methylene Chloride	Ū	U	ט	10
Acetone Carbon Disulfide	The second	, , , , , , , , , , , , , , , , , , ,	ū	10
1,1-Dichloroethene	ט	Ü	0	10
1,1-Dichloroethane	Ū	Ū	ָ ט	10 10
1,2-Dichloroethene (total)	U U	U U	U U	10
1,2-Dichloroethane 2-Butanone	ט	0	Ŭ	10
1,1,1-Trichloroethane	Ŭ	U	Ď	10 10
Bromodichloromethane	ָ ס	0	0	10 10
1,2-Dichloropropane cis-1,3-Dichloropropene	U U	U U	0	10
Trichloroethene	Ŭ	Ü	Ū	10 10
Dibromochloromethane 1,1,2-Trichloroethane	ט ט	ū	0	10
Benzene	5	U U	0	10 10
trans-1,3-Dichloropropene Bromoform	U	ŭ	U	10
4-Methyl-2-Pentanone	U	U U	U U	10 10
2-Hexanone	U	. "U	บ	10
Tetrachloroethene 1,1,2,2-Tetrachloroethane	ŭ	Ū	Ū	10
roluene	U	0	U U	10
Chlorobenzene	U U	ale de un m	Ü	10
Ethylbensene	, U	Ū	Ū	10
Styrene Xylene (total)	U	1J	U	10 10
Date Received	X10000005	01/06/95	01/06/95	
Date Extracted Date Analyzed	N/A 01/09/95	N/A 01/09/95	N/A 01/09/95	

TABLE VO-1.1 3095-0018 GERAGHTY & MILLER EPA TCL VOLATILE ORGANICS

All values are ug/L.

Chloromethane Bromomethane Vinyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethane 1,1-Dichloroethane 1,2-Dichloroethane 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene Trichloroethane	บ		1.00	with no Dilution
Vinyl Chloride Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethane 1,2-Dichloroethane 1,2-Dichloroethane 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene		מ	U	10
Chloroethane Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethane 1,1-Dichloroethane 1,2-Dichloroethane (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene	a	v v	"ס"	10
Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene 1,1-Dichloroethene 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene	ט	ט	Ū	10
Acetone Carbon Disulfide 1,1-Dichloroethene 1,1-Dichloroethene 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene	ט	. ע	ט	10
Carbon Disulfide 1,1-Dichloroethene 1,1-Dichloroethane 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene	U	U	ס	10
1,1-Dichloroethene 1,1-Dichloroethene 1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene	U	U	Ū	10
1,1-Dichloroethane 1,2-Dichloroethane (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene	U	Ū	2J	10
1,2-Dichloroethene (total) Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene	56X	53X	56X	10
Chloroform 1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene	D D	ט ט	Ū	10
1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene	Ū	U	U	10
2-Butanone 1,1,1-Trichloroethane Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene	Ū	Ü	U	10 10
Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene	Ū	ซ		10
Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene	י שיי ס	Ū	U	îo
1,2-Dichloropropane cis-1,3-Dichloropropene	ש	U	Ū	10
cis-1,3-Dichloropropene	ס	U	ט	10
Trichloroethan	ū	U	Ū	10
	U	U	Ū	10
Dibromochloromethane	49X	48X	52X	10
1,1,2-Trichloroethane	U	U	T T	10
Benzene	51X	50X	U 55X	10
trans-1,3-Dichloropropene	ט	บิ	U	10 10
Bromoform	U	Ū	U U	10
4-Methyl-2-Pentanone	Ū	Ū	Ü	10
2-Hexanone	U	U		10
Tetrachloroethene	ט	ס	Ū	10
1,1,2,2-Tetrachloroethane	U	U	U	10
Toluene Chlorobenzene	51X	50X	54X	10
Ethylbenzene	51X	51X	53X	10
The state of the s	U	U	ש	10
Xylene (total)	U	U U	U	10 10
Date Received	W-22-204 - 2-0-0			10
Date Extracted	01/06/95	01/06/95	01/06/95	1
Date Analyzed	N/A 01/10/95	N/A 01/09/95	N/A 01/10/95	l.

TABLE VO-1.2 3095-0018 GERAGHTY & MILLER EPA TCL VOLATILE ORGANICS

All values are ug/L.

		0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0 0 0	10
		0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0	10 10 10 10 10 10 10 10 10 10 10 10 10
		0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0 0	10 10 10 10 10 10 10 10 10 10 10 10 10
000000000000000000000000000000000000000		0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0	10 10 10 10 10 10 10 10 10 10 10
0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		0 0 0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0 0	10 10 10 10 10 10 10 10 10 10 10
0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		0 0 0 0 0 0 0 0 0 0	0 0 0 0 0 0 0	10 10 10 10 10 10 10 10 10
0 0 0 0 0 0 0 0 0 0 0 0 0 0		0 0 0 0 0 0 0 0 0	0 0 0 0 0 0	10 10 10 10 10 10 10 10
0 0 0 0 0 0 0 0 0 0 0		0 0 0 0 0 0 0	0 0 0 0 0 0	10 10 10 10 10 10 10 10
0 0 0 0 0 0 0 0 0 0		0 0 0 0 0	0 0 0 0	10 10 10 10 10
0 0 0 0 0		0 0 0 0	0 0 0 0	10 10 10 10 10
0 0 0 0	1	บ บ บ	0 0	10 10 10 10
0 0 0	1	ם מ	Ü	10 10
U U U		U	Ū	10
U U	1	17	11	
Ū		1000		
B. 1000000000		ט ט	U	10 10
U		Ŭ	Ū	10
<u> </u>		<u>ש</u>	a a	10
U		D D	U	10 10
U	1	U	0	10
U	0.00	<u>D</u>	U	10
ŭ		U U	U	10
Ū		U	Ū	10
	AND THE RESERVE OF THE PROPERTY OF THE PROPERT			10
ŭ		Ŭ		10 10
Ū		U	0.73	10
17K. 18E				
1/06/95	01/0	6/95	01/06/95	
	the state of the s	ָ ט	י י י י י י י י י י י י י י י י י י י	U U U U U U U U U U U U U U U U U U U

See Appendix for qualifier definitions Note: Compound detection limit = quantitation limit x dilution factor

1 .

TABLE VO-1.3 3095-0018 GERAGHTY & MILLER EPA TCL VOLATILE ORGANICS

All values are ug/L.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	DUP. 1 0018006 VBLKDC 1.00	MW-7 0018007 VBLKDC 1.00	NW-4 0018008 VBLKDC 1.00	Quant. Limits with no Dilution
Chloromethane Bromomethane Vinyl Chloride Chloroethane	0 0	0 0 0 0	U	10 10 10
Methylene Chloride Acetone Carbon Disulfide 1,1-Dichloroethene	0 0	0 0	0 0 0	10 10 10
1,1-Dichloroethane 1,2-Dichloroethene (total) Chloroform	ט ט ט	0 0 0	0 0 0	10 10 10
1,2-Dichloroethane 2-Butanone 1,1,1-Trichloroethane	0 0	0 0	0 0	10 10 10 10
Carbon Tetrachloride Bromodichloromethane 1,2-Dichloropropane cis-1,3-Dichloropropene	0 0	n n n	0 U	10 10 10
Trichloroethene Dibromochloromethane 1,1,2-Trichloroethane	Ü U	0 0 0	0 0 0	10 10 10 10
Benzene trans-1,3-Dichloropropene Bromoform	0 0	0 0 0	0 0	10 10 10
4-Methyl-2-Pentanone 2-Hexanone Tetrachloroethene 1,1,2,2-Tetrachloroethane	0 0 0	0 0	0 0 0	10 10 10
Toluene Chlorobensene Ethylbensene Styrene	0 0 0	0 0 0 0.5J	0 0 0	10 10 10 10 10
Xylene (total) Date Received Date Extracted Date Analyzed	01/06/95 N/A 01/10/95	9J 01/06/95 N/A 01/10/95	01/06/95 N/A 01/10/95	10

TABLE VO-1.4 3095-0018 GERAGHTY & MILLER EPA TCL VOLATILE ORGANICS

All values are ug/L.

Client Sample I.D. Lab Sample I.D. Method Blank I.D. Dilution Factor	MW-41 0018009 VBLKDC 1.00	FB 010595 0018010 VBLKDC 1.00	TB 010595 0018011 VBLKDC 1.00	Quant. Limits With no Dilution
Chloromethane	ן ס	U	U	10
Bromomethane Vinyl Chloride	ū	U	ū	10
Chloroethane	U U	0	U	10
Methylene Chloride	Ü	ď	ָ ט	10 10
Acetone	ס	Ŭ.	Ŭ	10
Carbon Disulfide 1,1-Dichloroethene	<u>U</u>	U	U	10
1,1-Dichloroethane	U V	<u> </u>	ā	10
1,2-Dichloroethene (total)	Ŭ	Ŭ	U	10 10
Chloroform	Ū	13	Ū	10
1,2-Dichloroethane 2-Butanone	U	Ų	U	10
1,1,1-Trichloroethane	Table Table	- 8	0 0	10
Carbon Tetrachloride	Ū	Ū	Ū	10 10
Bromodichloromethane 1,2-Dichloropropane	ט	U	ם ביי	10
cis-1,3-Dichloropropene	Ü	U	U U	10
Trichloroethene	Ŭ	Ŭ	Ö	10 10
Dibromochloromethane	U	U	ס	10
1,1,2-Trichloroethane Benzene	T T	U U	Ū	10
trans-1,3-Dichloropropene	Ü	Ŭ	t	10 10
Bromoform	U	Ū	Ü	10
4-Nethyl-2-Pentanone 2-Nexanone	Ū	U	Ū	10
Tetrachloroethene	U	U	U	10
1,1,2,2-Tetrachloroethane	Ū.	Ü	D	10 10
Toluene	<u> </u>	Ū	Ū	10
Chlorobensene Ethylbensene	0	Ū	ā	10
Styrene	PERSONAL PROPERTY AND ADMINISTRATION OF THE PROPERTY OF THE PR	U	U	10
Xylene (total)	Ü	ס ס	ט ט	10 10
Date Received	01/06/95	01/06/95	01/05/05	
Date Extracted	N/A	N/A	01/06/95 N/A	
Date Analyzed	01/10/95	01/09/95	01/09/95	

TABLE VO-2.0 3095-0018 GERAGHTY & MILLER VOLATILE TENTATIVELY IDENTIFIED COMPOUNDS

Sample Identification: Method Blank VBLKDC

CAS#	Compound	RT	Estimated Concentration, ug/L
	None detected		
	Sample Identification:	MW-6	
CAS#	Compound	RT	Estimated Concentration, ug/L
	None detected		
	Sample Identification:	MW-1	ž.
CAS#	Compound	RT	Estimated Concentration, ug/L
	None detected		
	Sample Identification:	MW-5	
CAS#	Compound	RT	Estimated Concentration, ug/L
	None detected		
	Sample Identification:	MW-2	
CAS#	Compound	<u>RT</u>	Estimated Concentration, ug/L
	None detected		
	Sample Identification:	MW-3	
CAS#	Compound	RT	Estimated Concentration, ug/L
	None detected		

TABLE VO-2.1 3095-0018 GERAGHTY & MILLER VOLATILE TENTATIVELY IDENTIFIED COMPOUNDS

Sample Identification: DUP 1

	C _p		
CAS#	Compound	RT	Estimated Concentration, ug/L
	None detected		
	Sample Identification:	MW-7	
CAS#	Compound	RT	Estimated Concentration, ug/L
	Unknown C ₃ alkylbenzene Unknown isomer of benzene, 1-ethyl	20. 49 19.86	9J 7J
	Sample Identification:	MW-4	
CAS#	Compound	RT	Estimated Concentration, ug/L
	None detected		
	Sample Identification:	MW-41	
CAS#	Compound	RT	Estimated Concentration, ug/L
	None detected		
	Sample Identification: F	B 010595	
CAS#	Compound	RT	Estimated Concentration, ug/L
	None detected		
See Apper	ndix for qualifier definitions		

TABLE VO-2.2 3095-0018 GERAGHTY & MILLER VOLATILE TENTATIVELY IDENTIFIED COMPOUNDS

Sample Identification: TB 010595

CAS#	Compound	RT	Estimated Concentration, ug/L
	None detected		

TABLE AS-1.0 3095-0018 GERAGHTY & MILLER EPA TAL METALS (Dissolved)

All values are ug/L.

Aluminum Antimony Arsenic Barium Beryllium Cadmium Cadmium Calcium Chromium Chromium Cobalt Copper Cyanide Iron Lead Magnesium Manganese Mercury Nickel Potassium Selenium Selenium Selenium Selenium Cadmium Cadmium Cadmium Calcium Cobalt Copper Cobalt Copper Cobalt Copper Cyanide Cyanid	Client Sample I.D. Lab Sample I.D.	MW-6 0018001	MW-1 0018002	MW-1 D 0018002D	MW-1 S 0018002S
Zinc 114. 47.6 47.1 489.	Antimony Arsenic Barium Beryllium Cadmium Calcium Chromium Cobalt Copper Cyanide Iron Lead Magnesium Manganese Mercury Nickel Potassium Selenium Silver Sodium Thallium	38.0U 1.1B 109.B 1.0U 2.0U 107000 4.7B 6.9B 34.9 NR 7440E 7.9 29200 464. 0.20U 14.6B 4060B 1.0U 3.0U 12100 1.0U 6.7B	38.0U 1.0U 35.5B 1.0U 2.0U 123000 2.0U 3.0U 5.5B NR 15.0UE 23.4 33400 3.4B 0.20U 8.0U 517.U 2.3B 3.0U 21200 1.0U 6.0U	21.4B 38.0U 1.0U 37.3B 1.0U 2.0U 125000 2.0U 3.5B NR 15.0U 24.3 34000 3.3B 0.20U 8.0U 983.B 2.0B 3.0U 21700 1.0U	2030 500. 39.4 1970 44.4 48.3 NR 177. 448. 228. NR 911. 46.6 NR 460. 1.0B 422. NR 12.0 44.1

TABLE AS-1.1 3095-0018 GERAGHTY & MILLER EPA TAL METALS (Dissolved)

All values are ug/L.

	1	·		
ž.	~	/		ν
Client Sample I.D.	MW - 5	MW - 2	MW - 3	DUP. 1
Lab Sample I.D.	0018003	0018004	0018005	0018006
Aluminum Antimony Arsenic Barium Beryllium Cadmium Calcium Chromium Cobalt Copper Cyanide Iron Lead Magnesium Manganese Mercury Nickel Potassium Selenium Silver Sodium Thallium Vanadium Zinc	360.E 38.0U 2.7B 38.6B 1.0U 3.5B 86800 2.0U 3.0U 7.8B NR 716.E 3.0 28900 21.3 0.20U 8.0U 8700 1.0U 3.0U 69500 1.0U 7.2B 80.2	31.6BE 38.0U 1.0U 20.7B 1.0U 2.0U 460000 2.0U 3.0U 6.6B NR 18.2BE 1.0U 51400 650. 0.20U 8.0U 517.U 1.0U 3.0U 41000 1.0UW 6.0U 29.7	17.4BE 38.0U 1.6B 29.6B 1.0U 2.0U 172000 2.0U 3.0U 2.9B NR 1120E 2.2BW 44300 549. 0.20U 8.0U 517.U 1.0U 3.0U 29300 1.0UW 6.0U 38.9	16.9BE 38.0U 1.9B 31.0B 1.0U 2.0U 178000 2.0U 3.0U 2.0U NR 1160E 3.0 45700 567. 0.20U 8.0U 517.U 1.0U 3.0U 3.0U 3.0U 3.0U 40.9

TABLE AS-1.2 3095-0018 GERAGHTY & MILLER EPA TAL METALS (Dissolved)

All values are ug/L.

		T		
Client Sample I.D.	MW-7	MW - 4	MW-41	FB 010595
Lab Sample I.D.	0018007	0018008	0018009	0018010
Aluminum Antimony Arsenic Barium Beryllium Cadmium Calcium Chromium Cobalt Copper Cyanide Iron Lead Magnesium Manganese Mercury Nickel Potassium Selenium Silver Sodium Thallium Vanadium	12.0UE 38.0U 1.0B 25.6B 1.0U 2.0U 231000 2.0U 5.3B 2.0U NR 2340E 3.7 14300 1970 0.20U 8.0U 4080B 1.0U 3.0U 32900 1.0UW 6.0U	34.5BE 38.0U 1.0U 18.4B 1.0U 2.0U 403000 2.0U 3.0U 2.0U NR 32.4BE 2.7BW 23700 1590 0.20U 8.0U 2920B 1.0U 3.0U 36000 1.0UW 6.0U	62100E 58.6B 37.2S 576. 1.0U 3.7B 741000 114. 54.4 197. NR 106000E 145.S 165000 4380 0.24B 132. 28500 1.7BW 3.0U 25900 1.0UW 94.2	57.5BE 38.0U 1.0U 8.0U 1.0U 2.0U 856.B 2.0U 3.0U 2.0U NR 128.E 1.0UW 163.B 7.0B 0.20U 8.0U 517.U 1.0U 3.0U 51.9B 1.0U 6.0U
Zinc	36.6	51.8	377.	9.8B

TABLE AS-1.5 3095-0018 GERAGHTY & MILLER EPA TAL METALS (Total)

All values are ug/L.

Client Sample I.D.	MW-7 /	MW - 4	MW-41	FB 010595
Lab Sample I.D.	0018007	0018008	0018009	0018010
Aluminum	9580E	55800E	51800E	
Antimony	38.0U	38.00		49.2BE
Arsenic	11.1	27.1s	38.0T 27.4S	38.0U
Barium	90.3B	512.	470.	1.00
Beryllium	1.00	1.00	1.00	8.00
Cadmium	2.00	4.6B	2.00	1.00
Calcium	303000	610000	720000	2.0U 709.B
Chromium	15.9	62.3	95.7	2.00
Cobalt	11.4B	47.8B	42.4B	3.00
Copper	19.7B	135.	155.	2.00
Cyanide	10.00	10.00	10.00	10.00
Iron	17200E	95800E	85200E	114.E
Lead	216.	51.0S+	71.0S+	1.00
Magnesium	37200	. 99400	157000	140.B
Manganese	2530	38200	3920	14.0B
Mercury	0.20ប	0.200	0.200	0.200
Nickel	16.1B	106.	108.	8.0U
Potassium	6530	9370	28000	517.U
Selenium	1.00	1.5BW	2.7BW	1.00
Silver	3.00	3.0U	3.0U	3.00
Sodium	33600	38900	25500	153.B
Thallium	1.00	1.0UW	1.00W	1.00
Vanadium	12.1B	88.3	74.2	6.0U
Zinc	52.4	292.	294.	17.4B

APPENDIX H

LEAD MODEL

LEAD MODEL Version 0.99d

IR CONCENTRATION: 0.100 ug Pb/m3 DEFAULT foor AIR Pb Conc: 30.0 percent of outdoor.

.ner AIR Parameters:

Age	Time Outdoors (hr)	Vent. Rate (m3/day)	Lung Abs. (%)
0-1	1.0	2.0	32.0
1-2	2.0	3.0	32.0
2-3	3.0	5.0	32.0
3-4	4.0	5.0	32.0
4-5	4.0	5.0	32.0
5-6	4.0	7.0	32.0
6-7	4.0	7.0	32.0

Diet: alternate diet selected by user as follows:

Nome-grown Fruit: 0.000 ug Pb/g 0.0 %
Nome-grown Vegetables: 0.000 ug Pb/g 0.0 %
Recreational Fish: 1.400 ug Pb/g 5.0 %
Wild Game: 0.000 ug Pb/g 0.0 %

PRINKING WATER Conc: 4.00 ug Pb/L DEFAULT

WATER Consumption: DEFAULT

SOIL & DUST:

\$oil: constant conc.
Dust: constant conc.

Age	Soil (ug Pb/g)	House Dust (ug Pb/g)
0-1	200.0	200.0
1-2	200.0	200.0
2-3	200.0	200.0
3-4	200.0	200.0
4-5	200.0	200.0
5-6	200.0	200.0
6-7	200.0	200.0

Additional Dust Sources: None DEFAULT


AINT Intake: 0.00 ug Pb/day DEFAULT

MATERNAL CONTRIBUTION: Infant Model
Maternal Blood Conc: 2.50 ug Pb/dL

"ALCULATED BLOOD Pb and Pb UPTAKES:

٠	Blood Level	Total Uptake	Soil+Dust Uptake
YEAR	(ug/dL)	(ug/day)	(ug/day)
٠ ٥.5-1:	4.6	8.60	4.62
1-2:	5.5	13.45	7.19
2-3:	5.3	14.31	7.28
3-4:	5.1	14.62	7.38
\$-5:	4.5	13.11	5.58
J-6:	4.1	13.07	5.07
6-7:	3.8	13.49	4.80
. · · · · · · · · · · · · · · · · · · ·			

YEAR	(ug/day)	(ug/day)	(ug/day)	(ug/day)
• • • • • •	********	•••••	********	•••••
1.5-1:	3.59	0.36	0.00	0.02
1-2:	5.33	0.89	0.00	0.03
3:	6.04	0.93	0.00	0.06
3-4:	6.21	0.97	0.00	0.07
4-5:	6.44	1.02	0.00	0.07
5-6:	6.82	1.09	0.00	0.09
6-7:	7.48	1.11	0.00	0.09



LEAD 0.99a

Function f(blood Pb)

Probability Density

LEAD MODEL Version 0.99d

AIR CONCENTRATION: 0.100 ug Pb/m3 DEFAULT

indoor AIR Pb Conc: 30.0 percent of outdoor.

ther AIR Parameters:

Age	Time Outdoors (hr)	Vent. Rate (m3/day)	Lung Abs. (%)
0-1	1.0	2.0	32.0
1-2	2.0	3.0	32.0
2-3	3.0	5.0	32.0
3-4	4.0	5.0	32.0
4-5	4.0	5.0	32.0
5-6	4.0	7.0	32.0
6-7	4.0	7.0	32.0

Diet: alternate diet selected by user as follows:

Home-grown Fruit: 0.000 ug Pb/g 0.0 % Home-grown Vegetables: 0.000 ug Pb/g 0.0 % Recreational fish: 1.400 ug Pb/g 10.0 %

Wild Game:

0.000 ug Pb/g 0.0 %

DRINKING WATER Conc: 4.00 ug Pb/L DEFAULT

WATER Consumption: DEFAULT

SOIL & DUST:

Soil: constant conc.

Dust: constant conc.

	Age	Soil (ug Pb/g)	House Dust	(ug	Pb/g)
N	0-1	200.0	200.0		
r	1-2	200.0	200.0		
	2-3	200.0	200.0		
	3-4	200.0	200.0		
	4-5	200.0	200.0		
	5-6	200.0	200.0		
	6-7	200.0	200.0		

Additional Dust Sources: None DEFAULT

'AINT Intake: 0.00 ug Pb/day DEFAULT

MATERNAL CONTRIBUTION: Infant Model Maternal Blood Conc: 2.50 ug Pb/dL

"ALCULATED BLOOD Pb and Pb UPTAKES:

week	Blood Level	Total Uptake	Soil+Dust Uptake
YEAR	(ug/dL)	(ug/day)	(ug/day)
	*********	**********	*********
0.5-1:	5.1	9.44	4.58
1-2:	6.4	15.81	7.04
2-3:	6.2	16.96	7.13
· 3-4:	6.1	17.51	7.24
4-5:	5.5	16.30	5.48
-6:	5.1	16.45	4.98
6-7:	4.8	17.16	4.72

YEAR	(ug/day)	(ug/day)	(ug/day)	(ug/day)	
•••••		•••••	•••••	•••••	
0.5-1:	4.48	0.36	0.00	0.02	
1-2:	7.86	0.87	0.00	0.03	
3:	8.85	0.92	0.00	0.06	
J-4:	9.25	0.95	0.00	0.07	
4-5:	9.74	1.01	0.00	0.07	
5-6:	10.30	1.07	0.00	0.09	
6-7:	11.25	1.09	0.00	0.09	

